

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

District 1
Schedule of Overhead Sign Structure Repair & Replacement

Location No.:	13	State I.D. No.:	1C099057R332.2				
County:	WILL	Route:	157	M.P.:	332.2	Direction:	NB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	34.50					
Remove and Re-erect Overhead Sign Structure-Cantilever	EACH	1.00					
Repair Concrete Foundation for Overhead Sign Structure Cantile	EACH	1.00					
Overhead Sign Support Grout Repair	EACH	1.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
<i>"Keeping the Expressway Open to Traffic" Special Provision</i>							
<i>All electrical work will be done by using our EMC</i>							

Location No.:	17	State I.D. No.:	1S099055R266.8				
County:	WILL	Route:	155	M.P.:	266.8	Direction:	NB
Description of Work	Unit	Quantity					
Remove and Re-erect Overhead Sign Structure-Span	EACH	1.00					
Overhead Sign Support Grout Repair	EACH	2.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
Furnish and Install Handrail (Aluminum)	FOOT	59.50					
<i>All electrical work will be done by using our EMC</i>							
<i>This work will be done during night time hours using District One</i>							
<i>"Keeping the Expressway Open to Traffic" Special Provision</i>							

Location No.:	21	State I.D. No.:	1S0221055E271.1				
County:	DU PAGE	Route:	155	M.P.:	271.1	Direction:	SB
Description of Work	Unit	Quantity					
Remove and Re-erect Overhead Sign Structure-Span	EACH	1.00					
Repair Concrete Foundation for Overhead Sign Structure Span	EACH	1.00					
Overhead Sign Support Grout Repair	EACH	2.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
Furnish and Install Handrail (Aluminum)	FOOT	65.00					
<i>This work will be done during night time hours using District One</i>							
<i>"Keeping the Expressway Open to Traffic" Special Provision</i>							
<i>All electrical work will be done by using our EMC</i>							

Location No.:	14	State I.D. No.:	1C099057R329.6				
County:	Will	Route:	157	M.P.:	329.6	Direction:	NB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	34.50					
Remove and Re-erect Overhead Sign Structure-Cantilever	EACH	1.00					
Rebuild Concrete Foundation for Overhead Sign Structure Cantile	EACH	1.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
Temporary Informational Signing	SQ FT	45.50					

Location No.:	18	State I.D. No.:	1S0221055R270.7				
County:	DU PAGE	Route:	155	M.P.:	270.7	Direction:	NB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	91					
Structural Steel Support for Overhead Sign Structure Span	EACH	2					
Remove and Re-erect Overhead Sign Structure-Truss	EACH	1					
Furnish and Install Saddle Shim Block	EACH	4					
Furnish and Install Internal Truss Damper	EACH	1					
<i>All electrical work will be done by using our EMC</i>							
<i>This work will be done during night time hours using District One</i>							
<i>"Keeping the Expressway Open to Traffic" Special Provision</i>							

Location No.:	22	State I.D. No.:	1C0221055E272.9				
County:	DU PAGE	Route:	155	M.P.:	272.9	Direction:	SB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	34.50					
Remove and Re-erect Overhead Sign Structure-Cantilever	EACH	1.00					
Repair Concrete Foundation for Overhead Sign Structure Cantile	EACH	1.00					
Overhead Sign Support Grout Repair	EACH	1.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
<i>This work will be done during night time hours using District One</i>							
<i>"Keeping the Expressway Open to Traffic" Special Provision</i>							
<i>All electrical work will be done by using our EMC</i>							

Location No.:	15	State I.D. No.:	1C099057R330.5				
County:	Will	Route:	157	M.P.:	330.5	Direction:	SB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	34.50					
Remove and Re-erect Overhead Sign Structure-Cantilever	EACH	1.00					
Rebuild Concrete Foundation for Overhead Sign Structure	EACH	1.00					
Overhead Sign Support Grout Repair	EACH	1.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
Temporary Informational Signing	SQ FT	45.50					

Location No.:	19	State I.D. No.:	1S099055L269.2				
County:	WILL	Route:	155	M.P.:	269.2	Direction:	SB
Description of Work	Unit	Quantity					
Remove and Re-erect Overhead Sign Structure-Span	EACH	1.00					
Repair Concrete Foundation for Overhead Sign Structure Span	EACH	1.00					
Overhead Sign Support Grout Repair	EACH	2.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
<i>This work will be done during night time hours using District One</i>							
<i>"Keeping the Expressway Open to Traffic" Special Provision</i>							
<i>All electrical work will be done by using our EMC</i>							

Location No.:	23	State I.D. No.:	1S0221055L274.8				
County:	DU PAGE	Route:	155	M.P.:	274.8	Direction:	SB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	52.50					
Remove and Re-erect Overhead Sign Structure-Span	EACH	1.00					
Repair Concrete Foundation for Overhead Sign Structure Span	EACH	1.00					
Overhead Sign Support Grout Repair	EACH	4.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
<i>This work will be done during night time hours using District One</i>							
<i>"Keeping the Expressway Open to Traffic" Special Provision</i>							
<i>All electrical work will be done by using our EMC</i>							

Location No.:	16	State I.D. No.:	1C099057E327.4				
County:	Will	Route:	157	M.P.:	327.4	Direction:	SB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	21.50					
Remove and Re-erect Overhead Sign Structure-Cantilever	EACH	1.00					
Rebuild Concrete Foundation for Overhead Sign Structure	EACH	1.00					
Overhead Sign Support Grout Repair	EACH	1.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
Temporary Informational Signing	SQ FT	93.50					

Location No.:	20	State I.D. No.:	1C0221055E270.8				
County:	DU PAGE	Route:	155	M.P.:	270.8	Direction:	SB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	34.50					
Remove and Re-erect Overhead Sign Structure-Cantilever	EACH	1.00					
Repair Concrete Foundation for Overhead Sign Structure Cantile	EACH	1.00					
Overhead Sign Support Grout Repair	EACH	1.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
<i>This work will be done during night time hours using District One</i>							
<i>"Keeping the Expressway Open to Traffic" Special Provision</i>							
<i>All electrical work will be done by using our EMC</i>							

Location No.:	24	State I.D. No.:	1S0221055E272.9				
County:	DU PAGE	Route:	155	M.P.:	274.9	Direction:	SB
Description of Work	Unit	Quantity					
Overhead Sign Structure Walkway	FOOT	93.00					
Structural Steel Support for Overhead Sign Structure Span	EACH	2.00					
Remove and Re-erect Overhead Sign Structure-Truss	EACH	1.00					
Tighten U-Bolts (at Left Sign)	EACH	2.00					
Furnish and Install Saddle Shim Block	EACH	4.00					
Furnish and Install Internal Truss Damper	EACH	1.00					
<i>This work will be done during night time hours using District One</i>							
<i>"Keeping the Expressway Open to Traffic" Special Provision</i>							
<i>All electrical work will be done by using our EMC</i>							

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
		CHECKED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Various	D-1 OVD SIN STR REPL 12-02	VARIOUS	39	4
				CONTRACT NO. 46175
ILLINOIS FED. AID PROJECT				