



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 19, 2011

SUBJECT: Various Routes
Section D-2 OVD SIN STR REPL 12-03
Various Counties
Contract No. 46176
Item No. 57, August 5, 2011 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added page 58 to the Special Provisions.
4. Revised sheets 2 & 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; D. Carl Puzey;
Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 46176

State Job # - C-60-003-12
 PPS NBR - 0-99988-0000
 County Name - VARIOUS- -
 Code - 0 - -
 District - 0 - -
 Section Number - D-2 OVD SIN STR REPL 12-03

Project Number

Route
 VARIOUS

* REVISED: JULY 18, 2011

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|---------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| X0325265 | REMOVE ELEC SERVICE | EACH | 8.000 | | | | |
| *ADD X0326338 | SIGN STRUCTURE | L SUM | 1.000 | | | | |
| X7010216 | TRAF CONT & PROT SPL | L SUM | 1.000 | | | | |
| X7200075 | REM & REIN SIGN PANEL | SQ FT | 1,450.000 | | | | |
| X7200095 | F & E SIGN PANEL | SQ FT | 1,221.000 | | | | |
| X7330066 | REP HDRL LOC PIN CON | EACH | 12.000 | | | | |
| X7330104 | REM & REINSTL WALKWAY | FOOT | 54.500 | | | | |
| 63000003 | SPBGR TY A 9FT POSTS | FOOT | 75.000 | | | | |
| 63301210 | REM RE-E SPBGR TY A | FOOT | 150.000 | | | | |
| 63301990 | REM RE-E T B TERM T1 | EACH | 6.000 | | | | |
| 63302000 | REM RE-E T B TERM T2 | EACH | 6.000 | | | | |
| 67100100 | MOBILIZATION | L SUM | 1.000 | | | | |
| * 73300200 | OVHD SIN STR-SPAN T2A | FOOT | 572.000 | | | | |
| 73301810 | OSS WALKWAY TY A | FOOT | 313.000 | | | | |
| 73302170 | OSS CANT 2CA 3-0X5-6 | FOOT | 58.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 46176

State Job # - C-60-003-12
 PPS NBR - 0-99988-0000
 County Name - VARIOUS--
 Code - 0 - -
 District - 0 - -
 Section Number - D-2 OVD SIN STR REPL 12-03

Project Number

Route

VARIOUS

* REVISED: JULY 18, 2011

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|----------------|-----------------------|--------------------|----------|---|------------|---|-------------|
| 73400200 | DRILL SHAFT CONC FDN | CU YD | 136.100 | | | | |
| 73600100 | REMOV OH SIN STR-SPAN | EACH | 6.000 | | | | |
| 73600200 | REMOV OH SIN STR-CANT | EACH | 2.000 | | | | |
| 73700300 | REM CONC FDN-OVHD | EACH | 12.000 | | | | |

SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE)..... 44
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 48
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE) 48
UTILITY COORDINATION AND CONFLICTS (BDE)..... 49
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 54
SIGN STRUCTURE 58

Revised 07/19/2011

SIGN STRUCTURE

This work shall consist of replacing the existing sign structure span, at location 2-04, with a new Type II-A (4'-6" X 5'-3") truss. The new truss shall be installed on the existing end supports.

The Contractor shall be responsible for field verifying the existing dimensions for the span length to assure the proper fit for the replacement truss on the existing end supports.

This work shall include all labor, material, and equipment necessary for proper execution and completion of the work as shown on the plans and as herein specified. It shall include all work not specifically included in the contract documents which is reasonably and properly inferable and necessary for proper completion of the improvement.

Materials shall meet the requirements of the sign structure detail sheets shown in the contract, conforming to the dimensions shown on the details included in the contract, and the applicable requirements of Section 1094.

The replacement overhead sign structure-span shall include the fabrication and installation of truss grating, to facilitate inspections, the entire length of the span conforming to the details shown in the contract.

The cost of fabricating and installing the truss grating and the truss damper shall be included in the cost of fabricating and installing the replacement overhead sign structure-span.

This work shall be done in accordance with Section 733, including providing all necessary mounting hardware and as specified herein.

Shop drawings for the new structure will be provided by the Contractor and approved in writing before any new materials are ordered or fabrication is begun.

Before starting work, the Contractor shall provide an erection plan to the Engineer detailing the method of erection proposed to be followed and the amount and type of equipment proposed to be used. The plan shall be subject to the approval of the Engineer. The approval of the Engineer shall not be considered as relieving the Contractor of the responsibility for the safety of the Contractor's method or equipment or from carrying out the work in full.

Traffic control and protection shall be included under this pay item. It shall be understood that the freeway will be closed a maximum of **15 minutes** to remove and re-erect the sign structure and the time of the week allowed for closure will be as directed by the Engineer.

Basis of Payment: This work will be paid for at the contract unit price per foot for SIGN STRUCTURE which price shall include providing all necessary traffic control.

Added 07/19/2011