

# SCHEDULE OF QUANTITIES

Location No.:	2-01	State I.D. No.:	2S081N000L000.0		
County:	ROCK ISLAND	Route:	7TH AVE	M.P.:	0
Direction:	WB				
Description of Work	Unit	Quantity			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.00			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00			
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	66.00			
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A (4'-6" X 5'-3")	FOOT	118.00			
FURNISH AND ERECT SIGN PANEL	SQ FT	315.00			
REMOVE ELECTRIC SERVICE	EACH	1.00			
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00			
<i>The new foundations will be built in line with the existing footings.</i>					
<i>Center the new sign structure 25 feet east of the center of the existing structure.</i>					
SIGN # 46					

Location No.:	2-03	State I.D. No.:	2S081I080L003.8		
County:	ROCK ISLAND	Route:	I-80	M.P.:	3.8
Direction:	WB				
Description of Work	Unit	Quantity			
REMOVE AND RE-ERECT SPGR, TYPE A	FOOT	75.00			
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2.00			
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.00			
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	110.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	25.00			
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00			
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	54.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	538.00			
REMOVE ELECTRIC SERVICE	EACH	1.00			
<i>Locate the new structure 25 feet east of the existing structure.</i>					
<i>Drilled shafts in the median shall be located halfway between the outside edges of the passing lanes.</i>					
SIGN # 100					

Location No.:	2-05	State I.D. No.:	2S098I088L036.4		
County:	WHITESIDE	Route:	I-88	M.P.:	36.4
Direction:	WB				
Description of Work	Unit	Quantity			
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A (4'-6" X 5'-3")	FOOT	120.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	25.00			
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00			
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	55.00			
FURNISH AND ERECT SIGN PANEL	SQ FT	288.00			
REMOVE ELECTRIC SERVICE	EACH	1.00			
<i>Locate the new structure 25 feet east of the existing structure.</i>					
SIGN # 131					

Location No.:	2-07	State I.D. No.:	2C101S251L009.6		
County:	WINNEBAGO	Route:	IL 251	M.P.:	9.6
Direction:	SB				
Description of Work	Unit	Quantity			
OVERHEAD SIGN STRUCTURE-CANTILEVER TYPE II-C-A	FOOT	28.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	6.90			
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00			
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	18.00			
FURNISH AND ERECT SIGN PANEL	SQ FT	124.00			
REMOVE ELECTRIC SERVICE	EACH	1.00			
<i>Locate the new structure 15 feet north of the existing structure.</i>					
<i>Build the new foundation with the same pavement offset as the old.</i>					
SIGN # 167					

Location No.:	2-02	State I.D. No.:	2S081I080R003.2		
County:	ROCK ISLAND	Route:	I-80	M.P.:	3.2
Direction:	EB				
Description of Work	Unit	Quantity			
REMOVE AND RE-ERECT SPGR, TYPE A	FOOT	75.00			
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2.00			
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.00			
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	110.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	25.00			
REMOVE OVERHEAD SIGN STRUTURE	EACH	1.00			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00			
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	48.00			
REMOVE ELECTRIC SERVICE	EACH	1.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	478.00			
<i>Locate the new structure 25 feet west of the existing structure.</i>					
<i>Drilled shafts in the median shall be located halfway between the outside edges of the passing lanes.</i>					
SIGN # 97					

Location No.:	2-04	State I.D. No.:	2S081I088R015.8		
County:	ROCK ISLAND	Route:	I-88	M.P.:	15.6
Direction:	EB				
Description of Work	Unit	Quantity			
SIGN STRUCTURE	L SUM	1.00			
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00			
REMOVE AND REINSTALL WALKWAY	FOOT	54.50			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12.00			
REMOVE ELECTRIC SERVICE	EACH	1.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	434.00			
<i>Locate the new structure 25 feet west of the existing structure.</i>					
<i>Drilled shafts in the median shall be located halfway between the outside edges of the passing lanes.</i>					
SIGN # 102					

Location No.:	2-06	State I.D. No.:	2S081I280R010.8		
County:	ROCK ISLAND	Route:	I-280	M.P.:	10.8
Direction:	EB				
Description of Work	Unit	Quantity			
STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	75.00			
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2.00			
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.00			
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	114.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	24.60			
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00			
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	53.00			
FURNISH AND ERECT SIGN PANEL	SQ FT	419.00			
REMOVE ELECTRIC SERVICE	EACH	1.00			
<i>Locate the new structure 25 feet west of the existing structure.</i>					
<i>Drilled shafts in the median shall be located halfway between the outside edges of the passing lanes.</i>					
SIGN # 135					

Location No.:	2-08	State I.D. No.:	2C101S251R009.6		
County:	WINNEBAGO	Route:	IL 251	M.P.:	9.6
Direction:	NB				
Description of Work	Unit	Quantity			
OVERHEAD SIGN STRUCTURE-CANTILEVER TYPE II-C-A	FOOT	30.00			
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	8.60			
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00			
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	19.00			
FURNISH AND ERECT SIGN PANEL	SQ FT	75.00			
REMOVE ELECTRIC SERVICE	EACH	1.00			
<i>Locate the new structure 15 feet south of the existing structure.</i>					
<i>Build the new foundation with the same pavement offset as the old.</i>					
SIGN # 168					

▲ Rev. 7-18-11