

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	SIGN 46	SIGN 97	SIGN 100	SIGN 102	SIGN 131	SIGN 135	SIGN 167	SIGN 168
* 6300003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	75						75		
* 63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL TYPE A	FOOT	150		75	75					
* 63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	6		2	2			2		
* 63302000	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 2	EACH	6		2	2			2		
67100100	MOBILIZATION	L SUM	1	0.125	0.125	0.125	0.125	0.125	0.125	0.125	0.125
73300200	OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A (4'-6" X 5'-3')	FOOT	572	118	110	110		120	114		
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	313	66	48	54		55	53	18	19
73302170	OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A (36" X 5'-6").	FOOT	58							28	30
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	136.1	21	25	25		25	24.6	6.9	8.6
73600100	REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	6	1	1	1	1	1	1		
73600200	REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	2							1	1
73700300	REMOVE CONCRETE FOUNDATIONS-OVERHEAD	EACH	12	2	2	2		2	2	1	1
X0325265	REMOVE ELECTRIC SERVICE	EACH	8	1	1	1	1	1	1	1	1
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.125	0.125	0.125	0.125	0.125	0.125	0.125	0.125
X7200075	REMOVE AND RE-INSTALL SIGN PANEL	SQ FT	1450		478	538	434				
X7200095	FURNISH AND ERECT SIGN PANEL	SQ FT	1221	315				288	419	124	75
X7330066	REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12				12				
X7330104	REMOVE AND REINSTALL WALKWAY	FOOT	54.5				54.5				
X0326338	SIGN STRUCTURE	L SUM	1				1				

* Specialty Items
Rev. 7-18-11

SCHEDULE OF QUANTITIES

Location No.:	2-01	State I.D. No.:	2S081N000L000.0				
County:	ROCK ISLAND	Route:	7TH AVE	M.P.:	0	Direction:	WB
Description of Work	Unit	Quantity					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	66.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A (4'-6" X 5'-3")	FOOT	118.00					
FURNISH AND ERECT SIGN PANEL	SQ FT	315.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
<i>The new foundations will be built in line with the existing footings.</i>							
<i>Center the new sign structure 25 feet east of the center of the existing structure.</i>							
SIGN # 46							

Location No.:	2-03	State I.D. No.:	2S081080L003.8				
County:	ROCK ISLAND	Route:	I-80	M.P.:	3.8	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE AND RE-ERECT SPGR, TYPE A	FOOT	75.00					
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2.00					
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	110.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	25.00					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	54.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	538.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
<i>Locate the new structure 25 feet east of the existing structure.</i>							
<i>Drilled shafts in the median shall be located halfway between the outside edges of the passing lanes.</i>							
SIGN # 100							

Location No.:	2-05	State I.D. No.:	2S098I088L036.4				
County:	WHITESIDE	Route:	I-88	M.P.:	36.4	Direction:	WB
Description of Work	Unit	Quantity					
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A (4'-6" X 5'-3")	FOOT	120.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	25.00					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	55.00					
FURNISH AND ERECT SIGN PANEL	SQ FT	288.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
<i>Locate the new structure 25 feet east of the existing structure.</i>							
SIGN # 131							

Location No.:	2-07	State I.D. No.:	2C101S251L009.6				
County:	WINNEBAGO	Route:	IL 251	M.P.:	9.6	Direction:	SB
Description of Work	Unit	Quantity					
OVERHEAD SIGN STRUCTURE-CANTILEVER TYPE II-C-A	FOOT	28.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	6.90					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	18.00					
FURNISH AND ERECT SIGN PANEL	SQ FT	124.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
<i>Locate the new structure 15 feet north of the existing structure.</i>							
<i>Build the new foundation with the same pavement offset as the old.</i>							
SIGN # 167							

Location No.:	2-02	State I.D. No.:	2S081080R003.2				
County:	ROCK ISLAND	Route:	I-80	M.P.:	3.2	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE AND RE-ERECT SPGR, TYPE A	FOOT	75.00					
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2.00					
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	110.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	25.00					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	48.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	478.00					
<i>Locate the new structure 25 feet west of the existing structure.</i>							
<i>Drilled shafts in the median shall be located halfway between the outside edges of the passing lanes.</i>							
SIGN # 97							

Location No.:	2-04	State I.D. No.:	2S081088R015.8				
County:	ROCK ISLAND	Route:	I-88	M.P.:	15.6	Direction:	EB
Description of Work	Unit	Quantity					
SIGN STRUCTURE	L SUM	1.00					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
REMOVE AND REINSTALL WALKWAY	FOOT	54.50					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	434.00					
<i>Locate the new structure 25 feet west of the existing structure.</i>							
<i>Drilled shafts in the median shall be located halfway between the outside edges of the passing lanes.</i>							
SIGN # 102							

Location No.:	2-06	State I.D. No.:	2S081280R010.8				
County:	ROCK ISLAND	Route:	I-280	M.P.:	10.8	Direction:	EB
Description of Work	Unit	Quantity					
STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	75.00					
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2.00					
REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	114.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	24.60					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	53.00					
FURNISH AND ERECT SIGN PANEL	SQ FT	419.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
<i>Locate the new structure 25 feet west of the existing structure.</i>							
<i>Drilled shafts in the median shall be located halfway between the outside edges of the passing lanes.</i>							
SIGN # 135							

Location No.:	2-08	State I.D. No.:	2C101S251R009.6				
County:	WINNEBAGO	Route:	IL 251	M.P.:	9.6	Direction:	NB
Description of Work	Unit	Quantity					
OVERHEAD SIGN STRUCTURE-CANTILEVER TYPE II-C-A	FOOT	30.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	8.60					
REMOVE OVERHEAD SIGN STRUCTURE	EACH	1.00					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	19.00					
FURNISH AND ERECT SIGN PANEL	SQ FT	75.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
<i>Locate the new structure 15 feet south of the existing structure.</i>							
<i>Build the new foundation with the same pavement offset as the old.</i>							
SIGN # 168							