

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004	0021	0021	0021		0021	0031	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004	0021	0021	0021		0021	0031
				ROADWAY	LIGHTING	TRAFFIC SIGNAL	SIDEWALK		PRE-EMPTION EQUIPMENT	LAND-SCAPING					ROADWAY	LIGHTING	TRAFFIC SIGNAL	SIDEWALK		PRE-EMPTION EQUIPMENT	LAND-SCAPING
				(80/20)	(80/20)	(80/10/10)	(80/20)		(100% CITY)	(80/20)					(80/20)	(80/20)	(80/10/10)	(80/20)		(100% CITY)	(80/20)
M7030210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	17	17							M8360100	LIGHT POLE FOUNDATION, 600MM DIAMETER	METER	30		30					
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	11145	11145							M8380095	BREAKAWAY DEVICE, TRANSFORMER BASE, 381MM BOLT CIRCLE	EACH	10		10					
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	225	225							M8731210	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	METER	320						320	
M7030260	TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	50	50							M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	METER	470						470	
M7030280	TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	32	32							M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	METER	237						237	
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	1147	1147							M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	METER	524						524	
M7200100	SIGN PANEL - TYPE 1	SQ M	1.26						1.26		M8731300	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	METER	561						561	
M7200200	SIGN PANEL - TYPE 2	SQ M	2.78						2.78		M8731800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	METER	50						50	
M7800100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	17	17							M8750510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 4.85 METER	EACH	3						3	
M7800105	THERMOPLASTIC PAVEMENT MARKING - LINE 100MM	METER	2196	2196							M8770030	STEEL MAST ARM ASSEMBLY AND POLE, 7.31 METER	EACH	1						1	
M7800115	THERMOPLASTIC PAVEMENT MARKING - LINE 150MM	METER	225	225							M8770045	STEEL MAST ARM ASSEMBLY AND POLE, 9.14 METER	EACH	1						1	
M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	METER	50	50							M8770055	STEEL MAST ARM ASSEMBLY AND POLE, 10.36 METER	EACH	1						1	
M7800140	THERMOPLASTIC PAVEMENT MARKING - LINE 600MM	METER	58	58							M8770075	STEEL MAST ARM ASSEMBLY AND POLE, 12.80 METER	EACH	1						1	
M8100060	CONDUIT IN TRENCH, 50MM DIA., GALVANIZED STEEL	METER	200						200		M8770755	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 10.97 METER	EACH	1						1	
M8100070	CONDUIT IN TRENCH, 65MM DIA., GALVANIZED STEEL	METER	22						22		M8770760	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 11.58 METER	EACH	1						1	
M8100100	CONDUIT IN TRENCH, 100MM DIA., GALVANIZED STEEL	METER	3						3		M8770770	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 12.80 METER	EACH	2						2	
M8101050	CONDUIT PUSHED, 50MM DIA., GALVANIZED STEEL	METER	81						81		M8780100	CONCRETE FOUNDATION, TYPE A	METER	5						5	
M8101070	CONDUIT PUSHED, 75MM DIA., GALVANIZED STEEL	METER	100			100					M8780150	CONCRETE FOUNDATION, TYPE C	METER	1.2						1.2	
M8101090	CONDUIT PUSHED, 100MM DIA., GALVANIZED STEEL	METER	85						85		M8780200	CONCRETE FOUNDATION, TYPE D	METER	12						12	
M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	195						195		M8780400	CONCRETE FOUNDATION, TYPE E 750MM DIAMETER	METER	19						19	
M8170060	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	METER	50			50					MX032057	STORM SEWER REMOVAL	METER	9						9	
M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	535			340			195		MX032178	TEMPORARY INFORMATION SIGNING	SQ M	13.8						13.8	
M8300820	LIGHT POLE, ALUMINUM, 10.5M M.H., 3.0M MAST ARM	EACH	10			10															

⚠ *Specialty Items

⚠ Rev. 7-26-11

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL. 50 AT COURT STREET

5/7/2011