

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FED/ST	FED/ST	FED/ST	FED/ST	CITY	FED/ST	
				ROADWAY	LIGHTING	TRAFFIC SIGNAL	SIDEWALK	PRE-EMPTION EQUIPMENT	LAND-SCAPING	
				(80/20)	(80/20)	(80/10/10)	(80/20)		(100% CITY)	(80/20)
M7030210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	17	17						
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	11145	11145						
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	225	225						
M7030260	TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	50	50						
M7030280	TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	32	32						
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	1147	1147						
M7200100	SIGN PANEL - TYPE 1	SQ M	1.26						1.26	
M7200200	SIGN PANEL - TYPE 2	SQ M	2.78						2.78	
M7800100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	17	17						
M7800105	THERMOPLASTIC PAVEMENT MARKING - LINE 100MM	METER	2196	2196						
M7800115	THERMOPLASTIC PAVEMENT MARKING - LINE 150MM	METER	225	225						
M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	METER	50	50						
M7800140	THERMOPLASTIC PAVEMENT MARKING - LINE 600MM	METER	58	58						
M8100060	CONDUIT IN TRENCH, 50MM DIA., GALVANIZED STEEL	METER	200						200	
M8100070	CONDUIT IN TRENCH, 65MM DIA., GALVANIZED STEEL	METER	22						22	
M8100100	CONDUIT IN TRENCH, 100MM DIA., GALVANIZED STEEL	METER	3						3	
M8101050	CONDUIT PUSHED, 50MM DIA., GALVANIZED STEEL	METER	81						81	
M8101070	CONDUIT PUSHED, 75MM DIA., GALVANIZED STEEL	METER	100				100			
M8101090	CONDUIT PUSHED, 100MM DIA., GALVANIZED STEEL	METER	85						85	
M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	195						195	
M8170060	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	METER	50			50				
M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	535			340			195	
M8300820	LIGHT POLE, ALUMINUM, 10.5M M.H., 3.0M MAST ARM	EACH	10			10				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FED/ST	FED/ST	FED/ST	FED/ST	CITY	FED/ST	
				ROADWAY	LIGHTING	TRAFFIC SIGNAL	SIDEWALK	PRE-EMPTION EQUIPMENT	LAND-SCAPING	
				(80/20)	(80/20)	(80/10/10)	(80/20)		(100% CITY)	(80/20)
M8360100	LIGHT POLE FOUNDATION, 600MM DIAMETER	METER	30			30				
M8380095	BREAKAWAY DEVICE, TRANSFORMER BASE, 381MM BOLT CIRCLE	EACH	10			10				
M8731210	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	METER	320						320	
M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	METER	470						470	
M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	METER	237						237	
M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	METER	524						524	
M8731300	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	METER	561						561	
M8731800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	METER	50						50	
M8750510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 4.85 METER	EACH	3						3	
M8770030	STEEL MAST ARM ASSEMBLY AND POLE, 7.31 METER	EACH	1						1	
M8770045	STEEL MAST ARM ASSEMBLY AND POLE, 9.14 METER	EACH	1						1	
M8770055	STEEL MAST ARM ASSEMBLY AND POLE, 10.36 METER	EACH	1						1	
M8770075	STEEL MAST ARM ASSEMBLY AND POLE, 12.80 METER	EACH	1						1	
M8770755	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 10.97 METER	EACH	1						1	
M8770760	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 11.58 METER	EACH	1						1	
M8770770	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 12.80 METER	EACH	2						2	
M8780100	CONCRETE FOUNDATION, TYPE A	METER	5						5	
M8780150	CONCRETE FOUNDATION, TYPE C	METER	1.2						1.2	
M8780200	CONCRETE FOUNDATION, TYPE D	METER	12						12	
M8780400	CONCRETE FOUNDATION, TYPE E 750MM DIAMETER	METER	19						19	
MX032057	STORM SEWER REMOVAL	METER	9						9	
MX032178	TEMPORARY INFORMATION SIGNING	SQ M	13.8						13.8	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL. 50 AT COURT STREET

5/7/2011 10:42:11 AM C:\Users\jrb\Documents\cib-01882\FPI02397-sh-1-1\06.dgn