F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	143N	WILL	121	6
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

- - -

CONTRACT NO. - 60445

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004 ROADWAY (80/20)	0021 LIGHTING (80/20)	0021 TRAFFIC SIGNAL (80/10/10)	0021 SIDEWALK (80/20)		0021 PRE-EMPTION EQUIPMENT (100% CITY)	0031 LAND-SCAPING (80/20)
				FED/ST	FED/ST	FD/ST/city	FED/ST		CITY	FED/ST
M8860100	DETECTOR LOOP, TYPE I	METER	261			261				
M8731850	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR NO. 6 1C	METER	323			323				
	~~DRILLING AND SETTING SOLDIER PILES~~	~~CU M~~	~~90~~					~~90~~		
MX873030	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	METER	82			82				
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	10360	10360						
28000510	INLET FILTERS	EACH	37							37
MX030428	STORM SEWER, WATER MAIN TYPE 3 450 mm	METER	24	24						
X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	1			1				
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	2	2						
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	10	10						
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	15	15						
X4023000	TEMPORARY ACCESS (ROAD)	EACH	12	12						
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1			1				
88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	6			6				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1						
Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	37	37						
Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	10		10					
MX816074	UNIT DUCT, 600V, 3-1/C #4 AND 1/C #6 GROUND, (XLP-TYPE RHW) 30 MM DIA., SCHEDULE 40 POLYETHYLENE	METER	440		440					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004 ROADWAY	0021 LIGHTING	0021 TRAFFIC SIGNAL	0021 SIDEWALK		0021 PRE-EMPTION EQUIPMENT	0031 LAND-SCAPING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

IL. 50 AT COURT STREET

PLOT DATE: 5/19/2011

5/19/2011
pdbw_scr1$cwldot1$pwcrdb01$pwcrdb01092419$102371.dgn typicaldgn