

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE				
				0004		0021	0011	0021
				KEDZIE AVE.	I-57	SIGNING	SNO16-1196	LIGHTING
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	95	95				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3766	3766				
44000600	SIDEWALK REMOVAL	SO FT	9006	9006				
44003100	MEDIAN REMOVAL	SO FT	14678	14678				
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	209	209				
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	209	209				
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	105	105				
44201294	CLASS B PATCH - EXPANSION JOINT	FOOT	696	696				
44201296	DEFORMED BARS - EXPANSION JOINT	EACH	696	696				
44201297	DOWEL BARS 1 1/2"	EACH	580	580				
44213200	SAW CUTS	FOOT	2088	2088				
44213204	TIE BARS 3/4"	EACH	135	135				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3660	3660				
45100200	CRACK FILLING	POUND	2211.0	2211.0				
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	841	841				
48203049	HOT-MIX ASPHALT SHOULDERS 13"	SQ YD	324		324			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1				1	
50157300	PROTECTIVE SHIELD	SQ YD	1250				1250	
50200100	STRUCTURE EXCAVATION	CU YD	494				494	
50300225	CONCRETE STRUCTURES	CU YD	280.9				280.9	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	916.6				916.6	
50300260	BRIDGE DECK GROOVING	SQ YD	1924				1924	
50300280	CONCRETE ENCASEMENT	CU YD	13.2				13.2	
50300300	PROTECTIVE COAT	SO YD	2880				2880	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1				1	
50500505	STUD SHEAR CONNECTORS	EACH	7328				7328	
50800105	REINFORCEMENT BARS	POUND	791		791			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	252450				252450	
50800515	BAR SPLICERS	EACH	2536				2536	
50901730	BRIDGE FENCE RAILING	FOOT	614				614	
51100100	SLOPE WALL 4 INCH	SQ YD	691				691	
51201800	FURNISHING STEEL PILES HP14X73	FOOT	2439				2439	
51202305	DRIVING PILES	FOOT	2439				2439	
51203800	TEST PILE STEEL HP14X73	EACH	3				3	
51204650	PILE SHOES	EACH	62				62	
51500100	NAME PLATES	EACH	1				1	
52100520	ANCHOR BOLTS, 1"	EACH	32				32	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	32				32	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	361	361				
55100500	STORM SEWER REMOVAL 12"	FOOT	569	569				

REV. 7-28-11

TYLIN INTERNATIONAL	USER NAME = #USER#	DESIGNED - EMK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	KEDZIE AVENUE PROJECT SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = #SCALE#	DRAWN - EMK	REVISED -			57	1313.1B-1	COOK	162	6
	PLOT DATE = 5/4/2011	CHECKED - SES	REVISED -			CONTRACT NO. 60K14				
DATE - 5/5/2011				SCALE: NTS	SHEET NO. 2 OF 5 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		