

SPECIALTY ITEM	CODE NO.	ITEM NAME	URBAN UNIT	TOTAL QUANTITY	I	II	III	IV	V	VI
					100% STATE 0004	100% STATE 0014	100% STATE 0040	100% STATE 0021	100% ELGIN 0021	80% STATE 20% ELGIN 0021
	28100107	STONE RIPRAP, CLASS A4	SQ YD	62	62					
	31101800	SUBBASE GRANULAR MATERIAL, TYPE B 10"	SQ YD	111	111					
	31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT 4 1/2"	SQ YD	1666	1666					
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	1578	1578					
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	24					
	40600895	CONSTRUCTING TEST STRIP	EACH	4	4					
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	88	88					
	40600990	TEMPORARY RAMP	SQ YD	65	65					
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	193	193					
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	415	415					
	40701876	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 3/4"	SQ YD	9781	9781					
	42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	1295	1295					
	42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	592	592					
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	483	483					
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	11087	3944					7143
	42400800	DETECTABLE WARNINGS	SQ FT	83	83					
	44000100	PAVEMENT REMOVAL	SQ YD	19272	19272					
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2976	2976					
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	891	891					
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3312	3312					
	44000300	CURB REMOVAL	FOOT	516	516					
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4537	4537					
	44000600	SIDEWALK REMOVAL	SQ FT	2734	2734					
	44001980	CONCRETE BARRIER REMOVAL	FOOT	1659	1659					
	44003100	MEDIAN REMOVAL	SQ FT	219	219					
	44004000	PAVED DITCH REMOVAL	FOOT	640	640					

LEGEND

- I - ROADWAY
- II - BRIDGE
- III - RETAINING WALLS
- IV - TRAFFIC SIGNALS, LIGHTING, SIDEWALK REPLACEMENT
- V - CITY OF ELGIN EVP AND WELD RD WATER MAIN
- VI - NEW CITY ELGIN SIDEWALK
- * - SPECIALTY ITEM

..\D:\60K\98-BORDER\01.DGN ..\D:\60K\98-S000\01.DGN ..\D:\60K\98-S000\01.DGN ..\D:\60K\98-S000\01.DGN ..\D:\60K\98-S000\01.DGN
 5-18-2011 10:34:02 \\F:\0244\MM\VAULT_ID_TRANS_07\2202\21379-001\CIVIL\ACAD\60K\98\SHEET\01\60K\98-SHT-S000\02.DGN

FILE NAME = *FILEL*	USER NAME = *USER*	DESIGNED - MH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION FAP ROUTE 345 / US ROUTE 20	SUMMARY OF QUANTITIES - II				F.A.P. RTE. 345	SECTION BR-HB-2-BY-1	COUNTY KANE	TOTAL SHEETS 434	SHEET NO. 5
	PLOT SCALE = *SCALE*	CHECKED - DDH	DATE - 05/18/11		REVISED -	SCALE: N.T.S.	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	[ILLINOIS] FED. AID PROJECT	CONTRACT NO. 60K90		



Rev