TREE REMOVAL (6 TO 15 UNITS DIAMETER) — TOTAL 251 UNIT

LOCATION	STATION	OFFSET	SUBTOTALS
US 20	80+77.53	113.5' LT	15
US 20	88+51.32	112.8' LT	13
US 20	93+09.80	90.7' RT	14
US 20	93+19.40	100.3' RT	13
US 20	100+70.00	110.6' RT	9
US 20	109+77.60	99.2' RT	12
US 20	109+91.90	92.2' RT	10
US 20	111+53.93	84.3' RT	8
US 20	138+96.40	68.9' RT	6
US 20	139+14.60	69.6' RT	8
US 20	139+50.80	68.7' RT	8
US 20	142+46.40	65.8' RT	13
US 20	148+25.84	71.6' RT	12
US 20	148+42.24	71.2' RT	12
US 20	148+50.90	72.6' RT	8
US 20	148+69.65	67.6' RT	8
McLEAN BLVD.	62+84.24	45.8' LT	6
McLEAN BLVD.	63+28.61	46.3' LT	14
FLEETWOOD DR.	305+08.20	39.1' LT	8
FLEETWOOD DR.	305+66.00	38.8' LT	6
FLEETWOOD DR.	306+35.90	34.3' RT	8
FLEETWOOD DR.	306+87.50	35.4' RT	8
FLEETWOOD DR.	307+39.30	31.1' RT	10
FLEETWOOD DR.	308+16.30	35.4' RT	10
FLEETWOOD DR.	308+63.30	34.0' RT	12

TREE REMOVAL (OVER 15 UNITS DIAMETER) — TOTAL 612 UNIT

LOCATION	STATION	OFFSET	SUBTOTALS
US 20	76+46.55	102.0' LT	22
US 20	77+39.90	118.8' LT	19
US 20	78+44.15	100.9' LT	16
US 20	79+92.88	97.9' LT	21
US 20	81+58.22	103.4' LT	21
US 20	82+38.77	106.3' LT	19
US 20	83+45.57	103.8' LT	27
US 20	86+87.07	114.2' LT	18
US 20	92+04.50	139.6' LT	23
US 20	93+09.84	147.5' LT	21
US 20	94+14.40	155.8' LT	21
US 20	97+14.80	98.0' RT	19
US 20	97+28.70	121.5' RT	20
US 20	99+43.98	153.8' RT	17
US 20	99+74.45	129.1' RT	19
US 20	99+89.20	156.8' RT	16
US 20	100+66.20	104.2' RT	18
US 20	101+41.10	116.9' RT	22
US 20	101+92.60	103.5' RT	28
US 20	105+39.50	131.0' RT	23
US 20	105+82.60	120.6' RT	26
US 20	109+63.10	97.8' RT	16
US 20	110+05.60	97.2' RT	20
US 20	112+07.50	85.3' RT	22
US 20	149+03.70	69.2' RT	20
US 20	149+39.20	69.6' RT	26
FLEETWOOD DR.	307+50.50	36.8' LT	16
FLEETWOOD DR.	308+64.10	36.9' LT	16
FLEETWOOD DR.	309+19.58	36.4' LT	20
RAMP D	03+44.36	31.9' RT	20

TEMPORARY FENCE — TOTAL 6887 FOOT

LOCATION	FROM STA.	TO STA.	OFFSET EOP to CNTR. of TREE FT.	SUBTOTALS
RAMP D	91+50.80	95+17.26		370
RAMP B	103+91.67	112+50.35		895
WELD RD.	8+00.00	18+80.00		1092
McLEAN BLVD.	62+16.17		9.19	39
FLEETWOOD DR.	302+92.85		14.85	173
FLEETWOOD DR.	303+97.31		11.81	47
FLEETWOOD DR.	304+37.85		9.20	94

CONTINUED NEXT COLUMN

CONTINUED FROM PREVIOUS COLUMN

SHEPARD DR.	21+43.95	11.74	31
SHEPARD DR.	30+28.67	12.31	47
WELD RD	16+87.55	13.80	79
WELD RD	17+37.36	9.79	79
US 20	96+48.54	127.93	126
US 20	96+35.43	156.78	132
US 20	107+95.58	21.67	86
US 20	108+08.29	19.41	47
US 20	108+36.61	17.81	283
US 20	111+53.14	16.65	47
US 20	112+04.37	14.33	94
US 20	112+11.41	17.34	79
US 20	112+19.24	12.05	173
US 20	118+15.88	17.92	79
US 20	118+46.29	18.72	79
US 20	119+15.90	18.74	79
US 20	127+73.92	17.44	79
US 20	127+82.22	17.22	79
US 20	127+94.38	17.10	79
US 20	129+30.05	17.30	79
US 20	130+60.76	16.85	79
US 20	138+87.30	14.10	47
US 20	138+99.55	14.88	47
US 20	139+55.44	13.53	47
US 20	141+08.43	19.73	47
US 20	141+35.72	20.28	63
US 20	141+42.49	22.96	47
US 20	141+51.70	19.33	47
US 20	141+57.35	23.26	47
US 20	141+72.01	21.07	79
US 20	141+81.23	19.20	47
US 20	142+22.16	18.21	63
US 20	142+24.52	19.45	110
US 20	142+72.11	18.46	39
US 20	142+79.51	21.73	39
US 20	142+95.19	18.46	39
US 20	143+63.37	20.72	47
US 20	143+64.92	18.09	47
US 20	144+07.85	16.41	47
US 20	144+30.95	16.30	39
US 20	146+27.58	16.50	39
US 20	146+45.11	17.65	47
US 20	146+59.46	13.61	236
US 20	146+78.34	15.37	39
US 20	149+76.34	20.50	188
US 20	150+94.28	20.92	141
US 20	152+11.58	19.21	157
US 20	152+55.24	17.32	220
US 20	152+95.36	17.07	188

TREE PROTECTION ADJACENT TO CONSTRUCTION AREAS
LOCAL ROAD TREE PROTECTION BEGINS 15 FT. FROM EOP
EXPRESSWAY TREE PROTECTION BEGINS 25 FT FROM EOP

TREE TRUNK PROTECTION — TOTAL 6 EACH

LOCATION	STA.	OFFSET FT.	RT/LT	SUBTOTALS
US 20	94+47.16	166.62	LT	1
US 20	94+80.62	178.62	LT	1
US 20	100+92.46	289.02	LT	1
US 20	101+14.62	293.03	RT	1
US 20	101+85.55	323.32	RT	1
US 20	102+13.24	290.90	RT	1
US 20	108+00.00		RT	
US 20	108+01.00		RT	
US 20	108+02.00		RT	

SUBBASE GRANULAR MATERIAL, TYPE B 10" — TOTAL 111 SQ YD

LOCATION	FROM STA.	TO STA.	SUBTOTALS
US 20	136+00	141+00	111.11

STABILIZED SUBBASE - HOT-MIX ASPHALT 4 1/2" — TOTAL 1666 SQ YD

LOCATION	FROM STA.	TO STA.	SUBTOTALS
FLEETWOOD DR.	307+83.84	309+38.90	1523.93
McLEAN BLVD.	59+73.25	63+19.79	141.83

HOT-MIX ASPHALT BASE COURSE, 8" — TOTAL 1578 SQ YD

LOCATION	CENTERLINE OF DRIVEWAY STA.	OFFSET	SUBTOTALS
WELD RD.	6+19.85	RT	160.20
WELD RD.	7+32.60	RT	138.86
WELD RD.	9+01.52	RT	182.19
WELD RD.	10+22.21	RT	129.07
WELD RD.	11+73.29	RT	123.84
WELD RD.	14+54.79	RT	84.87
WELD RD.	15+65.12	RT	96.93
WELD RD.	16+26.21	RT	54.45
WELD RD.	17+15.89	RT	70.87
SHEPARD DR.	21+94.89	RT	70.97
SHEPARD DR.	29+43.74	LT	35.96
SHEPARD DR.	29+78.63	RT	20.38
FLEETWOOD DR.	302+44.20	RT	65.29
FLEETWOOD DR.	304+24.31	RT	54.05
FLEETWOOD DR.	304+78.53	LT	56.49
FLEETWOOD DR.	306+12.13	RT	5.62
FLEETWOOD DR.	306+20.09	LT	57.78
FLEETWOOD DR.	306+98.36	LT	37.64
FLEETWOOD DR.	307+10.56	RT	13.77
FLEETWOOD DR.	307+77.84	RT	4.28
FLEETWOOD DR.	308+26.07	LT	22.50
MCLEAN BLVD	59+96.64	LT	84.53
MCLEAN BLVD	61+26.66	LT	3.33
MCLEAN BLVD	62+44.82	LT	3.88

* 8" HMA BASE COURSE, used for commercial driveways

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT — TOTAL 61 SQ YD

STA.	OFFSET	SUBTOTALS
US 20		
55+00.00	E.B. RT.	5.00
59+34.80	E.B. LT.	3.00
60+00.00	W.B. LT.	3.00
70+00.00	W.B. RT.	2.50
78+50.00	W.B. LT.	3.25
84+50.00	W.B. LT.	3.25
97+51.42	E.B. LT.	3.50
97+66.93	E.B. RT.	6.00
99+13.00	E.B. RT.	6.50
113+68.00	CENTER	4.00
117+00.00	CENTER	4.00
119+60.00	W.B. RT.	2.00
138+88.38	W.B. RT.	5.00
148+00.00	W.B. RT.	5.00
156+01.87	E.B. RT.	4.50

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 — TOTAL 193 TON

LOCATION	CENTERLINE OF DRIVEWAY STA.	OFFSET	AREA SQ. YDS.	SUBTOTALS
WELD RD.	6+19.85	RT	156.86	17.57
WELD RD.	7+32.60	RT	138.86	15.55
WELD RD.	9+01.52	RT	182.18	20.40
WELD RD.	10+22.21	RT	129.07	14.46
WELD RD.	11+73.29	RT	123.84	13.87
WELD RD.	14+54.79	RT	84.87	9.51
WELD RD.	15+65.12	RT	96.93	10.86
WELD RD.	16+26.21	RT	54.45	6.10
WELD RD.	17+15.89	RT	70.87	7.94
SHEPARD DR.	21+94.89	RT	70.97	7.95
SHEPARD DR.	29+43.74	LT	35.96	4.03
SHEPARD DR.	29+78.63	RT	20.38	2.28
FLEETWOOD DR.	302+44.20	RT	65.29	7.31
FLEETWOOD DR.	304+24.31	RT	54.05	6.05
FLEETWOOD DR.	304+78.53	LT	56.49	6.33
FLEETWOOD DR.	306+12.13	RT	5.62	0.63
FLEETWOOD DR.	306+20.09	LT	57.78	6.47
FLEETWOOD DR.	306+98.36	LT	37.64	4.22
FLEETWOOD DR.	307+10.56	RT	13.77	1.54
FLEETWOOD DR.	307+77.84	RT	4.28	0.48
FLEETWOOD DR.	308+26.07	LT	22.50	2.52
MCLEAN BLVD	59+96.64	LT	84.53	9.47
MCLEAN BLVD	61+26.66	LT	3.33	0.37
MCLEAN BLVD	62+44.82	LT	3.88	0.43

CONTINUED NEXT SHEET