CONTINUED FROM PREVIOUS SHEET

* 2" HMA SURFACE COURSE, MIX "C", N50 used for commercial driveways 112 LB./ SQ. YD./ IN.
* 4" HMA SURFACE COURSE MIX "C", N50 used for parking lots 112LB/SQ. YD./IN

PARKING LOTS

LOCATION				
FLEETWOOD DR. AT SHEPARD DR. N.E. CORNER	STA.		5.53	1.24
FLEETWOOD DR. N. EDGE	306+52.61		6.27	1.40
FLEETWOOD DR. N. EDGE	307+15.86	306+80.18	20.83	4.66
FLEETWOOD DR. N. EDGE	308+42.34	308+09.55	10.51	2.35
FLEETWOOD DR. AT McLEAN BLVD. N.W. CORNER		308+89.73	33.25	7.45

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 — TOTAL 415 TON

LOCATION	DIRECTION	FROM STA.	TO STA.	AREA SQ. YD.	THICKNESS IN	SUBTOTALS
U.S. 20	EB (INSDIE LN)	99+18.36	103+08.81	86.77	3.00	14.58
U.S. 20	EB (SHOULDER.)	99+18.36	103+08.81	378.33	2.38	50.32
U.S. 20	WB (RT.)	148+00.00	156+01.87	890.97	2.00	99.79
SHEPARD DR	FULL WIDTH	22+30.00	28+83.65	2,378.14	1.50	199.76
WELD RD.	FULL WIDTH	5+74.15	8+00.00	601.30	1.50	50.51

HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 3/4" — TOTAL 9781 SQ YD

LOCATION	FROM STA.	TO STA.	SUBTOTALS
WELD RD.	08+00.00	20+00.00	4,133.19
SHEPARD DR.	20+00.00	31+01.59	2,205.48
FLEETWOOD DR.	302+42.10	307+83.86	3,057.07
McLEAN BLVD.	56+85.81	59+73.25	385.44

PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) — TOTAL 1295 SQ YD

LOCATION	STA.	STA.	SUBTOTALS
FLEETWOOD DR.	307+82.90	309+39.03	1,295.49

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH — TOTAL 483 SQ YD

LOCATION	STA.	SUBTOTALS
FLEETWOOD DR.	306+12.13	32.27
FLEETWOOD DR.	306+27.09	38.13
FLEETWOOD DR.	306+98.36	46.06
FLEETWOOD DR.	307+10.56	24.37
FLEETWOOD DR.	307+77.84	43.42
FLEETWOOD DR.	308+26.07	43.37
McLEAN BLVD.	62+44.82	40.09
McLEAN BLVD.	61+26.66	35.60
McLEAN BLVD.	59+96.64	39.26
SHEPARD DR	22+52.67	47.22
SHEPARD DR	28+14.85	58.33
SHEPARD DR	28+91.17	34.44

PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH — TOTAL 11087 SQ FT

LOCATION	SIDE of ROADWAY	FROM STA.	TO STA.	SUBTOTALS
McLEAN BLVD.	W. SIDE	59+62.44	63+59.33	1,964.20
McLEAN BLVD.	W. SIDE	72+40.47	73+06.39	373.76
FLEETWOOD DR.	N. SIDE	304+91.25	308+49.90	1,998.20
FLEETWOOD DR.	S. SIDE	304+45.13	309+06.82	2,880.40
FLEETWOOD DR. @ McLEAN BLVD. N.W. CORNER		308+42.45	309+92.21	1,119.90
CORNER ISLAND AT FLEETWOOD RD. AND McLEAN BLVD. S.W. QUADRANT				191.80
FLEETWOOD DR. @ McLEAN BLVD.				
N.E. CORNER		65+45.30	65+56.50	51.40
S.E. CORNER		64+18.30	64+41.30	111.15
McLEAN BLVD.	W. SIDE	73+84.00	74+00.00	66.00
McLEAN BLVD.	E. SIDE	73+73.00	73+90.00	66.10
FLEETWOOD DR.	N. SIDE	301+08.70	304+66.00	1,303.35
FLEETWOOD DR.	S. SIDE	302+62.90	304+04.00	961.10

PAVEMENT REMOVAL — TOTAL 19272 SQ YD

LOCATION	FROM STA.	TO STA.	SUBTOTALS
WELD RD.	8+00	20+00	4,459.43
WELD RD.	8+72	13+66	1,036.83
FLEETWOOD DR - N. EDGE.	301+13	302+79	148.83
FLEETWOOD DR	302+41	309+62	3,042.10
McLEAN BLVD.	56+85	65+62	1,146.22
U.S. 20 E.B. RT	86+12	92+92	714.09
U.S. 20 E.B. LT	95+61	97+51	42.44
U.S. 20 E.B. RT	103+37	118+67	1,946.80
SHEPARD DR.	20+00	22+30	790.08
SHEPARD DR. EAST EDGE & FLEETWOOD DR. NORTH EDGE	27+84	309+77	1,745.60
SHEPARD DR.	28+84	31+02	789.64
WELD RD.SOUTH EDGE & SHEPARD DR. WEST EDGE	5+74	24+15	3,410.22

HOT-MIX ASPHALT SURFACE REMOVAL, 2" — TOTAL 891 SQ YD

LOCATION	FROM STA	TO STA	SUBTOTALS
US 20 WB (RT)	148+00.00	156+01.87	890.97

DRIVEWAY PAVEMENT REMOVAL — TOTAL 3312 SQ YD

ROADWAY	STA.	OFFSET	SUBTOTALS
WELD RD.	06+20.56	RT	166.87
WELD RD.	07+33.10	RT	165.11
WELD RD.	9+01.38	RT	189.14
WELD RD.	10+22.21	RT	200.61
WELD RD.	11+73.29	RT	169.10
WELD RD.	14+54.79.	RT	114.45
WELD RD.	15+65.12	RT	126.43
WELD RD.	16+26.21	RT	151.57
WELD RD.	17+15.68	RT	182.42
SHEPARD DR.	21+94.89	RT	70.42
SHEPARD DR.	22+58.26	RT	46.20
SHEPARD DR.	28+15.50	LT	57.58
SHEPARD DR.	28+91.17	LT	34.38
SHEPARD DR.	29+43.74	LT	45.26
SHEPARD DR.	29+78.65	RT	22.12
FLEETWOOD DR.	302+44.20	RT	68.40
FLEETWOOD DR.	304+24.31	RT	88.57
FLEETWOOD DR.	304+78.53	LT	92.48
FLEETWOOD DR.	306+12.13	RT	47.15
FLEETWOOD DR.	306+27.09	LT	154.93
FLEETWOOD DR.	306+98.36	LT	91.02
FLEETWOOD DR.	308+26.07	LT	92.44
FLEETWOOD DR.	307+10.56	RT	59.46
FLEETWOOD DR.	307+77.84	RT	100.47
McLEAN BLVD.	62+44.82	LT	59.26
McLEAN BLVD.	61+26.66	LT	37.31
McLEAN BLVD.	59+96.64	LT	111.71
US 20 RAMP D	4+34 TO 6+15	RT	40.97
US 20	151+59.56	RT	96.06
MARATHON GAS STATION PARKING LOT			126.84
ADVANCED ENGINEERING CORP. PARKING LOT			284.20
N.E. CORNER OF FLEETWOOD DR. AND SHEPARD DR.			19.54

CURB REMOVAL — TOTAL 516 FOOT

LOCATION	FROM STA	TO STA	OFFSET	SUBTOTALS
MCLEAN BLVD	60+22.00	60+22.00	LT	2.3
MCLEAN BLVD	61+02.00	61+02.00	LT	4.4
SHEPARD DR	22+34.52	22+45.87	RT	19.47
SHEPARD DR	22+68.32	22+66.31	RT	17.26
SHEPARD DR	29+65.00	29+68.00	RT	11.5
SHEPARD DR	29+89.00	29+92.00	RT	12.6
WELD RD	05+91.70	06+07.94	RT	34.37
WELD RD	06+31.75	06+43.83	RT	32.81
WELD RD	07+11.38	07+20.38	RT	31.56
WELD RD	07+44.81	07+54.19	RT	32.16
WELD RD	8+72.00	8+83.00	RT	33.8
WELD RD	9+20.00	9+30.00	RT	32.4
WELD RD	9+79.00	10+07.00	RT	43.5
WELD RD	10+35.00	10+56.00	RT	42.9
WELD RD	15+97.00	16+14.00	RT	39.5
WELD RD	16+37.00	16+51.00	RT	36.5
WELD RD	16+85.16	17+01.54	RT	42.11
WELD RD	17+32.79	17+39.43	RT	47.05

COMBINATION CURB AND GUTTER REMOVAL — TOTAL 4537 FOOT

LOCATION	FROM STA	TO STA	OFFSET	SUBTOTALS
SHEPARD DR. (W. EDGE FROM WELD RD.)	20+25.60	22+30.00	RT	215.0
SHEPARD DR. (E. EDGE FROM WELD RD.)	20+78.00	22+30.00	LT	205.7
SHEPARD DR. (E. EDGE) TO FLEETWOOD DR.	28+78.63	31+02.60	LT	231.2
SHEPARD DR. (W. EDGE TO FLEETWOOD DR.)	28+83.65	31+04.70	RT	247.9
FLEETWOOD DR. (N. EDGE)	303+30.60	308+75.00	LT	544.8
FLEETWOOD RD. @ McLEAN BLVD. (N.W. CORNER)	308+75.00	310+00.00	LT	162.5
FLEETWOOD DR. (S. EDGE)	302+18.00	308+72.85	RT	657.2
FLEETWOOD RD. @ McLEAN BLVD. (S.W. CORNER)	308+72.85	309+29.00	RT	97.0
McLEAN BLVD. (W. EDGE)	56+85.81	57+05.00	LT	19.3
McLEAN BLVD. (W. EDGE)	59+62.50	63+65.70	LT	405.6
McLEAN BLVD. (E. EDGE)	61+48.80	64+42.09	RT	293.76
McLEAN BLVD. (E. EDGE)	65+45.40	65+56.50	RT	14.0
McLEAN BLVD. (W. EDGE)	72+64.34	72+78.76	LT	14.4
FLEETWOOD DR. @ McLEAN BLVD. (MEDIAN IN S.W. CORNER)			LT	85.5
FLEETWOOD DR. MARATHON GAS PARKING LOT	307+95.40	309+08.00	RT	186.0
FLEETWOOD RD. (N.EDGE)	300+15.25	301+42.26	LT	127.01
FLEETWOOD DRIVEWAY	307+59.00	307+59.00	RT	31.0
FLEETWOOD DRIVEWAY	304+66.00	304+66.00	LT	37.5
FLEETWOOD DRIVEWAY	304+90.00	304+90.00	LT	34.5
SHEPARD DR. (W. EDGE)	22+30.00	24+14.61	RT	191.18
SHEPARD DR. (E. EDGE)	27+83.55	28+83.91	LT	100.36
SHEPARD DRIVEWAY	27+93.60	28+01.35	LT	17.09
SHEPARD DRIVEWAY	28+28.34	28+35.92	LT	17.05
SHEPARD DRIVEWAY	28+80.18	28+82.99	LT	15.97
SHEPARD DRIVEWAY	28+99.09	29+02.45	LT	16.39
SHEPARD DRIVEWAY	29+30.00	29+30.00	LT	19.0
SHEPARD DRIVEWAY	29+57.00	29+57.00	LT	19.0
SHEPARD @ FLEETWOOD N.E. INDUSTRILA PARKING LOT	30+53.00	30+70.00		37.3
MCLEAN DRIVEWAY	62+26.25	62+26.25	LT	8.5
MCLEAN DRIVEWAY	62+62.80	62+62.80	LT	9.1
WELD RD. AT MCLEAN BLVD	10+66.90	13+20.83	LT	267.2
WELD RD. AT MCLEAN BLVD	12+68.12	13+58.30	LT	143.7
SHEPARD DR. Estimate 5% of the total C&G length in resurfacing area				65.365

SIDEWALK REMOVAL — TOTAL 2734 SQ FT

LOCATION		FROM STA.	TO STA.		SUBTOTALS
FLEETWOOD at McLEAN	S.E. CORNER	64+20.06	64+41.18		107.0
FLEETWOOD at McLEAN	N.W. CORNER				760.8
FLEETWOOD at McLEAN	S. W. CORNER				597.9
McLEAN BLVD.		59+62.95	62+27.42		1076.5
McLEAN BLVD.		73+84.00	74+00.00	LT	69.0
McLEAN BLVD.		73+73.00	73+90.00	RT	66.2
McLEAN BLVD. at WELD RD. N.W. CORNER					57.1