

CHAIN LINK FENCE, 4'				TOTAL 1999 FOOT
LOCATION	FROM STA.	TO STA.		SUBTOTALS
RAMP B	99+31.33	112+50.31		1382.6
RAMP D	89+76.38	95+63.92		579.7
MCLEAN BLVD	73+80.00	74+00.60		20.6
MCLEAN BLVD	73+73.50	73+90.00		16.5

TEMPORARY CONCRETE BARRIER (INSTALL ONLY)					TOTAL 13737.5 FOOT
LOCATION	FROM STA.	TO STA.	DIRECTION OFFSET		SUBTOTALS
US 20		94+72.86	97+51.53	MEDIAN	278.67
STAGE I					
US 20		56+01.13	92+30.64	EB (RT)	3,629.51
US 20		91+65.89	97+60.42	EB (RT)	594.53
US 20		99+27.03	108+30.57	EB (RT)	903.54
US 20/ T RAMP B		102+74.30	155+58.54	EB (RT)	5,284.24
STAGE II					
US 20		60+28.50	68+52.93	MEDIAN	824.43
US 20		78+69.00	84+30.92	MEDIAN	561.92
US 20		113+57.83	117+00.00	MEDIAN	342.17
US 20		140+24.00	153+41.34	MEDIAN	1317.34

PARTIAL DEPTH PATCHING (SPECIAL)				TOTAL 1409 SQ YD
FROM STA.	TO STA.	LENGTH FT.		SUBTOTALS
SOUTH EDGE OF U.S. 20 (*ESTIMATED AS 50% OF THE TOTAL LENGTH)				
54+00.00	61+00.00	700.00		77.78
61+00.00	75+00.00	1,400.00		155.56
75+00.00	89+00.00	1,400.00		155.56
89+00.00	97+35.03	835.03		92.78
99+43.71	103+50.00	406.29		45.14
103+50.00	117+00.00	1,350.00		150.00
117+00.00	131+00.00	1,400.00		155.56
131+00.00	145+00.00	1,400.00		155.56
145+00.00	156+01.87	1,101.87		122.43
U.S.20 - WB (RT)				
112+88.06	119+60.00	671.94		298.64

TEMPORARY FENCE (SPECIAL)				TOTAL 1336 FOOT
LOCATION	FROM STA.	TO STA.		SUBTOTALS
WELD RD.	8+00.00	19+60.40		1160.4
WELD RD.	19+60.40	20+43.49		109.1
WELD RD.	20+43.49	20+92.00		66.6

TEMPORARY ACCESS (COMMERCIAL ENTRANCE)				TOTAL 27 EACH
LOCATION	STA	OFFSET		SUBTOTALS
MCLEAN BLVD	59+96.64	LT		1
MCLEAN BLVD	61+26.66	LT		1
MCLEAN BLVD	62+44.82	LT		1
FLEETWOOD DR	302+44.20	RT		1
FLEETWOOD DR	304+24.31	RT		1
FLEETWOOD DR	304+78.53	LT		1
FLEETWOOD DR	306+12.13	RT		1
FLEETWOOD DR	306+27.09	LT		1
FLEETWOOD DR	306+98.36	LT		1
FLEETWOOD DR	307+10.56	RT		1
FLEETWOOD DR	307+77.84	RT		1
FLEETWOOD DR	308+26.07	LT		1
SHEPARD DR	21+94.89	RT		1
SHEPARD DR	22+48.32	RT		1
SHEPARD DR	28+15.26	LT		1
SHEPARD DR	28+91.17	LT		1
SHEPARD DR	29+43.74	LT		1
SHEPARD DR	29+78.63	RT		1
WELD RD	6+19.85	RT		1
WELD RD	7+32.60	RT		1
WELD RD	9+01.18	RT		1
WELD RD	10+16.16	RT		1
WELD RD	11+68.87	RT		1
WELD RD	14+54.79	RT		1
WELD RD	15+65.12	RT		1
WELD RD	16+25.98	RT		1
WELD RD	17+15.88	RT		1

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH				TOTAL 465 SQ YD
LOCATION	FROM STA.	TO STA.		SUBTOTALS
US 20 EB	99+18.36	103+08.80		465.32

CONCRETE CURB, TYPE B (SPECIAL)				TOTAL 169 FOOT
LOCATION	FROM STA.	TO STA.		SUBTOTALS
FLEETWOOD DR.	306+52.59	306+80.86		28.27
FLEETWOOD DR.	307+15.86	308+09.65		93.79
FLEETWOOD DR.	308+42.48	308+89.00		46.90

TEMPORARY CHAIN LINK FENCE (PORTABLE)				TOTAL 723 FOOT
LOCATION	FROM STA.	TO STA.		SUBTOTALS
MCLEAN BLVD	56+77.00	64+00.00		723

CHAIN LINK FENCE REMOVAL				TOTAL 2684 FOOT
LOCATION	FROM STA.	TO STA.		SUBTOTALS
RAMP B	101+68.74	102+35.49		76.4
RAMP B	103+88.70	112+50.00		897.2
RAMP D	89+76.38	95+63.92		580.4
WELD RD.	8+00.00	18+77.01		1093.2
MCLEAN BLVD	73+80.00	74+00.60		20.6
MCLEAN BLVD	73+73.50	73+90.00		16.5

AGGREGATE SUBGRADE 12"				TOTAL 12617 SQ YD
LOCATION	FROM STA.	TO STA.		SUBTOTALS
WELD RD.	08+00.00	20+00.00		4,767.32
SHEPARD DR.	20+00.00	31+01.59		2,474.78
FLEETWOOD RD.	302+42.10	307+83.84		4,843.90
McLEAN BLVD.	56+85.81	59+73.25		385.44
McLEAN BLVD.	59+73.25	63+19.79		141.83
McLEAN BLVD.	56+85.81	57+04.97		3.86

TEMPORARY PAVEMENT				TOTAL 6802 SQ YD
LOCATION	FROM STA.	TO STA.		SUBTOTALS
McLEAN BLVD. WEST EDGE	59+73	65+61		1262.4
McLEAN BLVD. EAST EDGE	61+48	64+42		90.7
FLEETWOOD RD. NORTH EDGE	301+12	302+79		148.8
FLEETWOOD RD. PROP MEDIAN	307+83	309+38		102.2
FLEETWOOD RD. CENTERLINE	310+51	310+83		41.9
SHEPARD DR. EAST EDGE & FLEETWOOD DR. NORTH EDGE	27+83	309+77		1745.6
WELD RD. SOUTH EDGE & SHEPARD DR. WEST EDGE	5+74	24+15		3410.2

TEMPORARY PAVEMENT (INTERSTATE)					TOTAL 43680 SQ YD
LOCATION	STA.	STA.	AREA SQ FT		SUBTOTALS
US 20 MEDIAN	59+34.85	70+00.00	36,486.28		4,054.03
US 20 MEDIAN	70+00.00	84+50.00	30,701.48		3,411.28
US 20 MEDIAN	84+50.00	97+51.53	11,993.40		1,332.60
W.B. US 20 RT	138+88.38	148+00.00	9,116.20		1,012.91
US 20 MEDIAN	113+68.00	117+00.00	2,687.15		298.57
US 20 MEDIAN	140+24.00	153+32.29	10,648.80		1,183.20
E.B. US 20	54+00.00	64+37.37	10,373.70		1,152.63
E.B. US 20	64+37.37	67+99.98	7,468.70		829.86
E.B. US 20	67+99.98	75+00.00	18,200.52		2,022.28
E.B. US 20	75+00.00	88+00.00	33,800.00		3,755.56
E.B. US 20	88+00.00	96+38.57	27,952.33		3,105.81
E.B. US 20	100+45.08	108+25.50	23,661.50		2,629.06
TEMP RAMP B	102+59.24	108+25.50	10,096.30		1,121.81
E.B. US 20	108+25.50	117+00.00	36,634.86		4,070.54
E.B. US 20	117+00.00	131+00.00	47,180.00		5,242.22
E.B. US 20	131+00.00	141+00.00	33,700.00		3,744.44
E.B. US 20	141+00.00	149+90.78	30,774.62		3,419.40
E.B. US 20	149+90.78	156+01.87	11,494.80		1,277.20

FILE NAME = \\10606910-BURDERPOLDEN... \10606910-SCHEDULED\01.DGN  
 USER NAME = #USER#  
 DESIGNED - designed  
 DRAWN - JFS  
 CHECKED - DDH  
 DATE - 05/27/11  
 REVISED -  
 REVISED -  
 REVISED -  
 REVISED -  
 STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION  
 FAP ROUTE 345 / US ROUTE 20  
 SCHEDULE OF QUANTITIES - IV  
 SCALE: N.T.S.  
 SHEET NO. OF SHEETS STA. TO STA.  
 F.A.P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.  
 345 8R-HB-2-BY-1 KANE 434 28  
 FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT CONTRACT NO. 60K90