

SCHEDULE OF QUANTITIES			
PAY ITEM NO.	DESIGNATION	UNIT	TOTAL QUANTITY
80400100	ELECTRIC SERVICE INSTALLATION	EACH	2
80400200	ELECTRIC UTILITY SERVICE CONNECTION	LSUM	1
81301110	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 12" X 8" X 6"	EACH	4
81800300	AERIAL CABLE, 3-1/2 NO. 2 WITH MESSENGER WIRE	FOOT	19842
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	18
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1
* X8210405	LUMINAIRE SHIELD	EACH	45
* Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	21
* -	TEMPORARY WOOD POLE, 90 FT., CLASS 4, 20FT. MAST ARM, AND LUMINAIRE	EACH	2
* -	MAST ARM, 20FT., FOR WOOD POLE (MATERIAL ONLY)	EACH	93
* -	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 20FT. MAST ARM, AND LUMINAIRE (INSTALL ONLY)	EACH	76
* -	TEMPORARY WOOD POLE, 90 FT., CLASS 4, 20FT. MAST ARM, AND LUMINAIRE (INSTALL ONLY)	EACH	17
* -	TEMPORARY LIGHTING CONTROLLER, 240 VOLT, POLE MOUNTED (INSTALL ONLY)	EACH	2

* DESIGNATES SPECIAL PROVISIONS

ga GANDHI AND ASSOCIATES, INC.
ENGINEERS AND PLANNERS
6035 N. NORTHWEST HIGHWAY
SUITE 305
CHICAGO, ILLINOIS 60631 TEL: (773) 774-5910

FILE NAME =	USER NAME = .GAI.	DESIGNED - PKG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	U.S. RTE. 20 & McLEAN BLVD. TEMPORARY LIGHTING SCHEDULE OF QUANTITIES			F.A.P. RTE. 345	SECTION 8R-HB-2-BY-1	COUNTY KANE	TOTAL SHEETS 434	SHEET NO. 227
FILEL		DRAWN - MAA, SHM	REVISED -		SCALE: NONE	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 60K90	
		CHECKED - PKG	REVISED -								FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	
		DATE - 05/18/2011	REVISED -									