



NOTES:

NOTE 1: THE CONTRACTOR SHALL INSTALL A LIGHT SHIELD ON THIS LIGHT FIXTURE TO AVOID LIGHT SPILLING TOWARDS THE RESIDENTIAL AREAS. THE COST FOR THE LIGHT SHIELD SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR LUMINAIRE, OF THE LAMP TYPE, MOUNT TYPE, AND WATTAGE SPECIFIED.

NOTE 2: ALL MATERIALS, EQUIPMENT, AND LABOR NEEDED TO INSTALL AND CONNECT THE SERVICE FROM THE COMED UTILITY TRANSFORMER TO THE TEMPORARY LIGHTING CONTROLLER CABINET SHALL BE PART OF PAY ITEM NO. 80400100 - ELECTRIC SERVICE INSTALLATION. THAT SHALL INCLUDE THE APPROVED METER SOCKET, CABLE, CONDUIT PUSHED AND TRENCHED FOR THE CONDUIT SHOWN ON THE PLANS. ALL CONNECTIONS, SPlicing, AND WIRING TO THE TEMPORARY LIGHTING CONTROLLER IS ALSO INCLUDED UNDER THE SAME PAY ITEM. THE SERVICE CABLE AND CONDUIT SIZE SHALL BE AS SHOWN ON THE PLANS.

NOTE 3: THE ELEVATION SPECIFIED INDICATES A FUTURE GROUND SURFACE ELEVATION AT THE POLE LOCATION. THE DEPTH OF THE POLE IN THE GROUND SHALL BE BASED ON THE LOWEST OF THE FOLLOWING ELEVATIONS:
 THE EXISTING GROUND SURFACE ELEVATION
 THE PROPOSED GROUND SURFACE ELEVATION
 INTERIM GROUND SURFACE ELEVATION
 OR THE ELEVATION SPECIFIED

GO GANDHI AND ASSOCIATES, INC.
 ENGINEERS AND PLANNERS
 6055 N. NORTHWEST HIGHWAY
 SUITE 305
 CHICAGO, ILLINOIS 60631 TEL: (773) 774-5910

FILE NAME =	USER NAME = .GAI.	DESIGNED - PKG	REVISED -
#FILE#		DRAWN - MAA, SHM	REVISED -
	PLOT SCALE = #SCALE#	CHECKED - PKG	REVISED -
	PLOT DATE = 5/12/2011	DATE - 05/18/2011	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**TEMPORARY LIGHTING PLAN
 (SHEET 5 OF 5)**

SCALE: 1" = 50'

SHEET NO.	OF	SHEETS	STA.	TO	STA.
-----------	----	--------	------	----	------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	BR-HB-2-BY-1	KANE	434	232
CONTRACT NO. 60K90				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

PROJECT ENDS
 STA. 156+00.00