



NOTE:
 ONLY REPLACEMENT OF DETECTOR LOOPS NOTED WITH AN ASTERISK (*) IS PROPOSED AT THIS INTERSECTION.
 QUANTITIES FOR DETECTOR LOOP REPLACEMENT ARE INCLUDED IN THE SCHEDULE OF QUANTITIES ON THE CABLE PLAN FOR IL ROUTE 19 (IRVING PARK ROAD) AT BARRINGTON ROAD, CONTRACT NO. 60L23.

NOTE:
 THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

RESTORATION OF WORK AREA, RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED, ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND, ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDING IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

FILE NAME = K:\Projects\10055\DesignCAD\Sheet Files\141889rwaME\01.dgn	USER NAME = \$USER\$ 141889rwaME\01.dgn	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 19 (IRVING PARK ROAD) AT BARRINGTON ROAD EXISTING TRAFFIC SIGNAL EQUIPMENT AT MENARDS ENTRANCE	F.A.U. RTE. 1321	SECTION 2010-048-N	COUNTY COOK	TOTAL SHEETS 53	SHEET NO. 21		
PLOT SCALE = \$SCALE\$	CHECKED -	REVISED -	SCALE: N.T.S.			SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				
PLOT DATE = 3/6/2011	DATE -	REVISED -										
CONTRACT NO. 60L23												