

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL	0005				CODE NO	ITEM	UNIT	TOTAL	0005			
			QUANTITIES	100%STATE	ROADWAY							QUANTITIES	100%STATE	ROADWAY	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	18	18				70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	460	460			
25200110	SODDING, SALT TOLERANT	SO YD	18	18				70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	565	565			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30	30				70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	45	45			
40600300	AGGREGATE (PRIME COAT)	TON	146	146				70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2270	2270			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	55	55				* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	182	182			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	31380	31380			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	228	228				* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	460	460			
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	273	273				* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	565	565			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	139	139				* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	45	45			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3061	3061				* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	355	355			
42001300	PROTECTIVE COAT	SO YD	20	20				78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	350	350			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	30317	30317				* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	173	173			
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	605	605				X2020110	GRADING AND SHAPING SHOULDERS	UNIT	150	150			
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	6143	6143				X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1590	1590			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	433	433				X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	1405	1405			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	79	79				X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	204	204				Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	105	105			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	600	600				Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	6	6			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	6	6				Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8			
64200105	SHOULDER RUMBLE STRIPS	FOOT	300	300											
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6											
67100100	MOBILIZATION	L SUM	1	1											
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1											
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1											
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1											
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1											
70300100	SHORT TERM PAVEMENT MARKING	FOOT	6810	6810											
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	182	182											
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	31380	31380											