

SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			URBAN 100% STATE CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES							CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
				0005										0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	59	59						*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	234	234					
25200110	SODDING, SALT TOLERANT	SO YD	59	59						*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3203	3203					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13	13						*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1886	1886					
40600300	AGGREGATE (PRIME COAT)	TON	65	65						*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	10	10					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	25	25						*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	282	282					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	251	251					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	192	192						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	211	211					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	77	77						*88600600	DETECTOR LOOP REPLACEMENT	FOOT	630	630					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1352	1352						X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	664	664					
42001300	PROTECTIVE COAT	SO YD	156	156						X5539700	STORM SEWERS TO BE CLEANED	FOOT	300	300					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	59	59						X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	75	75					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2-1/4"	SO YD	16085	16085						Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	700	700					
44000600	SIDEWALK REMOVAL	SO FT	59	59						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	25	25					
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SO YD	391	391						Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	150	150															
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SO YD	90	90															
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SO YD	100	100															
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	15	15															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3951	3951															
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	234	234															
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3203	3203															
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1886	1886															
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	10	10															
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	282	282															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1317	1317															

* SPECIALTY ITEM