

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES						CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES					
				0005									0005				
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	31	31					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	496	496				
40600300	AGGREGATE (PRIME COAT)	TON	152	152					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	510	510				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	57	57					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	30900	30900				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1520	1520				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1898	1898					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	200	200				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	19	19					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	800	800				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3173	3173					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	60	60				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1-1/2"	SQ YD	2686	2686					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	514	514				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2-1/4"	SQ YD	35083	35083					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	514	514				
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	92	92					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	150	150				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	80	80					X2020110	GRADING AND SHAPING SHOULDERS	UNIT	110	110				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	16	16					X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1448	1448				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	27	27					X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	8				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	5	5					Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1													
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1													
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1488	1488													
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	510	510													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	30900	30900													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1520	1520													
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	200	200													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	800	800													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	60	60													

\* Specialty Items