

CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY 0004	BRIDGE 0011
				URBAN	URBAN
55100700	STORM SEWER REMOVAL, 15"	FOOT	125	125	
550A0070	STORM SEWER, CLASS A, TYPE 1 15"	FOOT	56	56	
550A0120	STORM SEWER, CLASS A, TYPE 1 24"	FOOT	5	5	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	250		250
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	4	4	
60107600	PIPE UNDERDRAINS 4"	FOOT	984	984	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	201	201	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2	
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2	
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	4	4	
60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	FOOT	408	408	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	195	195	
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	155		155
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2	
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	302	302	
66400305	CHAIN LINK FENCE, 6'	FOOT	132	132	
66402900	CHAIN LINK GATES, 6' X 6' SINGLE	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1520	1520	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	49	49	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50	50	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	18	18	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	

CODE NO.	ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY 0004	BRIDGE 0011
				URBAN	URBAN
78300100	PAVEMENT MARKING REMOVAL	SQ FT	607	607	
X0322584	REVTMENT MAT REMOVAL	SQ YD	54	54	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	333		333
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	8	8	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	2935	2935	
Z0001056	AGGREGATE SUBGRADE 16"	SQ YD	946	946	
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	371	371	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0022800	FENCE REMOVAL	FOOT	262	262	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	206	206	
* Z0054517	ROCK FILL - FOUNDATION	TONS	467		467
Z0076600	TRAINERS	FOOT			
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2	2	

* - DENOTES SPECIALTY ITEM

FILE NAME = I:\6611\661124 - Fullerton over Silver - Creek\LOAD\CADD\CAD\Drawings\16\661124.dgn



USER NAME = rjgall
PLOT SCALE = 50.0000' / IN.
PLOT DATE = 5/27/2011

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1381	0101.1-T	COOK	42	4
CONTRACT NO. 60M82				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.