

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 342	2011-026-I	COOK & LAKE	71	13

CONTRACT NO. 60P26

West Panel No.	Wooden Batten, Secure Existing (LF)	Wooden Batten, Salvage and Reposition (LF)	Wooden Batten, Furnish and Install (LF)	Wooden Plank, Salvage and Reposition (SF)	Wooden Plank, Furnish and Install (SF)	Wooden Wall, Painting (1 Unit = 100 SF)	Porous Granular Material (CU YD)	Comments (All Panel had 4 vertical battens unless otherwise noted)
217	64				36		0.2778	
218	64				24	0.72	0.2778	
219	68				12	0.25	0.2778	
220	68				18		0.2778	
221	68			30	24		0.2778	
222	68				18	0.2	0.2778	
223	68				12		0.2778	
224	68				24	0.3	0.2778	
225	64			190			0.2778	
226	64				18	0.55	0.1852	
227	64				12	0.55	0.1852	
228	60				36		0.2778	
229	60				30		0.1852	
230	60			190	12	0.2	0.2778	
231	57		7		36	0.2	0.2778	
232	68				24		0.2778	
233	64				6	0.2	0.2778	
234	64				24		0.2778	
235	68				36	0.12	0.2778	
236	68				30		0.2778	
237	68				30		0.2778	
238	68						0.2778	
239	68						0.2778	
240	66		6		12			
241	68				24		0.1389	
242	68				42		0.2778	
243	64						0.2778	
244	57	7			18		0.2778	
245	62	2					0.2778	
246	64				6		0.2778	
247	64				18		0.2778	

ILLINOIS DEPARTMENT OF
TRANSPORTATION

SCHEDULE OF QUANTITIES
SHEET 8 OF 36