

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 342	2011-026-I	COOK & LAKE	71	34

CONTRACT NO. 60P26

East Panel No.	Wooden Batten, Secure Existing (LF)	Wooden Batten, Salvage and Reposition (LF)	Wooden Batten, Furnish and Install (LF)	Wooden Plank, Salvage and Reposition (SF)	Wooden Plank, Furnish and Install (SF)	Wooden Wall, Painting (1 Unit = 100 SF)	Porous Granular Material (CU YD)	Comments (All Panel had 4 vertical battens unless otherwise noted)
310	66				12		0.2778	22' Panel Height, 66' total Batten Length, 3 vertical battens
311	39	28	21		72		0.2778	22' Panel Height, 88' total Batten Length
312	78		14		42		0.2778	23' Panel Height, 92' total Batten Length
313	78	14			30		0.2315	23' Panel Height
314	58	31	3		18		0.2778	23' Panel Height, 92' total Batten Length
315	40	42	10	6	30		0.2778	
316	71	21			42		0.2778	23' Panel Height
317	73	9	10		72		0.2778	
318	78	7	7		42		0.2778	
319	92				30			
320	72						0.1389	24' Panel Height with 3 vertical battens
321	96				12		0.2778	24' Panel Height, 96' total Batten Length
322	92				30		0.2778	23' Panel Height
323	66	13	12		60		0.2778	
324	85		7		42		0.1389	
325	78	14			12		0.2315	
326	46	21	25	24	36		0.0463	
327	88				12			22' Panel Height, 88' total Batten Length Pillings- Rectangular
328	76	12			18			
329	43	21	24		60		0.0694	
330	63	25			18			
331	60	28			18			
332	60	28			42		0.2778	
333	84				30			21' Panel Height, 84' total Batten Length
334	56	14	14		60	0.72		21' Panel Height, 84' total Batten Length
335	66	14			18	0.32		20' Panel Height, 80' total Batten Length
336	73	7			18	0.84		
337	46		14		12	0.64	0.0463	20' Panel Height, 80' total Batten Length, 3 vertical battens
338	80				24	0.84		20' Panel Height

ILLINOIS DEPARTMENT OF
TRANSPORTATION

SCHEDULE OF QUANTITIES
SHEET 29 OF 36