F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FP	MCHENRY	292	006
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 63522

SUMMARY OF QUANTITIES

	ITEM NO	DESCRIPTION	UNIT	URBAN TOTAL	WALKUP RD CMAQ	WALKUP RD STU	WALKUP RD LOCAL
					CONSTRUCTION TYPE CODE		
					0003	0003	0043
	54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1		
	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2		
	5421D012	PIPE CULVERTS, CLASS D, TYPE 1 12" (TEMPORARY)	FOOT	712	466	246	
	542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	117	117		
	542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	54	54		
	542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	147	147		
	542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	114	114		
	542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	12	12		
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1402	1207	195	
	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	27	7	20	
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	564	564		
	550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	23	23		
	550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	67	67		
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	2697	1797	900	
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	1200	808	392	
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	3056	2724	332	
	550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	681	350	331	
	550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	208	77	131	
	550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	485		485	
	550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	439	343	96	
	550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	125		125	
	550A0660	STORM SEWERS, CLASS A, TYPE 3 15"	FOOT	59		59	
	550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	202		202	
	550A0770	STORM SEWERS, CLASS A, TYPE 3 42"	FOOT	179	179		
	550A5000	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 27"	FOOT	374	374		
	550A5300	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 36"	FOOT	874	874		
	550B0410	STORM SEWERS, CLASS B, TYPE 2 24"	FOOT	325		325	
	55100500	STORM SEWER REMOVAL 12"	FOOT	1917	455	1462	
	55100700	STORM SEWER REMOVAL 15"	FOOT	633	84	549	
	55100900	STORM SEWER REMOVAL 18"	FOOT	1456	1433	23	
	55101200	STORM SEWER REMOVAL 24"	FOOT	152	116	36	
	55101400	STORM SEWER REMOVAL 30"	FOOT	914	561	353	
	55101800	STORM SEWER REMOVAL 42"	FOOT	62		62	
*	56100003	DUCTILE IRON WATER MAIN TEE, 4" X 4"	EACH	1			1
*	56100010	DUCTILE IRON WATER MAIN TEE 8" X 4"	EACH	1			1
*	56100015	DUCTILE IRON WATER MAIN TEE, 8" X 6"	EACH	2			2
*	56100045	DUCTILE IRON WATER MAIN TEE, 12" X 4"	EACH	5			5
*	56100050	DUCTILE IRON WATER MAIN TEE, 12" X 6"	EACH	4			4
*	56100055	DUCTILE IRON WATER MAIN TEE, 12" X 8"	EACH	4			4
*	56100065	DUCTILE IRON WATER MAIN TEE, 12" X 12"	EACH	4			4
*	56101160	DUCTILE IRON WATER MAIN REDUCER, 12" X 8"	EACH	3			3
*	56102900	DUCTILE IRON WATER MAIN 4"	FOOT	127			127
*	56103000	DUCTILE IRON WATER MAIN 6"	FOOT	168			168

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SUMMARY OF QUANTITIES
SHEET 3 OF 8

SCALE: N.T.S. DRAWN BY: LK
DATE: 06/10/11 CHECKED BY: MCD

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0005

..\S002A00\JOB..\S002A00\JOB..\B999A00\JOB
6-24-2011 9:30:22 \\FS-0044\VAM-VAULT\D-TRANS_07\2202\300-03\CIVIL\CAD\02 CONTRACT\IA TENG\SHEET\S002A003.SHT STANKRJ