

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FP	MCHENRY	292	008
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
CONTRACT NO: 63522				

ITEM NO	DESCRIPTION	UNIT	URBAN TOTAL	CONSTRUCTION TYPE CODE		
				WALKUP RD CMAQ	WALKUP RD STU	WALKUP RD LOCAL
				0003	0003	0043
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	6	6		
60600605	CONCRETE CURB, TYPE B	FOOT	124		124	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6,24	FOOT	26607	21310	5297	
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	1019	1019		
63200310	GUARDRAIL REMOVAL	FOOT	464	464		
• 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1650		1650	
• 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1		1	
• 66900530	SOIL DISPOSAL ANALYSIS	EACH	3		3	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	18	6	
67100100	MOBILIZATION	L SUM	1	0.7	0.3	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	418	355	63	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	96	96		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8112	8112		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	545	291	254	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	103904	85596	18308	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2475	1348	1127	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	242	71	171	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	541		541	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2500	1000	1500	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	32037	32037		
• 72000100	SIGN PANEL - TYPE 1	SQ FT	32		32	
• 72000200	SIGN PANEL - TYPE 2	SQ FT	30	30		
• 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	72	42	30	
• 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	8	7	1	
• 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	176	106	70	
• 72900100	METAL POST - TYPE A	FOOT	35	23	12	
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1886	1409	477	
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	47253	38893	8360	
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6611	4342	2269	
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	207	207		
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2025	1640	385	
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	553	376	177	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	117		117	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	16600	14110	2490	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	105	105		
• 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2	1	1	
• 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1073	35	1038	
• 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	62	34	28	
• 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	94	74	20	
• 81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	65		65	
• 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	100	10	90	
• 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	242		242	
• 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	45	45		

• SPECIALTY ITEM

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SUMMARY OF QUANTITIES SHEET 5 OF 8

SCALE: N.T.S. DRAWN BY: LK
DATE: 06/10/11 CHECKED BY: MCD

TENG & ASSOCIATES, INC.
ENGINEERING ARCHITECTURE PLANNERS
185 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312-666-6000

\S0224001.DGN... \S0224001.DGN... \S0224001.DGN... \S0224001.DGN... \S0224001.DGN...
 6-22-2011 9:50:26
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63