

SCHEDULE OF QUANTITIES

F.A.U. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FR	MCHENRY	292	021
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT NO: 63522				

TOTAL 3179 TON						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70					
LOCATION	FR STA	WIDTH	TO STA	WIDTH	LENGTH	SUBTOTALS
RESURFACING (LEFT SIDE)						
WALKUP	225+00.18.0		307+45.18.0		8245.0	1511.8
RESURFACING (RIGHT SIDE)						
WALKUP	225+00.18.0		307+45.18.0		8245.0	1385.2
SIDE STREETS ALONG WALKUP						
ANVIL DR						31.3
COACHLIGHT RD						28.5
RAINTREE DR						28.4
MASON HILL RD						73.9
MASON HILL RD BUMPOUT						14.3
RESURFACING (WALKUP AVE)						
WALKUP AVE	43+22.6		45+00.0			105.2

TOTAL 13974 TON						
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70					
						SUBTOTALS
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70						7,642
Var Depth Binder Course						346
9" WIDENING (LEFT SIDE)						
225+00	307+45					3145
9" WIDENING (RIGHT SIDE)						
225+00	307+45					2625
SIDE STREETS						
SHENANDOAH CT						38
ANVIL DR						75
COACHLIGHT RD						76
RAINTREE DR						27

TOTAL 465 TON						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50					
LOCATION	FR STA	WIDTH	TO STA	WIDTH	LENGTH	SUBTOTALS
SHARED USE PATH						27.5
WALKUP	47+10	10	49+31	10	220.98	52.3
WALKUP	50+80	10	55+00	10	420.33	99.0
WALKUP	55+00	10	62+95	10	795.36	76.7
WALKUP	63+83	10	70+00	10	616.58	49.1
WALKUP	70+00	10	73+95	10	394.65	75.0
WALKUP	74+24	10	80+26	10	602.71	
RTE 176 2" DRIVEWAY PAVEMENT						62.7
HMA DRIVEWAY PAVEMENT 8"						22.5
HMA DRIVEWAY PAVEMENT 10"						

TOTAL 25320 SQ YD							
44000100	PAVEMENT REMOVAL						
LOCATION	FR STA	WIDTH	TO STA	WIDTH	AREA	AREA	SUBTOTALS
		FT		FT	SO FT	SO YD	
WALKUP Road							
WALKUP	45+00	VAR	49+39	VAR	19990.6	2221.2	2221.2
WALKUP	49+39	VAR	81+54	VAR	141152	15683.6	15683.6
WALKUP	248+47.	VAR	249+00	VAR	187	20.8	20.8
IL RTE 176	43+13	VAR	48+49	VAR	29028	3225.3	3225.3
IL RTE 176	51+00	VAR	60+08	VAR	37521	4169.0	4169.0

TOTAL 9102 FOOT					
44000500	COMBINATION CURB AND GUTTER REMOVAL				
ROAD NAME	FR STA	TO STA	LT/RT	LENGTH	SUBTOTALS
WALKUP	43+35	46+52	LT	317	317
WALKUP	RAD 46+63	-	LT	28	28
WALKUP	RAD 43+35	-	RT	50	50
WALKUP	43+72	46+74	RT	302	302
WALKUP	RAD 46+90	-	RT	107	107
WALKUP	RAD 46+96	-	LT	131	131
WALKUP	47+13	49+22	LT	209	209
WALKUP	47+52	49+31	RT	179	179
WALKUP	RAD 49+68	-	LT	49	49
WALKUP	RAD 49+74	-	RT	70	70
WALKUP	RAD 50+28	-	LT	52	52
WALKUP	RAD 50+30	-	RT	51	51
WALKUP	50+55	62+80	RT	1225	1225
WALKUP	50+54	52+59	LT	205	205
WALKUP	RAD 52+77	-	LT	32	32
WALKUP	52+59	53+27	LT	68	68
WALKUP	RAD 53+13	-	LT	37	37
WALKUP	53+27	54+38	LT	111	111
WALKUP	RAD 54+60	-	LT	64	64
WALKUP	RAD 55+28	-	LT	71	71
WALKUP	RAD 63+09	-	RT	55	55
WALKUP	RAD 63+62	-	RT	61	61
WALKUP	55+67	59+15	LT	348	348
WALKUP	RAD 59+33	-	LT	54	54
WALKUP	RAD 59+71	-	LT	62	62
WALKUP	59+93	62+85	LT	292	292
WALKUP	RAD 63+06	-	LT	65	65
WALKUP	RAD 63+65	-	LT	74	74
WALKUP	63+98	65+92	LT	194	194
WALKUP	77+27	80+29	RT	302	302
WALKUP	78+74	81+54	LT	280	280
WALKUP	RAD 80+53	-	RT	63	63
WALKUP	RAD 81+00	-	RT	104	104
IL RTE 176	41+68	43+25	LT	157	157
IL RTE 176	RAD 43+25	-	LT	50	50
IL RTE 176	RAD 43+64	-	LT	50	50
IL RTE 176	43+85	44+79	LT	94	94
IL RTE 176	RAD 44+84	-	LT	33	33
IL RTE 176	RAD 45+26	-	LT	47	47
IL RTE 176	45+49	49+49	LT	400	400
IL RTE 176	50+57	61+24	LT	1067	1067
IL RTE 176	41+67	48+12	RT	645	645
IL RTE 176	48+47	49+48	RT	101	101
IL RTE 176	50+55	52+06	RT	151	151
IL RTE 176	RAD 52+24	-	RT	73	73
IL RTE 176	RAD 52+60	-	RT	74	74
IL RTE 176	52+76	55+99	RT	323	323
IL RTE 176	RAD 56+13	-	RT	69	69
IL RTE 176	RAD 56+50	-	RT	70	70
IL RTE 176	56+64	59+22	RT	258	258
IL RTE 176	RAD 59+37	-	RT	54	54
IL RTE 176	RAD 59+75	-	RT	55	55
IL RTE 176	59+89	60+08	RT	19	19

TOTAL 13068 SQ FT						
44000600	SIDEWALK REMOVAL					
LOCATION	FR STA	WIDTH	TO STA	AREA	LT/RT	SUBTOTALS
WALKUP	43+39	VAR	45+51	970.7	LT	970.7
WALKUP	45+73	VAR	46+69	463.13	LT	463.13
WALKUP	43+54	VAR	46+89	1774	RT	1774
WALKUP	46+92	VAR	48+73	931	LT	931
WALKUP	47+06	VAR	49+71	1125	RT	1125
WALKUP	48+89	VAR	49+65	282	LT	282
WALKUP	50+42	VAR	51+77	551	RT	551
WALKUP	50+20	VAR	53+10	1461	LT	1461
WALKUP	54+61	VAR	-	28	LT	28
WALKUP	59+68	VAR	60+92	557	LT	557
WALKUP	63+10	VAR	-	114	LT	114
WALKUP	63+67	VAR	-	136	LT	136
IL RTE 176	41+67	VAR	43+34	840.92	LT	840.92
IL RTE 176	43+61	VAR	44+87	511.1	LT	511.1
IL RTE 176	45+24	VAR	48+37	1230.8	LT	1230.8
IL RTE 176	50+73	VAR	51+95	522	LT	522
IL RTE 176	50+29	VAR	52+21	786	RT	786
IL RTE 176	56+00	VAR	-	114	RT	114
IL RTE 176	56+48	VAR	57+99	670.7	RT	670.7
THIRD ST				53.87		53.87

TOTAL 16752 SQ FT						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH					
LOCATION	STATION	STATION	LENGTH	WIDTH	O/S	SUBTOTALS
IL 176	41+66.94	43+36.16			LT	1284.9
IL 176	43+62.35	44+82.85			LT	551.3
IL 176	45+29.57	49+00.00			LT	1999.6
IL 176	49+00.00	49+50.00	63.60	5.00	LT	318.0
IL 176	49+30.00		7.63	5.00	LT	38.2
IL 176	49+45.00		9.05	5.00	LT	45.3
IL 176	50+71.86	51+00.00	28.14	5.00	RT	140.7
IL 176	50+79.78	51+00.00			LT	119.9
IL 176	51+00.00	51+93.81	93.81	5.00	LT	469.1
IL 176	51+00.00	52+18.40	145.94	5.00	RT	729.7
IL 176	55+42.66	59+25.00	282.50	5.00	RT	1412.5
IL 176	59+86.41	60+43.75	57.21	5.00	RT	286.1
IL 176	Second St		8.34	5.00		41.7
IL 176	Thrd St		42.01	4.00		168.0
IL 176	Thrd St		9.75	4.00		39.0
WALKUP	43+34.83	46+59.81	324.98	5.00	LT	1624.9
WALKUP	43+50.00	46+54.71	305.36	8.00	RT	2442.9
WALKUP	47+04.08	49+44.76	250.50	5.00	LT	1252.5
WALKUP	49+32.25		13.38	5.00	LT	66.9
WALKUP	50+73.37	52+72.00	199.95	5.00	LT	999.7
WALKUP	53+12.53	53+93.74	80.89	5.00	LT	404.5
WALKUP	54+23.64	54+61.03	39.10	5.00	LT	195.5
WALKUP	59+70.02	63+09.17	355.39	5.00	LT	1777.0
WALKUP	63+67.33	63+67.33	23.79	4.00	LT	95.2
WALKUP	Burden Drive				RT	218.5
WALKUP	Burden Drive				RT	30.9

TOTAL 1320 SQ FT					
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH				
ROAD NAME	STATION	LT/RT			SUBTOTALS
WALKUP	49+31.03RT				444.3
WALKUP	50+68.66RT				373.4
WALKUP	62+95.36RT				106.9
WALKUP	63+83.42RT				116.5
WALKUP	80+26.32RT				121.3
WALKUP	81+00.00RT				157.4

TOTAL 8708 SQ YD					
Z0062456	TEMPORARY PAVEMENT				
LOCATION	FR STA	TO STA	LT/RT	AREA	SUBTOTALS
WALKUP	50+56	5458+37	LT	11550	1283.3
WALKUP	55+53	59+34	LT	2072	230.22222
WALKUP	59+66	63+09	LT	4311	479
WALKUP	63+65	82+78	LT	33305	3700.5556
IL RTE 176	50+50	52+10	RT	1665	185
IL RTE 176	41+02	42+31	LT	412	45.777778
IL RTE 176	46+32	49+86	LT	6443	715.88889
IL RTE 176	50+21	61+23	LT	18618	2068.6667

TOTAL 26608 FOOT					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24				
LOCATION	FROM STA	TO STA	LT/RT	LENGTH	SUBTOTALS
	from	to			
WALKUP	43+34.67	43+46.5	RT	11.90	11.9
WALKUP	RAD 43+46.57	-			