

SCHEDULE OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FP	MCHENRY	292	022
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT NO: 63522				

28000305 TEMPORARY DITCH CHECKS				TOTAL 664 FOOT
LOCATION	STA	LT/RT	LENGTH FOOT	SUBTOTALS
WALKUP	76+65	RT	8	8
	226+60	RT	8	8
	229+25	RT	8	8
	230+80	RT	8	8
	234+95	RT	8	8
	235+25	RT	8	8
	237+10	RT	8	8
	239+15	RT	8	8
	246+10	RT	8	8
	248+15	RT	8	8
	250+15	RT	8	8
	253+85	RT	8	8
	255+90	RT	8	8
	257+45	RT	8	8
	259+10	RT	8	8
	259+80	RT	8	8
	266+80	RT	8	8
	268+70	RT	8	8
	270+90	RT	8	8
	271+15	RT	8	8
	272+95	RT	8	8
	274+75	RT	8	8
	281+30	RT	8	8
	283+15	RT	8	8
	285+85	RT	8	8
	288+10	RT	8	8
	290+35	RT	8	8
	292+10	RT	8	8
	394+45	RT	8	8
	299+45	RT	8	8
	299+60	RT	8	8
	301+75	RT	8	8
	303+75	RT	8	8
	305+65	RT	8	8
WALKUP	71+55	LT	8	8
	73+80	LT	8	8
	75+45	LT	8	8
	76+50	LT	8	8
	78+25	LT	8	8
	80+10	LT	8	8
	226+25	LT	8	8
	227+65	LT	8	8
	227+80	LT	8	8
	230+50	LT	8	8
	230+75	LT	8	8
	232+65	LT	8	8
	235+25	LT	8	8
	237+05	LT	8	8
	237+15	LT	8	8
	241+20	LT	8	8
	243+10	LT	8	8
	245+40	LT	8	8
	245+75	LT	8	8
	247+10	LT	8	8
	250+85	LT	8	8
	253+30	LT	8	8
	254+30	LT	8	8
	254+40	LT	8	8
	255+20	LT	8	8
	256+80	LT	8	8
	258+85	LT	8	8
	260+80	LT	8	8
	261+10	LT	8	8
	262+80	LT	8	8
	264+75	LT	8	8
	266+80	LT	8	8
	268+70	LT	8	8
	270+65	LT	8	8
	282+80	LT	8	8
	285+60	LT	8	8
	286+85	LT	8	8
	288+50	LT	8	8
	290+25	LT	8	8
	292+40	LT	8	8
	294+15	LT	8	8
	296+15	LT	8	8
	298+15	LT	8	8
	299+10	LT	8	8
	300+45	LT	8	8
	300+75	LT	8	8
	302+85	LT	8	8
	306+95	LT	8	8
	307+10	LT	8	8

35101800 AGGREGATE BASE COURSE, TYPE B 6"		TOTAL 3676 SQ YD
BIKE PATH		
HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	3392.86	
VET ARCES PARK RUNNING PATH SEE XX006613 FOR CALCULATION	283	
SUBTOTALS		

X4401198 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH						TOTAL 12728 SQ YD
LOCATION	FR STA	WIDTH FOOT	TO STA	WIDTH FOOT	LENGTH FOOT	SUBTOTALS
WALKUP	43+23		45+00			787.5
WALKUP	81+54	2.0	83+37	2.0	103.87	23.1
WALKUP	225+60		226+00			70.8
WALKUP	228+00		233+00			826.4
WALKUP	234+60		236+00			195.1
WALKUP	240+40		243+80			546.5
WALKUP	246+20		245+80			278.4
WALKUP	246+20		249+40			682.0
WALKUP	250+80		251+20			11.1
WALKUP	251+80		252+20			8.9
WALKUP	254+20		255+60			231.6
WALKUP	257+80		273+00			2217.9
WALKUP	273+00		273+80			15.7
WALKUP	275+20		278+40			463.0
WALKUP	278+60		279+20			26.7
WALKUP	279+20		280+80			93.3
WALKUP	281+20		290+20			1406.5
WALKUP	291+00		307+40			2284.1
SIDE STREETS						
RAILROAD ST						91.7
COACHLIGHT RD						268.9
RAINTREE DR						446.7
MASON HILL RD						479.4
ILL RTE 176	40+69.97		4443+12.74	45		1184.486
ILL RTE 176	60+07.05		262+42.77	2	LT	52.38
ILL RTE 176	60+07.05		261+68.21	2	RT	35.81

44201753 CLASS D PATCHES, TYPE II, 9 INCH						TOTAL 170 SQ YD
LOCATION	STA	LGTH	WIDTH	/SPOT		SUBTOTALS
NB & SB	22500	4	12	2		10.7
NB & SB	235+00	4	12	2		10.7
NB & SB	246+50	15	12	2		40.0
NB & SB	260+50	4	12	2		10.7
NB & SB	262+75	4	12	2		10.7
NB & SB	265+25	4	12	2		10.7
SB ONLY	265+50	4	16	1		7.1
NB & SB	266+00	4	12	2		10.7
NB & SB	266+25	8	12	2		21.3
NB ONLY	291+00	8	12	1		10.7
NB & SB	294+50	4	12	2		10.7
NB & SB	299+00	6	12	2		16.0

44201757 CLASS D PATCHES, TYPE III, 9 INCH						TOTAL 671 SQ YD
LOCATION	STA	LGTH	WIDTH	/SPOT		SUBTOTALS
WALKUP	274+00	6	12	2		16.0
WALKUP	288+50	4	12	2		10.7
WALKUP	294+00	4	12	2		10.7
LATERAL PATCHING FOR STORM SEWERS						0.0
WALKUP	228+00	25	8.5	1		23.6
WALKUP	230+77	26	10	1		28.9
WALKUP	232+90	25	8	1		22.2
WALKUP	235+10	24	8	1		21.3
WALKUP	237+00	25	8	1		22.2
WALKUP	240+93	25	8	1		22.2
WALKUP	243+50	25	8	1		22.2
WALKUP	245+63	25	8.5	1		23.6
WALKUP	246+69	25	8	1		22.2
WALKUP	249+92	25	8.25	1		22.9
WALKUP	256+00	25	8	1		22.2
WALKUP	257+65	25	8	1		22.2
WALKUP	259+25	25	8	1		22.2
WALKUP	270+92	27	11.5	1		34.5
WALKUP	274+00	27	7.5	1		22.5
WALKUP	283+35	25	8	1		22.2
WALKUP	286+00	25	8	1		22.2
WALKUP	288+40	25	8	1		22.2
WALKUP	290+50	25	8	1		22.2
WALKUP	292+25	25	8	1		22.2
WALKUP	294+60	25	8	1		22.2
WALKUP	300+63	24	9	1		24.0
WALKUP	306+00	25	8.5	1		23.6
VET ACRES	105+35	20	22	1		48.9
VET ACRES	106+06	20	22	1		48.9

44201759 CLASS D PATCHES, TYPE IV, 9 INCH						TOTAL 61 SQ YD
LOCATION	STA	LGTH	WIDTH	/SPOT		SUBTOTALS
NB & SB	227+00	4	12	2		10.7
NB & SB	247+25	15	12	2		40.0
NB & SB	260+00	4	12	2		10.7

48101500 AGGREGATE SHOULDERS, TYPE B 6"				TOTAL 813 SQ YD
LOCATION FROM STA	TO STA		SUBTOTALS	
WALKUP	298+69	308+25	424.8	
WALKUP	299+52	308+25	388.0	
Mason Hill	20+40.00	22+02.45		
Mason Hill	20+40.00	22+32.69		

48203029 HOT-MIX ASPHALT SHOULDERS, 8"				TOTAL 921 SQ YD
LOCATION	FROM STA	TO STA	SUBTOTALS	
WALKUP	298+20	308+25	446.8	
WALKUP	299+10	308+25	406.6	
Mason Hill	22+02.45	22+28.28	9.4	
Mason Hill	22+32.69	22+58.52	9.4	
Coachlight	236+07.44	236+08.92	9.8	

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SCHEDULE OF QUANTITIES SHEET 2 OF 8

SCALE: N.T.S. DRAWN BY: LK
DATE: 04/15/11 CHECKED BY: MCD

TENG

TENG & ASSOCIATES INC.
ENGINEERS ARCHITECTS SURVEYORS
305 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312.487.2000

\S:\S-004\AMVAULT\0-TRANS\07\2002\300-03\CIVIL\CAD\02 CONTRACT\VA TENG\SHEET\SC02A002.SHT
 4-14-2011 15:01:42
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63