

SCHEDULE OF QUANTITIES

STATION	TO STATION	EARTH EXCAVATION				REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (TOPSOIL & UNDERCUT)				EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)				EMBANKMENT				EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)				POROUS GRANULAR EMBANKMENT SUBGRADE					
		PRESTAGE CYD	STAGE I CYD	STAGE II CYD	STAGE III CYD	PRESTAGE CYD	STAGE I CYD	STAGE II CYD	STAGE III CYD	PRESTAGE CYD	STAGE I CYD	STAGE II CYD	STAGE III CYD	PRESTAGE CYD	STAGE I CYD	STAGE II CYD	STAGE III CYD	PRESTAGE CYD	STAGE I CYD	STAGE II CYD	STAGE III CYD	PRESTAGE CYD	STAGE I CYD	STAGE II CYD	STAGE III CYD		
ILLINOIS ROUTE 176																											
41+66.94	42+00.00	0.0	29.0	0.0	42.5	0.0	11.8	0.0	12.1	0.0	24.6	0.0	36.1	0.0	0.1	0.0	1.0	0.0	24.6	0.0	35.1	0.0	0.0	0.0	0.0	0.0	
42+00.00	43+00.00	0.0	88.6	0.0	97.4	0.0	37.1	0.0	32.0	0.0	75.3	0.0	82.7	0.0	0.2	0.0	4.8	0.0	75.1	0.0	78.0	0.0	0.0	0.0	0.0	0.0	
43+00.00	43+12.79	0.0	14.8	0.0	16.6	0.0	4.6	0.0	4.6	0.0	12.6	0.0	14.1	0.0	0.1	0.0	0.6	0.0	12.5	0.0	13.5	0.0	0.0	0.0	0.0	0.0	
43+12.79	44+00.00	0.0	89.9	0.0	109.5	0.0	37.3	0.0	9.9	0.0	76.4	0.0	93.1	0.0	30.9	0.0	3.1	0.0	45.5	0.0	90.0	0.0	0.0	0.0	0.0	0.0	
44+00.00	45+00.00	0.0	119.7	0.0	195.5	0.0	47.9	0.0	53.0	0.0	101.7	0.0	166.2	0.0	31.2	0.0	47.1	0.0	70.5	0.0	119.1	0.0	0.0	0.0	0.0	0.0	
45+00.00	46+00.00	5.6	112.1	0.0	171.3	8.0	53.0	0.0	15.4	4.8	95.3	0.0	145.6	0.4	43.4	0.0	38.9	4.4	52.0	0.0	106.7	0.0	0.0	0.0	0.0	0.0	
46+00.00	47+00.00	2.5	126.6	0.0	129.2	19.0	39.4	0.0	43.4	2.1	107.6	0.0	109.8	16.5	32.4	0.0	113.1	-14.4	75.2	0.0	-3.3	0.0	0.0	0.0	0.0	0.0	
47+00.00	48+00.00	10.0	120.8	0.0	84.0	40.6	63.1	0.0	20.8	8.5	102.7	0.0	71.4	48.9	17.9	0.0	93.2	-40.4	84.8	0.0	-21.8	0.0	0.0	0.0	0.0	0.0	
48+00.00	49+00.00	2.5	72.4	0.0	32.2	19.0	10.4	0.0	11.5	2.1	61.6	0.0	27.4	16.5	1.7	32.6	68.0	-14.4	59.8	-32.6	-40.6	0.0	0.0	0.0	0.0	0.0	
49+00.00	50+00.00	105.5	87.8	18.1	17.2	67.1	66.6	10.3	9.6	89.6	74.6	15.4	14.6	49.0	32.5	34.8	54.3	40.7	42.2	-19.4	-39.7	0.0	0.0	0.0	0.0	0.0	
50+00.00	51+00.00	74.1	20.6	11.1	0.0	29.8	29.8	8.4	2.4	63.0	17.5	9.5	0.0	0.4	33.2	66.7	0.0	62.6	-15.7	-57.2	0.0	0.0	0.0	0.0	0.0	0.0	
51+00.00	52+00.00	149.3	44.7	19.8	0.0	59.7	63.0	17.4	5.7	126.9	38.0	16.8	0.0	0.9	59.7	72.4	0.0	126.1	-21.7	-55.5	0.0	0.0	0.0	0.0	0.0	0.0	
52+00.00	53+00.00	79.6	44.4	11.1	0.0	47.7	46.9	19.4	7.0	67.7	37.8	9.5	0.0	8.4	53.8	93.8	0.0	59.3	-16.0	-84.3	0.0	0.0	0.0	0.0	0.0	0.0	
53+00.00	54+00.00	52.3	94.6	1.7	0.0	25.2	61.4	7.1	1.4	44.5	80.4	1.4	0.0	3.0	55.9	87.7	0.0	41.4	24.5	-86.2	0.0	0.0	0.0	0.0	0.0	0.0	
54+00.00	55+00.00	17.3	48.7	0.0	0.0	28.5	35.9	14.8	10.3	14.7	41.4	0.0	0.0	8.3	40.7	98.2	0.0	6.5	0.7	-98.2	0.0	0.0	0.0	0.0	0.0	0.0	
55+00.00	56+00.00	17.2	88.6	0.5	0.0	12.3	50.7	1.2	3.2	14.6	75.3	0.4	0.0	3.0	56.0	82.3	0.0	11.6	19.3	-81.9	0.0	0.0	0.0	0.0	0.0	0.0	
56+00.00	57+00.00	22.3	27.3	1.4	0.0	22.7	39.1	3.8	17.8	18.9	23.2	1.2	0.0	0.7	85.4	72.7	0.0	18.2	-62.2	-71.5	0.0	0.0	0.0	0.0	0.0	0.0	
57+00.00	58+00.00	17.7	75.3	45.8	0.0	23.2	39.9	1.2	15.3	15.0	64.0	38.9	0.0	3.8	37.5	43.6	0.0	11.2	26.5	-4.7	0.0	0.0	0.0	0.0	0.0	0.0	
58+00.00	59+00.00	16.9	61.2	59.3	0.0	23.9	31.3	0.0	24.1	14.4	52.0	50.4	0.0	0.8	66.0	46.8	0.0	13.6	-14.0	3.6	0.0	0.0	0.0	0.0	0.0	0.0	
59+00.00	60+00.00	4.6	119.4	102.5	0.0	10.9	29.6	0.0	10.7	3.9	101.5	87.1	0.0	3.4	1.3	23.2	0.0	0.5	100.2	63.9	0.0	0.0	0.0	0.0	0.0	0.0	
60+00.00	60+07.50	0.5	4.4	4.3	0.0	0.9	0.8	0.0	0.9	0.4	3.7	3.7	0.0	0.0	0.1	0.9	0.0	0.4	3.7	2.7	0.0	0.0	0.0	0.0	0.0	0.0	
60+07.50		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
STAGE TOTALS		577.9	1490.9	275.6	895.4	438.6	799.7	83.6	315.2	491.2	1267.3	234.3	761.1	164.2	679.9	755.7	424.3	327.0	587.4	-521.4	336.8	0.0	0.0	0.0	0.0		
GATES ST (CRYSTAL LAKE)																											
30+50.00	30+59.04	0.0	15.5	0.0	0.0	0.0	6.1	0.0	0.0	0.0	13.2	0.0	0.0	0.0	5.6	0.0	0.0	0.0	7.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
30+59.04	31+00.00	0.0	62.3	0.0	0.0	0.0	2.7	0.0	0.0	0.0	32.9	0.0	0.0	0.0	20.0	0.0	0.0	0.0	33.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
31+00.00	31+18.05	0.0	15.4	0.0	0.0	0.0	2.2	0.0	0.0	0.0	13.1	0.0	0.0	0.0	0.9	0.0	0.0	0.0	12.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
31+18.05		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
STAGE TOTALS		0.0	93.2	0.0	0.0	0.0	33.0	0.0	0.0	0.0	79.2	0.0	0.0	0.0	26.5	0.0	0.0	0.0	0.0	52.7	0.0	0.0	0.0	0.0	0.0		
WALKUP RD (CRYSTAL LAKE)																											
43+52.52	43+72.57	0.0	36.0	0.0	0.0	0.0	11.3	0.0	0.0	0.0	30.6	0.0	0.0	0.0	14.5	0.0	0.0	0.0	16.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
43+72.57	44+00.00	0.0	89.0	0.0	0.0	0.0	39.0	0.0	0.0	0.0	75.7	0.0	0.0	0.0	29.0	0.0	0.0	0.0	46.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
44+00.00	45+00.00	0.0	220.1	0.0	0.0	0.0	133.8	0.0	0.0	0.0	187.1	0.0	0.0	0.0	111.5	0.0	0.0	0.0	75.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
45+00.00	46+00.00	0.0	406.0	0.0	0.0	0.0	149.7	0.0	0.0	0.0	345.1	0.0	0.0	0.0	35.3	0.0	0.0	0.0	309.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
46+00.00	47+00.00	0.0	479.5	0.0	0.0	0.0	227.6	0.0	0.0	0.0	407.6	0.0	0.0	0.0	25.1	0.0	0.0	0.0	382.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
47+00.00	48+00.00	0.0	193.9	0.0	0.0	0.0	95.5	0.0	0.0	0.0	154.8	0.0	0.0	0.0	21.8	0.0	0.0	0.0	143.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
48+00.00	49+00.00	0.0	254.4	0.0	0.0	0.0	109.1	0.0	0.0	0.0	216.2	0.0	0.0	0.0	9.7	0.0	0.0	0.0	206.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
49+00.00	50+00.00	0.0	222.1	0.0	0.0	0.0	120.6	0.0	0.0	0.0	188.8	0.0	0.0	0.0	15.3	0.0	0.0	0.0	173.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
50+00.00		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
STAGE TOTALS		0.0	1901.0	0.0	0.0	0.0	886.5	0.0	0.0	0.0	1615.8	0.0	0.0	0.0	262.3	0.0	0.0	0.0	0.0	1353.6	0.0	0.0	0.0	0.0	0.0		
WALKUP RD (CRYSTAL LAKE) Drywell Park																											
44+00.00		0.0	280.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	238.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	238.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
STAGE TOTALS		0.0	280.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	238.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	238.0	0.0	0.0	0.0	0.0	0.0		
WALKUP RD (MCHENRY)																											
50+00.00	51+00.00	79.1	0.0	64.3	64.6	36.9	0.0	30.6	11.0	67.2	0.0	54.6	55.0	0.5	0.0	12.4	34.0	66.8	0.0	42.3							