F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FP	MCHENRY	292	155
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 63522

SCHEDULE OF EXISTING SIGNS

SIGN ID	ROAD	EXISTING LOCATION STATION	EXISTING LOCATION OFFSET +:RT, -:LT	RELOCATED STATION	RELOCATED OFFSET	SIGN DESCRIPTION	MUTCD CODE	GROUND MOUNTING TYPE	HEIGHT FT	WIDTH FT	AREA SQ. FT	PROP. ACTION	PANEL TYPE	REMOV SIN PAN ASSY TA 72400100	REMOV SIN PAN ASSY TB 72400200	RELOCATE SIGN PANEL TY 1 72400710	RELOCATE SIGN PANEL TY 2 72400720
T-1A	IL RTE. 176	47+53	24	45+53	36.8	DOWNTOWN DISTRICT	CUSTOM	TELESCOPING	1.50	3.00	4.50	RELOCATE	1	1.00		4.50	
T-1B	IL RTE. 176	47+53	24	45+53	36.8	RIGHT ARROW	CUSTOM		1.50	2.00	3.00	RELOCATE	1			3.00	
T-2A	IL RTE. 176	48+54	23	48+44	49.1	METRA	CUSTOM	TELESCOPING	3.00	2.50	7.50	RELOCATE	1		1.00	7.50	
T-2B	IL RTE. 176	48+54	23	48+44	49.1	RIGHT ARROW	CUSTOM		1.50	2.00	3.00	RELOCATE	1			3.00	
T-3	IL RTE. 176	51+78	23			SPEED LIMIT 30	R2-1	TELESCOPING	3.00	2.50	7.50	REMOVE	1	1.00			
T-4A	IL RTE. 176	52+15	27	51+83	34.1	STREET SIGN (THIRD ST)	CUSTOM	METAL POST	0.50	2.00	1.00	RELOCATE	1	1.00		1.00	
T-4B	IL RTE. 176	52+15	27	51+83	34.1	STREET SIGN (TERRA COTTA AVE)	CUSTOM	METAL POST	0.50	3.00	1.50	RELOCATE	1			1.50	
T-5	IL RTE. 176	52+61	38			STOP SIGN	R1-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00			
T-6	IL RTE. 176	56+17	59	56+10	73.4	NO PARKING, THIS SIDE	CUSTOM	TELESCOPING	1.50	1.00	1.50	RELOCATE	1	1.00		1.50	
T-7	IL RTE. 176	56+49	40			STOP SIGN	R1-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00			
T-8A	IL RTE. 176	56+58	26	56+84	29.8	STREET SIGN (SECOND ST)	CUSTOM	METAL POST	0.50	2.00	1.00	RELOCATE	1	1.00		1.00	
T-8B	IL RTE. 176	56+58	26	56+84	29.8	STREET SIGN (TERRA COTTA AVE)	CUSTOM	METAL POST	0.50	3.00	1.50	RELOCATE	1			1.50	
T-9	IL RTE. 176	59+71	37			STOP SIGN	R1-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00			
T-10A	IL RTE. 176	59+75	33	59+84	34.2	STREET SIGN (FIRST ST)	CUSTOM	MEATAL POST	0.50	2.00	1.00	RELOCATE	1	1.00		1.00	
T-10B	IL RTE. 176	59+75	33	59+84	34.2	STREET SIGN (TERRA COTTA AVE)	CUSTOM	METAL POST	0.50	3.00	1.50	RELOCATE	1			1.50	
T-11	IL RTE. 176	60+01	24			SPEED LIMIT 30	R2-1	TELESCOPING	3.00	2.50	7.50	REMOVE	1	1.00			
T-12A	IL RTE. 176	62+02	24			DOWNTOWN & RIGHT ARROW	CUSTOM	TELESCOPING	2.00	2.50	5.00	REMAIN	1				
T-12B	IL RTE. 176	62+02	24			NATURE CENTER & LEFT ARROW	CUSTOM	TELESCOPING	2.50	2.00	5.00	REMAIN	1				
T-13A	IL RTE. 176	61+72	-25			ILLINOIS SHAPE, LAND OF LINCOLN	CUSTOM	WOODEN POST	3.00	2.50	7.50	REMAIN	1				
T-13B	IL RTE. 176	61+72	-25			ADOPT A HIGHWAY	CUSTOM	WOODEN POST	1.50	2.50	3.75	REMAIN	1				
T-13C	IL RTE. 176	61+72	-25			KEEP ILLINOIS CLEAN	CUSTOM	WOODEN POST	3.00	3.00	9.00	REMAIN	1				
T-14	IL RTE. 176	58+84	-23			SPEED LIMIT 30	R2-1	TELESCOPING	3.00	2.50	7.50	REMOVE	1	1.00			
T-15	IL RTE. 176	48+03	-31			SPEED LIMIT 35	R2-1	TELESCOPING	3.00	2.50	7.50	REMOVE	1	1.00			
T-16	IL RTE. 176	47+84	-57			PREMIER COMMERCIAL REALTY, NOW LEASING	CUSTOM	WOOD POSTS	4.00	8.00	32.00	REMAIN	3				
T-17	IL RTE. 176	45+55	-42			RIGHT TURN ONLY	R3-5R	TELESCOPING	3.00	2.50	7.50	REMOVE	1	1.00			
T-18	IL RTE. 176	45+24	-70			PREMIER COMMERCIAL REALTY, NOW LEASING	CUSTOM	WOOD POSTS	4.00	8.00	32.00	REMAIN	3				
T-19	IL RTE. 176	44+85	-59			STOP SIGN	R1-1	TELESCOPING	2.50	2.50	5.20	REMOVE	1	1.00			
T-20	IL RTE. 176	44+78	-75			NORTHSIDE CENTER 7 ELEVEN, 24 HOURS	CUSTOM	FIBER GLASS / METAL	7.00	7.00	49.00	REMAIN	3				
T-21A	IL RTE. 176	44+35	-41			RIGHT TURN ONLY	R3-5R	TELESCOPING	2.50	2.50	6.25	REMOVE	1	1.00			
T-21B	IL RTE. 176	44+35	-41	42+26	32.0	NO PARKING ANY TIME	CUSTOM	TELESCOPING	1.50	1.00	1.50	RELOCATE	1			1.50	
T-22	IL RTE. 176	43+75	-85			PRIVATE DRIVE, NO TURN AROUND	CUSTOM	TELESCOPING	3.00	2.50	7.50	REMAIN	1				
													SUBTOTALS	15.00	1.00	28.50	0.00
W-1	WALKUP AVENUE	43+10	30			WARNING $500 FINE, RAIL ROAD CROSSING	CUSTOM	UTILITY POLE	2.00	1.50	3.00	REMAIN	1				
W-2	WALKUP AVENUE	43+50	38			STOP SIGN	R1-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00			
W-3A	WALKUP AVENUE	43+58	33	43+72	25.2	STREET SIGN (RAILROAD ST)	CUSTOM	METAL POST	0.75	3.50	2.63	RELOCATE	1	1.00		2.63	
W-3B	WALKUP AVENUE	43+58	33	43+72	25.2	STREET SIGN (WALKUP AVE)	CUSTOM	METAL POST	0.75	3.50	2.63	RELOCATE	1			2.63	
W-4	WALKUP AVENUE	43+89	23	44+84	30.5	WEIGHT LIMIT 12 TONS	R12-1	TELESCOPING	2.00	1.50	3.00	RELOCATE	1	1.00		3.00	
W-5A	WALKUP AVENUE	46+74	21	46+32	35.0	DO NOT BLOCK INTERSECTION	R10-7	TELESCOPING	2.50	2.00	5.00	RELOCATE	1	1.00		5.00	
W-5B	WALKUP AVENUE	46+74	21	46+32	35.0	CRIME STOPPERS	CUSTOM		1.50	1.00	1.50	RELOCATE	1			1.50	
W-6	WALKUP AVENUE	47+33	39			STOP SIGN	R1-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00			
W-7A	WALKUP AVENUE	47+59	23	47+23	34.5	STREET SIGN (GATES ST)	CUSTOM	METAL POST	0.75	2.50	1.88	RELOCATE	1	1.00		1.88	
W-7B	WALKUP AVENUE	47+59	23	47+23	34.5	STREET SIGN (WALKUP AVE)	CUSTOM	METAL POST	0.75	3.50	2.63	RELOCATE	1			2.63	
W-8	WALKUP AVENUE	47+77	22			LEFT TURN ONLY (LEFT), THRU OR RIGHT TURN (RIGHT)	R3-8L	TELESCOPING	2.50	2.50	6.25	REMOVE	1	1.00			
W-9	WALKUP AVENUE	48+41	24	48+47	35.0	NO PARKING, ANY TIME	CUSTOM	TELESCOPING	1.50	1.00	1.50	RELOCATE	1	1.00		1.50	
W-10	WALKUP AVENUE	49+50	25			FOLDING STOP	R1-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00			
W-84	WALKUP AVENUE	49+61	-37			FOLDING STOP SIGN	R1-1	TRAFFIC POST	3.00	3.00	7.45	•	1				
W-85A	WALKUP AVENUE	49+44	-29			STREET SIGN (TERRA COTTA AVE)	CUSTOM	TRAFFIC POST	0.50	2.50	1.25	•	1				
W-85B	WALKUP AVENUE	49+44	-29			STREET SIGN (WALKUP AVE)	CUSTOM	TRAFFIC POST	0.50	2.50	1.25	•	1				
W-86	WALKUP AVENUE	48+99	-21			THROUGH TRAFFIC (RIGHT), LEFT TURN ONLY (LEFT)	CUSTOM	TELESCOPING	2.50	2.50	6.25	REMOVE	1	1.00			
W-87A	WALKUP AVENUE	48+21	-21	47+75	-35.7	WEIGHT LIMIT 12 TONS	R12-1	TELESCOPING	2.50	2.00	5.00	RELOCATE	1	1.00		5.00	
W-87B	WALKUP AVENUE	48+21	-21	47+75	-35.7	CRIME STOPPERS	CUSTOM		1.50	1.00	1.50	RELOCATE	1			1.50	
W-88	WALKUP AVENUE	47+27	-23			RAILROAD CROSSING	W10-1	TELESCOPING	2.50	DIA.	4.92	REMOVE	1	1.00			
W-89	WALKUP AVENUE	46+67	-35			STOP SIGN	R12-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00			
W-90A	WALKUP AVENUE	46+63	-26	46+42	-36.5	STREET SIGN (BURDENT DR)	CUSTOM	METAL POST	0.75	3.50	2.63	RELOCATE	1	1.00		2.63	
W-90B	WALKUP AVENUE	46+63	-26	46+42	-36.5	STREET SIGN (WALKUP AVE)	CUSTOM	METAL POST	0.75	3.50	2.63	RELOCATE	1			2.63	
W-91	WALKUP AVENUE	43+46	-33			CAUTION GAS PIPELINE	CUSTOM	TELESCOPING	0.80	1.00	0.80	REMAIN	1				
W-92A	WALKUP AVENUE	43+43	-20	43+54	-21.6	DO NOT STOP ON TRACKS	R8-8	TELESCOPING	2.50	2.00	5.00	RELOCATE	1	1.00		5.00	
W-92B	WALKUP AVENUE	43+43	-20	43+54	-21.6	WARNING $500 FINE, RAIL ROAD CROSSING	CUSTOM		2.00	1.50	3.00	RELOCATE	1			3.00	
W-93	WALKUP AVENUE	43+41	-31			WARNING, BURIED FIBER OPTIC CABLE	CUSTOM	METAL POST	2.00	1.50	3.00	REMAIN	1				
													SUBTOTALS	15.00	0.00	40.50	0.00

• SEE NOTE 4 ON SHEET 173 FOR PROPOSED ACTION.

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SIGNING SCHEDULE
EXISTING CONDITIONS
SHEET 1 OF 3

SCALE: N.T.S. DRAWN BY: MN

DATE: 04/15/11 CHECKED BY: MM

TENG

TENG & ASSOCIATES, INC.
ENGINEERS&ARCHITECTS&PLANNERS
200 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE 312/616-0600

..\S02A003.DGN..\S02A003.DGN..\B099A00L.DGN STANKURJ
4-14-2011 15:43:48 \\FS-0046\AMVAULT\D-TRANS.07\2202\300-03\CIVIL\CAD\02_CONTRACT\A_TENG\SHEET\S02A009.SHT
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63