

SCHEDULE OF EXISTING SIGNS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-02-FP	MCHENRY	292	157
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT NO: 63522				

SIGN ID	ROAD	EXISTING LOCATION		RELOCATED		SIGN DESCRIPTION	MUTCD CODE	GROUND MOUNTING TYPE	HEIGHT FT	WIDTH FT	AREA SQ. FT	PROP. ACTION	PANEL TYPE	REMOV SIN	REMOV SIN	RELOCATE SIGN	RELOCATE SIGN						
		STATION	OFFSET +RT, -LT	STATION	OFFSET									PAN ASSY TA 72400100	PAN ASSY TB 72400200	PANEL TY 1 72400710	PANEL TY 2 72400720						
W-54B	WALKUP ROAD	236+43	-82			WARNING NEIGHBORHOOD WATCH	CUSTOM	TELESCOPING	2.00	1.50	3.00	REMAIN	1										
W-55	WALKUP ROAD	236+40	-82			WEIGHT LIMIT 5 TONS	R12-1	TELESCOPING	2.50	2.00	5.00	REMAIN	1										
W-56	WALKUP ROAD	235+93	-35			STOP SIGN	R1-1	WOODEN POST	3.00	3.00	7.45	REMOVE	1	1.00									
W-57	WALKUP ROAD	230+60	-28			SPEED LIMIT 45	R2-1	TELESCOPING	3.00	2.50	7.50	REMOVE	1	1.00									
W-58	WALKUP ROAD	228+95	-54			STREET SIGN (COACHLIGHT RIDGE)	CUSTOM	WOOD POSTS	8.00	2.50	20.00	REMAIN	2										
W-59	WALKUP ROAD	228+93	-34	228+06	-27.0	STREET SIGN (ANVIL RD)	CUSTOM	TELESCOPING	2.00	0.75	1.50	RELOCATE	1	1.00		1.50							
W-60	WALKUP ROAD	228+75	-60	228+77	-90.9	WEIGHT LIMIT 5 TONS	R12-1	TELESCOPING	2.50	2.00	5.00	RELOCATE	1	1.00		5.00							
W-61A	WALKUP ROAD	228+81	-171			SPEED LIMIT 25	R2-1	TELESCOPING	2.50	2.00	5.00	REMAIN	1										
W-61B	WALKUP ROAD	228+81	-171			NO PARKING ON TOWNSHIP ROADS	CUSTOM	TELESCOPING	2.00	1.50	3.00	REMAIN	1										
W-62	WALKUP ROAD	228+24	-40			STOP SIGN	R1-1	WOODEN POST	3.00	3.00	7.45	REMOVE	1	1.00									
W-63	WALKUP ROAD	83+54	-56			HERITAGE ESTATE	CUSTOM	WOODEN POST	4.00	4.00	16.00	REMAIN	2										
W-64	WALKUP ROAD	83+34	-96			SPEED LIMIT 25	R2-1	TELESCOPING	2.50	2.00	5.00	REMAIN	1										
W-65A	WALKUP ROAD	82+88	-38			STREET SIGN (RED BIRD LN)	CUSTOM	TELESCOPING	1.00	3.00	3.00	REMAIN	1										
W-65B	WALKUP ROAD	82+88	-38			STOP SIGN	R1-1	TELESCOPING	3.00	3.00	7.45	REMAIN	1										
W-66	WALKUP ROAD	79+13	-28			SPEED LIMIT 40	R2-1	TELESCOPING	3.00	2.00	6.00	REMAIN	1										
W-67A	WALKUP ROAD	74+98	-16	74+96	-24.6	CITY OF CRYSTAL LAKE	CUSTOM	TELESCOPING	0.75	2.50	1.88	RELOCATE	1	1.00		1.88							
W-67B	WALKUP ROAD	74+98	-16	74+96	-24.6	OUTSIDE WATER USAGE, CONSERVATION	CUSTOM	TELESCOPING	2.50	2.50	6.25	RELOCATE	1			6.25							
W-68	WALKUP ROAD	74+17	-32			ADMITTANCE FOR CHURCH PURPOSES ONLY	CUSTOM	TELESCOPING	1.50	1.00	1.50	REMAIN	1										
W-69A	WALKUP ROAD	63+59	-68			SPEED LIMIT 30	R2-1	TELESCOPING	2.50	2.00	5.00	REMOVE	1	1.00									
W-69B	WALKUP ROAD	63+59	-68	63+59	-71.1	WARNING NEIGHBORHOOD WATCH	CUSTOM	TELESCOPING	1.00	1.50	1.50	RELOCATE	1			1.50							
W-70	WALKUP ROAD	63+14	-68			STOP SIGN	R1-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00									
W-71A	WALKUP ROAD	63+13	-52	62+98	-42.2	STREET SIGN (WALKUP AVE)	CUSTOM	LIGHT POLE	0.75	4.00	3.00	RELOCATE	1	1.00		3.00							
W-71B	WALKUP ROAD	63+13	-52	62+98	-42.2	STREET SIGN (TALISMON DR)	CUSTOM	LIGHT POLE	0.75	4.00	3.00	RELOCATE	1			3.00							
W-72	WALKUP ROAD	61+99	-19			SPEED LIMIT 30	R2-1	TELESCOPING	3.00	2.50	7.50	REMOVE	1	1.00									
W-73A	WALKUP ROAD	59+86	-20	59+90	-34.9	STREET SIGN (PARKVIEW CT)	CUSTOM	METAL POST	0.75	4.00	3.00	RELOCATE	1	1.00		3.00							
W-73B	WALKUP ROAD	59+86	-20	59+90	-34.9	STREET SIGN (WALKUP AVE)	CUSTOM	METAL POST	0.75	4.00	3.00	RELOCATE	1			3.00							
W-74A	WALKUP ROAD	59+66	-70			SLOW CHILDREN	W9-11	TELESCOPING	2.00	1.50	3.00	REMAIN	1										
W-74B	WALKUP ROAD	59+66	-70			SIX HOUR PARKING	CUSTOM	TELESCOPING	1.50	1.00	1.50	REMAIN	1										
W-75	WALKUP ROAD	59+31	-45			STOP SIGN	R1-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00									
W-76	WALKUP ROAD	56+55	-32			TRAFFIC SIGNAL AHEAD	W3-3	WOODEN POST	3.00	3.00	9.00	REMOVE	1	1.00									
W-77	WALKUP ROAD	55+53	-38			DO NOT BLOCK INTERSECTION	R10-7	WOODEN POST	2.50	2.00	5.00	REMAIN	1										
W-78A	WALKUP ROAD	55+30	-42	55+40	-40.8	STREET SIGN (WALKUP AVE)	CUSTOM	METAL POST	0.75	3.00	2.25	RELOCATE	1	1.00		2.25							
W-78B	WALKUP ROAD	55+30	-42	55+40	-40.8	STREET SIGN (CRYSTAL RIDGE)	CUSTOM	METAL POST	0.75	4.00	3.00	RELOCATE	1			3.00							
W-79	WALKUP ROAD	54+96	-57			KEEP RIGHT OF MEDIAN AHEAD	R4-7	METAL POST	2.00	1.50	3.00	REMOVE	1	1.00									
W-80	WALKUP ROAD	54+65	-49			STOP SIGN	R1-1	TELESCOPING	3.00	3.00	7.45	REMOVE	1	1.00									
W-81	WALKUP ROAD	52+56	-25	53+25	-43.0	DOWNTOWN, LEFT ARROW	CUSTOM	TELESCOPING	2.00	2.50	5.00	RELOCATE	1	1.00		5.00							
W-82	WALKUP ROAD	51+30	-47			PROFESSIONAL BUILDING, LAW OFFICES	CUSTOM	WOOD POSTS	3.00	3.60	10.80		2										
W-83	WALKUP ROAD	50+25	-57			FOLDING STOP SIGN	R1-1	TRAFFIC POST	3.00	3.00	7.45	*	1										
SU-1	SHARED USE PATH	67+63	-			NO MOTOR VEHICLES	R5-3	METAL POST	2.00	2.00	4.00	REMOVE	1	1.00									
SU-2	SHARED USE PATH	80+46	-			STOP SIGN	R1-1	METAL POST	1.50	1.50	2.25	REMAIN	1										
SU-3	SHARED USE PATH	81+36	-			STOP SIGN	R1-1	METAL POST	1.50	1.50	2.25	REMAIN	1										
Z-100A	WALKUP ROAD	75+00	-	75+00	23.0	BICYCLE	W11-1	TELESCOPING	2.50	2.50	6.25	RELOCATE	1	1.00		6.25							
Z-100B	WALKUP ROAD	75+00	-	75+00	23.0	AHEAD	W16-9P		1.00	2.50	2.50	RELOCATE	1			2.50							
Z-101	EXISTING BIKE PATH	76+45	-	76+45	-30.0	STOP SIGN	R1-1	TELESCOPING	1.50	1.50	2.25	RELOCATE	1	1.00		2.25							
Z-102A	WALKUP ROAD	76+47	-	76+47	23.0	BICYCLE	W11-1	TELESCOPING	2.50	2.50	6.25	RELOCATE	1	1.00		6.25							
Z-102B	WALKUP ROAD	76+47	-	76+47	23.0	DOWN LEFT ARROW	W16-7PL		1.00	2.50	2.50	RELOCATE	1			2.50							
Z-103A	WALKUP ROAD	76+63	-	76+63	-24.0	BICYCLE	W11-1	TELESCOPING	2.50	2.50	6.25	RELOCATE	1	1.00		6.25							
Z-103B	WALKUP ROAD	76+63	-	76+63	-24.0	DOWN LEFT ARROW	W16-7PL		1.00	2.50	2.50	RELOCATE	1			2.50							
Z-104	EXISTING BIKE PATH	76+65	-	76+65	39.0	STOP SIGN	R1-1	TELESCOPING	1.50	1.50	2.25	RELOCATE	1	1.00		2.25							
Z-105A	WALKUP ROAD	78+22	-	78+22	-24.0	BICYCLE	W11-1	TELESCOPING	2.50	2.50	6.25	RELOCATE	1	1.00		6.25							
Z-105B	WALKUP ROAD	78+22	-	78+22	-24.0	AHEAD	W16-9P		1.00	2.50	2.50	RELOCATE	1			2.50							
												SUBTOTALS	48.00	7.00	145.25	0.00							
												TOTAL			1010.88		78.00	8.00	214.25	0.00			

\S:\02\003\004\150204003\004_18099A00100N
 4-14-2004 15:55:54
 \S:\5-004\AMVA\1.0-TRANS.07\2202\300-03\CIVIL\CAD\02 CONTRACT\VA_TENG\SHEET\SIG2\SIG2.SHT
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
 WALKUP ROAD F.A.U. 0085

SIGNING SCHEDULE
EXISTING CONDITIONS
SHEET 3 OF 3

SCALE: N.T.S. DRAWN BY: MN
 DATE: 04/15/11 CHECKED BY: MM

TENG

TENG & ASSOCIATES INC.
 600 N. MICHIGAN AVE. CHICAGO, IL 60611
 TELEPHONE: 312.466.4000