



* SEE TYPICAL SECTIONS FOR THICKNESS AND MATERIALS

NOTES:

1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

SEQUENCE OF CONSTRUCTION (MILLING FIRST)

1. MILL HMA FIRST IF THERE IS AT LEAST 4 1/2 INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| | | | |
|--|----------------------------|--------------------|-----------------------------|
| FILE NAME = c:\projects\distatd22x34\bd22.dgn | USER NAME = bouerd1 | DESIGNED - R. SHAH | REVISED - A. ABBAS 04-27-98 |
| | | DRAWN - | REVISED - R. BORO 01-01-07 |
| | PLOT SCALE = 60,000' / IN. | CHECKED - | REVISED - R. BORO 09-04-07 |
| | PLOT DATE = 12/27/2008 | DATE - 10-25-94 | REVISED - K. ENG 10-27-08 |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

| | | | |
|--|-------------------------|------|---------|
| PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT | | | |
| SCALE: NONE | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA. |

| | | | | |
|---|---------------------------|----------------|--------------------|-----------------|
| F.A.U. RTE. 1046 | SECTION 11-00109-00-RS | COUNTY COOK | TOTAL SHEETS 20 | SHEET NO. 13 |
| BD400-04 (BD-22) | | | CONTRACT NO. 63602 | |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | | |