STORM SEWER

STATION	OFFSET (FT)	TYPE	STANDARD	STORM SEWERS: WATER MAIN REQUIREMENTS 12"	15"	30"	42"	CLASS A, TYPE 1 12"	15"	30"	30" EQRS	CLASS A, TYPE 2 12"	15"	42"	CLASS B, TYPE 1 6"	12"	15"	INLETS TYPE A: TY. 23 FRAME & GRATE	TYPE 8 GRATE	INLETS TYPE B: TY. 23 FRAME & GRATE	WITH SPECIAL FRAME & GRATE	MANHOLES TYPE A 4' DIA.: TY. 1 FRAME CLOSED LID	TY. 23 FRAME & GRATE	TYPE 8 GRATE	MANHOLES TYPE A 5' DIA.: TY. 1 FRAME CLOSED LID	TY. 23 FRAME & GRATE	TYPE 8 GRATE	WITH SPECIAL FRAME & GRATE	MANHOLES TYPE A 6' DIA.: WITH SPECIAL FRAME & GRATE	WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	CATCH BASINS TYPE C: TY. 23 FRAME & GRATE	TYPE 8 GRATE	WITH SPECIAL FRAME & GRATE	CATCH BASINS TYPE D 3' DIA.: TY. 1 FRAME CLOSED LID	TY. 23 FRAME & GRATE	WITH SPECIAL FRAME & GRATE	STORM WATER TREATMENT STRUCTURES, 900 GALLONS	P.R.C. FLARED END SECTION, 12"	TRENCH BACKFILL
97+53.70	28.00 LT	CB	602011																												1								
		SS						18																															1
97+35.00	28.70 LT	MH	602401, 604001, 602601																			1																	
		SS										54																											11
97+35.00	28.30 RT	INLET	602306, 604086																	1																			
		SS										4																											0
97+35.00	35.90 RT	MH	602401, 604001, 602601																					1															
		SS												66																									0
98+03.00	28.30 RT	CB	602011, 604086																											1									
		SS										6																											0
98+03.00	35.90 RT	MH	602401, 604001, 602601																					1															
		SS												106																									54
99+11.20	34.30 RT	MH	602406, 604001, 602601																										1										
101+27.30	33.00 RT	MH	604001, 602601																																	1			
WALKER AVE. NON CASS																																							
		SS			16																																		7
600+48.20	35.80 LT	MH	604001, 602601																																	1			
		SS											22																										3
600+67.90	14.60 RT	INLET	602301, 604086															1																					
		SS		28																																			10
600+69.20	14.50 LT	CB	602016, 604086																											1									
		SS										4																											0
600+69.50	20.40 LT	MH	602401, 604036, 602601																				1																
		SS							88																														9
601+60.30	17.00 LT	MH	602401, 604001, 602601																			1																	
CLARENDON HILLS RD. NON CASS																																							
701+19.50	11.30 LT	INLET	602301, 604086															1																					
		SS										22																											7
701+19.50	11.1 RT	CB	602016, 604086																											1									
		SS										4																											0
701+20.00	17.70 RT	MH	602401, 604001, 602601																					1															
		SS												278																									117
703+99.40	23.30 RT	MH	602401, 604001, 602601																					1															
		SS												44																									88
NON CASS SUB TOTAL				412.0	170.0	50.0	50.0	266.0	88.0	120.0	266.0	142.0	82.0	872.0	65.0	62.0	22.0	6.0	1.0	5.0	1.0	4.0	0.0	1.0	11.0	3.0	3.0	1.0	1.0	2.0	6.0	3.0	3.0	1.0	4.0	1.0	2.0	3.0	986.0
USE				412	170	50	50	266	88	120	266	142	82	872	65	62	22	6	1	5	1	4	0	1	11	3	3	1	1	2	6	3	3	1	4	1	2	3	986
TOTAL				736.0	170.0	50.0	50.0	462.0	88.0	120.0	266.0	376.0	82.0	872.0	65.0	86.0	22.0	10.0	1.0	9.0	1.0	7.0	1.0	1.0	11.0	3.0	3.0	1.0	1.0	2.0	11.0	3.0	4.0	1.0	10.0	2.0	3.0	3.0	1118.0
USE				736	170	50	50	462	88	120	266	376	82	872	65	86	22	10	1	9	1	7	1	1	11	3	3	1	1	2	11	3	4	1	10	2	3	3	1118

FILE NAME = V:\2791\2791q015.dgn	USER NAME = shughes	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 1.000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 5/19/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

C.H. 35 (55TH ST.)
SCHEDULES OF QUANTITIES

SCALE: N/A | SHEET NO. 9 OF 14 SHEETS | STA. N/A | TO STA. N/A

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1504	94-00302-00-FP	DU PAGE	240	26

CONTRACT NO. 63609

ILLINOIS FED. AID PROJECT