SEC. 10 T. 38 N. R. 11 E. 3RD PM

END MILLING & RESURFACING 50' LT.

EXISTING CURB & GUTTER TO BE REMOVED & PATCHED STA. 62+52 TO STA. 63+23

PROPOSED COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12 (SEE SHEET 141 (TYP.))

66' R.O.W.

RICHMOND AVE.

CHURCH #275

HSE #328

EXISTING TEMPORARY EASEMENT LINE (TYP.)

CONC BLOCK RET WALL

PROPOSED CONSTRUCTION LIMITS

PROPOSED 5' PCC SIDEWALK (TYP.)

EXISTING R.O.W. LINE (TYP.)

STA. 60+00

STA. 66+00

MATCH LINE

℄ SURVEY & ℄ CONSTRUCTION

C.H. 35 (55TH ST.) BIT

B-6.12 C&G

5' CONC SW

WOOD RETAINING WALL

PROPOSED CONSTRUCTION LIMITS

SEC. 15 T. 38 N. R. 11 E. 3RD PM

EXISTING PROFILE GRADE LINE

MILLING & RESURFACING CONSISTS OF THE FOLLOWING:
EXISTING HOT-MIX ASPHALT SURFACE REMOVAL, 3¾"
PROPOSED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 1½"
PROPOSED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70, 2¼"

60+00	60+50	61+00	61+50	62+00	62+50	63+00	63+50	64+00	64+50	65+00	65+50	66+00
757.11	756.05	755.22	754.46	753.82	753.14	752.56	752.06	751.43	750.93	750.61	750.46	750.17

PLAN: SURVEYED, PLOTTED, DRAWN, CHECKED, AUTHORIZED, ENGINEER, STRUCTURE NOTATIONS CHKD, DATE, BY, NOTE BOOK, NO.

PROFILE: SURVEYED, PLOTTED, DRAWN, CHECKED, AUTHORIZED, ENGINEER, STRUCTURE NOTATIONS CHKD, DATE, BY, NOTE BOOK, NO.

FILE NAME = v:\2791\2791p010.dgn	USER NAME = shughes	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 20.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 5/19/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

C.H. 35 (55TH ST.) PLAN & PROFILE

SCALE: H=20 V=5 | SHEET NO. 10 OF 17 SHEETS | STA. 60+00 | TO STA. 66+00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1504	94-00302-00-FP	DU PAGE	240	46
		CONTRACT NO. 63609		
		ILLINOIS FED. AID PROJECT		