

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY 90% FED 10% COUNTY	CONSTRUCTION TYPE CODE	
				0003 QUANTITY	0021 QUANTITY
20101400	NITROGEN FERTILIZER NUTRIENT	LBS	41.7	41.7	-
20101500	PHOSPHORUS FERTILIZER NUTRIENT	LBS	41.7	41.7	-
20101600	POTASSIUM FERTILIZER NUTRIENT	LBS	41.7	41.7	-
20101700	SUPPLEMENTAL WATERING	UNIT	146	146	-
20200100	EARTH EXCAVATION	CU YD	50	50	-
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2321	2321	-
20400800	FURNISHED EXCAVATION	CU YD	24.2	24.2	-
20800150	TRENCH BACKFILL	CU YD	11	11	-
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	2245	2245	-
25200110	SODDING, SALT TOLERANT	SQ YD	2245	2245	-
28000250	TEMPORARY EROSION CONTROL SEEDING	LBS	46.37	46.37	-
28000400	PERIMETER EROSION BARRIER	FEET	813	813	-
28000510	INLET FILTERS	EACH	15	15	-
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	730	730	-
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	35	35	-
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.3	2.3	-
40600300	AGGREGATE (PRIME COAT)	TON	11.3	11.3	-
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	9	-
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	77	77	-
40600990	TEMPORARY RAMP	SQ YD	14	14	-
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	50.4	50.4	-
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	632	632	-
42001300	PROTECTIVE COAT	SQ YD	437	437	-
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	75	75	-
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	5711	5711	-
42400800	DETECTABLE WARNINGS	SQ FT	119	119	-
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	4907	4907	-
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	170	170	-
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1894	1894	-

+ SPECIAL PROVISION
* SPECIALTY ITEM

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY 90% FED 10% COUNTY	CONSTRUCTION TYPE CODE	
				0003 QUANTITY	0021 QUANTITY
44000600	SIDEWALK REMOVAL	SO FT	5605	5605	-
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	300	300	-
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	256	256	-
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1811	1811	-
50901760	PIPE HANDRAIL	FOOT	48	48	-
550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	20	20	-
55100400	STORM SEWER REMOVAL 10"	FOOT	50	50	-
60211800	CATCH BASINS, TYPE D, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	-
60212813	CATCH BASINS, TYPE D, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	7	7	-
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	-
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	9	9	-
60404940	FRAMES AND GRATES, TYPE 23	EACH	2	2	-
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2	-
60500060	REMOVING INLETS	EACH	7	7	-
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1812	1812	-
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	-
67100100	MOBILIZATION	L SUM	1	1	-
* 70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	-
* 70300100	SHORT-TERM PAVEMENT MARKING	FOOT	849	849	-
* 70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	448	448	-
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10683	10683	-
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1688	1688	-
* 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	287	287	-
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	271	271	-
* 70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	1000	1000	-
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	95	95	-
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	172	172	-
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2852	2852	-
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	844	844	-

FILE NAME : F:\2010\ME10015_Roselle_DP\CDOT\CADD\Shets\04-S00-sh1-Roselle.dgn
 PLOT SCALE : 1/8"=1'-0"
 USER NAME : Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
 630.765.8110 voice, 630.839.2566 fax
 www.mps-il.com

MILLENNIA PROFESSIONAL SERVICES

DESIGNED	CJD	REVISED	-
DRAWN	CJD	REVISED	-
CHECKED	TVN	REVISED	-
DATE	5/23/2011	REVISED	-

**DUPAGE COUNTY
DEPARTMENT OF TRANSPORTATION**

**ROSELLE RD. & WALNUT ST.
INTERSECTION IMPROVEMENTS**

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.P. RTE. 364	SECTION 07-00184-12-CH	COUNTY DUPAGE	TOTAL SHEETS 49	SHEET NO. 4
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT				
CONTRACT NO. 63611				

F:\2010\ME10015_Roselle_DP\CDOT\CADD\Shets\04-S00-sh1-Roselle.dgn