

CODE NO.	ITEM	UNIT	CONSTR. CODE
			100% STATE
			ROADWAY
			0005 RURAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1262
40600300	AGGREGATE (PRIME COAT)	TON	19
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4
40600725	POLYMERIZED LEVELING BINDER (HAND METHOD), N50	TON	4
40600990	TEMPORARY RAMP	SQ YD	136
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	693
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	17
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	8220
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	26
48100100	AGGREGATE SHOULDERS, TYPE A	TON	30
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3129
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	313
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	140

\* SPECIALITY ITEMS

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RON WOODSHANK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\woodshankr1\d0268411\366845-shr-deta11.dgn	DRAWN - RON WOODSHANK	REVISED -	591			D3 INTERMITTENT RS 2012-1	DEKALB	12	3	
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -	CONTRACT NO. 66B45							
PLOT DATE = 6/13/2011	DATE -	REVISED -	SCALE: _____			SHEET NO. 1 OF 2 SHEETS	STA. 351+58 TO STA. 367+18	ILLINOIS FED. AID PROJECT		