

SCHEDULE OF QUANTITIES

PROTECTIVE COAT

LOCATION	SQYD
Parapet Wall Replacement Concrete & Surface of Concrete Joints	46
TOTAL	46

CONCRETE REMOVAL

LOCATION	CUYD
E. & W. Structure Joints & Parapets	29.5
TOTAL	29.5

CONCRETE SUPERSTRUCTURE

LOCATION	CUYD
E. & W. Structure Joints & Parapets	29.5
TOTAL	29.5

REINFORCEMENT BARS, EPOXY COATED

LOCATION	Pound
E. & W. Joint Replacements	3043
TOTAL	3043

BAR SPLICERS

LOCATION	EACH
E. & W. Joint Replacements	48
TOTAL	48

PREFORMED JOINT STRIP SEAL

LOCATION	FOOT
E. & W. Joint Replacements	194
TOTAL	194

MOBILIZATION

LOCATION	LSUM
Jobsite - SN.072-0154	1
TOTAL	1

CHANGEABLE MESSAGE SIGN

LOCATION	CALMO
Jobsite - SN.072-0154	2
TOTAL	2

PAVMT. MRKG. TAPE, TYPE III, 4"

LOCATION	FOOT
Jobsite - SN.072-0154	5055
TOTAL	5055

PVMT. MRKG. TAPE, TYPE III, 6"

LOCATION	FOOT
Jobsite - SN.072-0154	1025
TOTAL	1025

WORKZONE PVMT. MRKG. REM.

LOCATION	SQFT
Jobsite - SN.072-0154	1685
TOTAL	1685

TEMPORARY CONC. BARRIER

LOCATION	FOOT
Jobsite - SN.072-0154	925
TOTAL	925

RELOCATE TEMP. CONC. BARRIER

LOCATION	FOOT
Jobsite - SN.072-0154	925
TOTAL	925

EPOXY MRKG. - LINE, 4"

LOCATION	FOOT
Jobsite - SN.072-0154	921
TOTAL	921

PAVEMENT MARKING REMOVAL

LOCATION	SQFT
Jobsite - SN.072-0154	307
TOTAL	307

T. C. & PROTECTION (SPECIAL)

LOCATION	LSUM
Jobsite - SN.072-0154	1
TOTAL	1

WIDTH RESTRICTION SIGNING

LOCATION	LSUM
EB. Traffic Control	0.5
WB. Traffic Control	0.5
TOTAL	1

IMPACT ATTEN., TEMP. (NRD) TL2

LOCATION	EACH
Jobsite - SN.072-0154	4
TOTAL	4

IMPACT ATTEN., RELOC. (NRD) TL2

LOCATION	EACH
Jobsite - SN.072-0154	4
TOTAL	4

RAILROAD PROT. LIABILITY INS.

LOCATION	LSUM
Jobsite - SN.072-0154	1
TOTAL	1

S:\GEN\DRIFT\STD&PLNS\SQUAD BRIDGES\BRIDGE CONTRACTS\JOINTS\68685 SN072-0154 US150 ovr CNRR.dgn