

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	*	VAR	38	4
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

*** D4 SCOUR MITIGATION 2011**

SCHEDULE OF QUANTITIES			STRUCTURE NUMBER				
CODE NO.	ITEM	UNIT	055-0006	078-0003	090-0087	090-0092	090-0100
20300100	CHANNEL EXCAVATION	CU YD	53	52	0	0	0
25000300	SEEDING CLASS 3	ACRE	0.2	0.2	0.6	0	0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18	54	0	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18	54	0	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18	54	0	0
25100630	EROSION CONTROL BLANKET	SQ YD	90	90	137	0	133
28000400	PERIMETER EROSION BARRIER	FOOT	140	100	299	19	72
28100209	STONE RIPRAP, CLASS A5	TONS	1945	689	1850	117	449
28200200	FILTER FABRIC	SQ YD	997	316	1058	69	263
31102000	SUBBASE GRANULAR MATERIAL, TYPE C	CU YD	20	10	0	0	0
67100100	MOBILIZATION	L SUM	0.2	0.2	0.2	0.2	0.2
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	0.5	0.5	0	0	0
X0301852	DEWATERING STRUCTURE NO. 1	EACH	1	0	0	0	0
X0301853	DEWATERING STRUCTURE NO. 2	EACH	0	1	0	0	0
X0301854	DEWATERING STRUCTURE NO. 3	EACH	0	0	1	0	0
X0322587	CONSTRUCTION ACCESS	EACH	1	1	0	0	1
X0323689	REMOVE EXISTING EROSION CONTROL	L SUM	0	0	0	0.5	0.5

QUANTITIES NOT OTHERWISE SHOWN

ITEM	UNIT	TOTAL	DESCRIPTION
TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	SEE GENERAL NOTE #8

ITEM	UNIT	TOTAL	LOCATION
SEEDING, CLASS 3	ACRE	1.0	JOBSITE
NITROGEN FERTILIZER NUTRIENT	POUND	90	JOBSITE
PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	JOBSITE
POTASSIUM FERTILIZER NUTRIENT	POUND	90	JOBSITE
EROSION CONTROL BLANKET	SQ YD	450	JOBSITE
MOBILIZATION	L SUM	1	JOBSITE