

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE
				RDWY QUANTITY 0005
20200100	EARTH EXCAVATION	CU YD	603	603
20400800	FURNISHED EXCAVATION	CU YD	3,689	3,689
25000200	SEEDING, CLASS 2	ACRE	2.5	2.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	225	225
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	225	225
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	225	225
25000700	AGRICULTURAL GROUND LIMESTONE	TON	5.0	5.0
25100115	MULCH, METHOD 2	ACRE	2.5	2.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	250	250
28000500	INLET AND PIPE PROTECTION	EACH	8	8
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A, 6"	SQ YD	6,514	6,514
35501326	HOT MIX ASPHALT BASE COURSE, 10 1/2"	SQ YD	5,352	5,352
35501328	HOT-MIX ASPHALT BASE COURSE, 11"	SQ YD	1,391	1,391
35501334	HOT-MIX ASPHALT BASE COURSE, 12 1/2"	SQ YD	1,434	1,434
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13.4	13.4
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	476	476
40600990	TEMPORARY RAMP	SQ YD	356	356
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1,624	1,624
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	909	909
44004250	PAVED SHOULDER REMOVAL	SQ YD	4,599	4,599
48101200	AGGREGATE SHOULDERS, TYPE B	TON	872	872
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 18"	EACH	2	2
550A0090	STORM SEWERS, CLASS A, TYPE 1, 18"	FOOT	1,004	1,004
* 60108200	PIPE UNDERDRAINS, 6" (SPECIAL)	FOOT	132	132
60240366	INLETS, TYPE B, WITH MEDIAN INLET (604106)	EACH	4	4

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE
				RDWY QUANTITY 0005
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6' POSTS	FOOT	450.0	450.0
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) TANGENT	EACH	2	2
63200310	GUARDRAIL REMOVAL	FOOT	300.0	300.0
* 63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL	FOOT	725.0	725.0
63301990	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	3	3
63302700	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINALS, TYPE 6	EACH	3	3
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	8
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	856	856
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	282	282
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 5"	FOOT	238	238
* 78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	23	23
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8
* 78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	2	2
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,178	1,178
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	23	23
* X0325299	INLET MODIFICATION	EACH	2	2
* X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	5,052	5,052
* X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1	1

***SPECIALTY ITEM**

USER NAME : sparksgv	DESIGNED -	REVISED -	<p align="center">STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</p>	<p align="center">SUMMARY OF QUANTITIES</p>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE : 2.0000' / in.	DRAWN - BDM	REVISED -					1-72	(84-10-1)I-7	SANGAMON	41	3
PLOT DATE : Jun-08-2011 09:38:22AM	CHECKED - JSA	REVISED -					CONTRACT NO. 72E51				
	DATE - 7/15/09	REVISED -					ILLINOIS FED. AID PROJECT				
SCALE:			SHEET NO. OF SHEETS STA. TO STA.								