

SUMMARY OF QUANTITIES			100% STATE CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021	
				LIGHTING	
67100100	MOBILIZATION	L SUM	1	1	
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
80400100	ELECTRIC SERVICE INSTALLATION	EACH	3	3	
81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	649	649	
81603010	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	5012	5012	
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4003	4003	
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	28	28	
82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 60AMP	EACH	3	3	
83003600	LIGHT POLE, ALUMINUM, 45 FT. M. H., 15 FT. DAVIT ARM	EACH	28	28	
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	28	28	
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	112	112	
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	3	3	
84200804	REMOVAL OF POLE FOUNDATION	EACH	3	3	
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	3	3	
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	3	3	