

## LIGHTING SCHEDULE

PAYITEM	LOCATION #1	LOCATION #2	LOCATION #3	TOTAL
	S WOODS ST INTERSECTION	WASHINGTON ST INTERSECTION	LAKE FORK RD INTERSECTION	
ELECTRIC SERVICE INSTALLATION	1	1	1	3
CONDUIT PUSHED, 2" DIA., PVC	170	259	220	649
UNIT DUCT, 600V, 2-1C #10, 1/C #10 GROUND, (XLP-TYPE USE) 3/4" POLYETHYLENE	1815	1782	1415	5012
TRENCH AND BACKFILL FOR ELECTRICAL WORK	1517	1395	1091	4003
LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	10	10	8	28
LIGHTING CONTROLLER, POLE MOUNTED, 240 VOLT, 60 AMP	1	1	1	3
LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM	10	10	8	28
LIGHT POLE, FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6'	10	10	8	28
BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	40	40	32	112
REMOVAL OF LIGHTING UNIT, SALVAGE	1	1	1	3
LIGHTING FOUNDATION REMOVAL	1	1	1	3
REMOVAL OF LIGHTING CONTROLLER	1	1	1	3
REMOVAL OF ELECTRIC SERVICE INSTALLATION	1	1	1	3

FILE NAME =	USER NAME = mcollella	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>LIGHTING SCHEDULE</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\mcollella\dms35866\774344-shr-light.dgn		DRAWN -	REVISED -			322	(51,52)-2	MACON	11	5	
PLOT SCALE = 50.0000' / 1"		CHECKED -	REVISED -			CONTRACT NO. 74344					
PLOT DATE = 5/26/2011		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT