SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITY	ST. CLAIR COUNTY ROADWAY	BRIDGE REL. IL ROUTE 3	RET. WALL RAMPS	LIGHTING								
				CONSTRUCTION TYPE CODE											
				0001	0008	0040	0021								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	32	32											
20100500	TREE REMOVAL, ACRES	ACRE	3.5	3.5											
20200100	EARTH EXCAVATION	CU YD	4,445	4,445											
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	9,624	9,624											
20400800	FURNISHED EXCAVATION	CU YD	173,670	173,670											
20800150	TRENCH BACKFILL	CU YD	906	906											
20900110	POROUS GRANULAR BACKFILL	CU YD	272	272											
25000305	SEEDING, CLASS 3A	ACRE	1.25	1.25											
25100115	MULCH, METHOD 2	ACRE	15.75	15.75											
25100630	EROSION CONTROL BLANKET	SQ YD	76,230	76,230											
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,575	1,575											
28000305	TEMPORARY DITCH CHECKS	FOOT	60	60											
28000400	PERIMETER EROSION BARRIER	FOOT	8,454	8,454											
28000510	INLET FILTERS	EACH	22	22											
28100107	STONE RIPRAP, CLASS A4	SQ YD	59	59											
28200200	FILTER FABRIC	SQ YD	59	59											
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	4,292	4,292											
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	100	100											
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SQ YD	4,120	4,120											
42001300	PROTECTIVE COAT	SQ YD	7,717	7,717											
44000100	PAVEMENT REMOVAL	SQ YD	827	827											
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	120	120											
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SQ YD	319	319											
50200100	STRUCTURE EXCAVATION	CU YD	2,520		1085	1,435									
50300225	CONCRETE STRUCTURES	CU YD	1,360.9		1,299.8	61.1									
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2,752.2	1,261.1	1,491.1										
50300260	BRIDGE DECK GROOVING	SQ YD	3,320		3,320										
50300285	FORM LINER TEXTURED SURFACE	SQ FT	8,561			8,561									
50300300	PROTECTIVE COAT	SQ YD	7,939	2,947	4,992										
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1										
50500505	STUD SHEAR CONNECTORS	EACH	22,449		22,449										

• DENOTES SPECIALTY ITEMS

..\DBCONN-10-BORDER.DGN,..\DBCONN-10-SQDI.DGN,..\DBCONN-99-MOTIF.DGN,..\DBCONN-10-LEGEND.DGN,..\DBCONN-11-MOTIF.DGN
5-12-2011,12:38:44 NEWMANMD \\FS-0044\AM\VAULT_D-TRANS_07\2282\20868-001\CIVIL\CAD\99 ALL CONTRACTS\CONN\SHEETS CONTRACT 10\DBCONN-10-SHT-SUMMARY1.DGN

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - JB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION RELOCATED ILLINOIS ROUTE 3
TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS		DRAWN - JB	REVISED -	
	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -	
	PLOT DATE = $DATE$	DATE - 05/13/11	REVISED -	

SUMMARY OF QUANTITIES 1

SCALE: N.T.S. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-2-1HVB-1	ST. CLAIR	345	4
		CONTRACT NO. 76D05		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT