SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITY	ST. CLAIR COUNTY ROADWAY 0001	BRIDGE REL. IL ROUTE 3 0008	RET. WALL RAMPS 0040	LIGHTING 0021								
				CONSTRUCTION TYPE CODE											
60240324	INLETS, TYPE B, TYPE 20 FRAME AND GRATE	EACH	7	7											
60602800	CONCRETE GUTTER, TYPE B	FOOT	1,501	1,501											
X6063100	CONCRETE GUTTER TRANSITION (SPECIAL)	FOOT	66	66											
60605000	COMBINATION CONCRETE CURB AND GUTTER,TYPE B-6.24	FOOT	152	152											
60609000	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (SPECIAL)	FOOT	29	29											
60610800	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 (SPECIAL)	FOOT	23	23											
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	4,528	4,528											
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	60	60											
63200310	GUARDRAIL REMOVAL	FOOT	26	26											
66400305	CHAIN LINK FENCE, 6'	FOOT	198	198											
66402900	CHAIN LINK GATES, 6' X 6' SINGLE	EACH	1	1											
• 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2,000	2,000											
• 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1											
• 66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4											
67100100	MOBILIZATION	L SUM	1	1											
72000100	SIGN PANEL - TYPE 1	SQ FT	4	4											
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2											
80300100	LOCATING UNDERGROUND CABLE	FOOT	50				50								
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1				1								
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	150				150								
~~81018600~~	~~CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL~~	~~FOOT~~	~~150~~				~~150~~								
81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	285				285								
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	340				340								
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	2				2								
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1				1								
81702420	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 8	FOOT	300				300								
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	205				205								
82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	6				6								
82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 60AMP	EACH	1				1								
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	33				33								
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	1	1											
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	1,588	1,588											
X0325155	REMOVE ABANDONED GAS MAIN	FOOT	172	172											

• DENOTES SPECIALTY ITEMS

..\DBCONN-10 BORD-R.DGN..\DBCONN-10-SQUI.DGN..\DBCONN-99-MOTIF1.DGN..\DBCONN-10-LEGEND.DGN..\DBCONN-10-MOTIF1.DGN
5-12-2011, 12:34:00 NEWMANMD \\FS-0044\AM\VAULT0-TRANS.07\2202\28868 00\CIVIL\CAD\99 ALL CONTRACTS\CONN\SHEETS CONTRACT 10\DBCONN-10-SHT-SUMMARY3.DGN

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - JB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION RELOCATED ILLINOIS ROUTE 3	SUMMARY OF QUANTITIES 3	F.A.P. RTE. 998	SECTION 82-2-1HVB-1	COUNTY ST. CLAIR	TOTAL SHEETS 345 / SHEET NO. 6
		DRAWN - JB	REVISED -						
	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -					CONTRACT NO. 76D05	
TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT DATE = $DATE$	DATE - 05/13/11	REVISED -		SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	