SEEDING, CLASS 7 (SPECIAL)

TOTAL 14.50 ACRE

	SUBTOTALS
FROM ITEM 28000250 TEMPORARY EROSION CONTROL SEEDING	
SUBTRACT ITEM 25000305 SEEDING, CLASS 3A	14.61

AGGREGATE SURFACE COURSE, TYPE B 8"

TOTAL 2,152 SQ YD

LOCATION	FROM STA.	OFFSET	TO STA.	OFFSET	AREA (SF)	SUBTOTALS
REL IL RTE 3	1677+66.25	23.6 RT	1677+86.26	51.6 LT	1,725	192
REL IL RTE 3	1678+32.01	23.6 RT	1680+67.74	51.6 LT	16,614	1,846
REL IL RTE 3	1680+79.49	23.6 RT	1681+35.30	60.2 LT	1,029	114

WATER MAIN REMOVAL, 4"

TOTAL 411 FOOT

LOCATION	FROM STA.	FROM OFF.	RT/LT	TO STA.	TO OFF.	SUBTOTALS
VERIFIED WATER MAIN REMOVAL, 4"						
REL IL RTE 3	1687+79	11	RT	1689+88	2	210
REL IL RTE 3	1687+79	16	RT	1689+80	4	201

WATER MAIN REMOVAL, 8"

TOTAL 263 FOOT

LOCATION	FROM STA.	FROM OFF.	RT/LT	TO STA.	TO OFF.	SUBTOTALS
VERIFIED WATER MAIN REMOVAL, 8"						
REL IL RTE 3	1687+80	34	RT	1689+52	23	172
REL IL RTE 3	1689+66	84	LT	1689+75	6	91

WATER MAIN REMOVAL, 10"

TOTAL 172 FOOT

LOCATION	FROM STA.	FROM OFF.	RT/LT	TO STA.	TO OFF.	SUBTOTALS
VERIFIED WATER MAIN REMOVAL, 10"						
REL IL RTE 3	1687+79	22	RT	1689+50	11	172

WATER MAIN REMOVAL, 12"

TOTAL 912 FOOT

LOCATION	FROM STA.	FROM OFF.	TO STA.	SUBTOTALS
UNVERIFIED WATER MAIN, SIZE UNKNOWN				
REL IL RTE 3	1687+78	3	1688+97	173
REL IL RTE 3	1687+79	19	1688+72	173
REL IL RTE 3	1688+02	17	1688+87	167
REL IL RTE 3	1688+64	105	1688+79	16
REL IL RTE 3	1688+81	109	1689+53	73
VERIFIED WATER MAIN, SIZE UNKNOWN				
REL IL RTE 3	1689+74	5	1690+00	53
REMOVAL OF UNKNOWN UTILITY, SIZE UNKNOWN				
REL IL RTE 3	1687+80	32	1689+51	172
REL IL RTE 3	1689+20	121	1689+26	85

CHAIN LINK FENCE REMOVAL

TOTAL 670 FOOT

	FROM			TO			
LOCATION	STA	OFF	LT/RT	STA	OFF	LT/RT	SUBTOTALS
PR REL IL 3	1671+76.57	168.63	LT	1671+98.17	74.69	RT	245
PR REL IL 3	1671+75.88	165.11	RT	1671+98.52	109.12	RT	82
PR REL IL 3	1671+76.28	163.95	RT	1671+91.47	162.55	RT	16
PR REL IL 3	1687+72.55	139.61	LT	1688+10.35	134.67	LT	41
PR REL IL 3	1690+72.23	42.00	LT	1692+89.65	132.73	LT	286

AGGREGATE SUBGRADE 12"

TOTAL 7,037 SQ YD

LOCATION	DESCRIPTION	FROM STA.	TO STA.	LT/RT	LENGTH	AREA (SF)	SUBTOTALS
RAMP A	PAVEMENT/SHOULDER AREA	17+25.00	20+00.00	LT & RT		8,860	984
RAMP A	0.5' STRIP	17+25.00	19+00.00	LT	175.0	88	10
RAMP A	1.0' STRIP	19+00.00	20+00.00	LT	100.0	100	11
RAMP A	1.0' STRIP	17+25.00	20+00.00	RT	275.0	275	31
RAMP A	PAVEMENT/SHOULDER AREA	20+00.00	25+14.68	LT & RT		25,618	2,846
RAMP A	1.0' STRIP	20+00.00	24+51.20	LT	447.0	447	50
RAMP A	1.0' STRIP	20+00.00	24+42.20	RT	454.3	454	50
RAMP B	PAVEMENT/SHOULDER AREA	50+00.00	53+50.00	LT & RT		12,803	1,423
RAMP B	1.0' STRIP	50+27.20	53+50.00	LT	339.8	340	38
RAMP B	1.0' STRIP	50+20.90	53+50.00	RT	355.4	355	39
RAMP B	PAVEMENT/SHOULDER AREA	53+50.00	58+14.00	LT & RT		12,910	1,434
RAMP B	1.0' STRIP	53+50.00	55+37.85	RT	187.9	188	21
RAMP B	0.5' STRIP	55+37.85	58+14.00	RT	276.2	138	15
RAMP B	1.0' STRIP	53+50.00	57+00.00	LT	350.0	350	39
RAMP B	0.5' STRIP	57+00.00	58+14.00	LT	114.0	57	6
REL IL RTE 3	CB & GUTTER AREA	1681+49.31	1682+21.10	LT	134	346	38

ATTENUATOR BASE

TOTAL 13 SQ YD

LOCATION	STA	OFF	WIDTH	LENGTH	SUBTOTALS
RAMP A	19+00	27.2 LT	4'	30'	13.33

CONCRETE REMOVAL (SPECIAL)

TOTAL 56 SQ YD

LOCATION	STA.	OFF.		MIN. REMOVAL ELEVATION	AREA SQ FT	SUBTOTALS
REL IL RTE 3	1688+20.7	6.04	LT	407		
	1688+21.2	2.62	LT	407		
	1688+27.1	3.28	LT	407		
	1688+26.5	6.18	LT	407	18.8	2.09
REL IL RTE 3	1688+25.7	33.23	LT	407		
	1689+18.8	32.24	LT	407		
	1688+87.0	30.24	LT	407		
	1688+84.8	95.19	LT	407	489.4	54.38

SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE

TOTAL 1000 SQ YD

LOCATION	FROM STA.	TO STA.	LT/RT	LENGTH	WIDTH	SUBTOTALS
EXISTING ST. CLAIR	107+29.00	107+59.00	RT	75	30	250
EXISTING ST. CLAIR	107+81.00	108+11.00	LT	75	30	250
EXISTING ST. CLAIR	103+78.84	104+46.44	RT	75	30	250
REL IL RTE 3	1689+02.00	1689+77.00	RT	75	30	250

IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

TOTAL 1 EACH

LOCATION	FROM STA.	OFF.	TO STA.	OFF.	SUBTOTALS
PR RAMP A	18+74.8	28.5' LT	19+00.0	27.2' LT	1

SAND DRAINAGE BLANKET

TOTAL 5,010 CU YD

LOCATION	FROM STA.	OFF.	TO STA.	OFF	AREA (SQ FT)	THICKNES FT	SUBTOTALS
REL IL RTE 3	1674+25	-113.5	1674+25	77.4	67,633	2	5,010
REL IL RTE 3	1676+00	-123.1	1676+00	96.8			
REL IL RTE 3	1676+50	-116	1676+50	89.4			
REL IL RTE 3	1676+95	-119.8	1676+95	93.2			
REL IL RTE 3	1677+50	-120	1677+50	90.2			

CONCRETE RETAINING WALL REMOVAL

TOTAL 10 FOOT

LOCATION	STA	OFF	STA	OFF	SUBTOTALS
RELOCATED IL 3	1686+97	90.57	1687+07	88.83	10

..\DBCONN-10_BORDER.DGN ..\DBCONN-10-SCHEDD.DGN ..\DBCONN-99-MOTIF1.DGN ..\DBCONN-10-MOTIF1.DGN
5-11-2011, 10:51:05 NEWMANMD \\FS 0844\AMVALT\D TRANS 07\2202\20868-00\CIVIL\CAD\99 ALL CONTRACTS\CONN\SHEETS CONTRACT 10\DBCONN-10-SHT-SCHEDULES.DGN