

INDEX OF SHEETS

1. COVER PAGE
2. INDEX OF SHEETS/HIGHWAY STANDARDS/GENERAL NOTES/COMMITMENTS SUMMARY OF QUANTITIES
3. GENERAL PLAN AND ELEVATION
4. CONCRETE REMOVAL
5. CONCRETE DETAILS
6. BAR SPLICER
7. FOR INFORMATION SHEET - 1959 APPROACH PAVEMENT STD 2138-1
8. FOR INFORMATION SHEET - 1984 APPROACH PAVEMENT STD 2324-6
9. FOR INFORMATION SHEET - 1986 APPROACH PAVEMENT STD 2382-2 (SHT 1 OF 2)
10. FOR INFORMATION SHEET - 1986 APPROACH PAVEMENT STD 2382-2 (SHT 2 OF 2)

HIGHWAY STANDARDS

000001-06
001001-02
001006
701400-05
701402-08
704001-06
701901-01

GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AT&T ILLINOIS
 - BOND MADISON WATER COMPANY
 - SOUTHWESTERN ELECTRIC COOPERATIVE, INC.

MEMBERS OF J.U.L.I.E. (800)-892-0123 ARE INDICATED BY *. NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
4. ALL TURF AREAS DISTURBED BY THE CONTRACTOR SHALL BE SEEDED WITH THE APPROPRIATE EROSION CONTROL AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE.

COMMITMENTS

NONE

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	100% STATE CONSTRUCTION TYPE CODE 0014
CODE NO	ITEM	UNIT		
50102400	CONCRETE REMOVAL	CU YD	35.2	35.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	68.9	68.9
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6240	6240
50800515	BAR SPLICERS	EACH	64	64
67100100	MOBILIZATION	L SUM	1	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2	2
70400100	TEMPORARY CONCRETE BARRIER	FOOT	550	550
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	550	550
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3056	3056
78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	522	522
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1193	1193
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1

FILE NAME *	USER NAME * gelrh	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pwwork\psidot\gelrh\d820025\08766	5-shr-500.dgn	DRAWN - ---	REVISED - ---			70	60-118-1	MADISON	10	2	
	PLOT SCALE = 1/8" = 100.0000' / IN.	CHECKED - ---	REVISED - ---								
	PLOT DATE = 3/4/2011	DATE - -----	REVISED - ---								
						SCALE: -----		SHEET NO. 1 OF 1 SHEETS		STA. ----- TO STA. -----	
						FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					