

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION
 DIVISION OF HIGHWAYS



**PROPOSED
 HIGHWAY PLANS**

FAI ROUTE 70 (I-70)
 SECTION 60-11B-I
 EXPANSION JOINTS - CM
 MADISON COUNTY

C-98-118-10

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-11B-I	MADISON	10	1
		ILLINOIS	CONTRACT NO. 76E25	



FOR INDEX OF SHEETS, SEE SHEET NO. 2



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.
 JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION
 1-800-892-0123
 OR 811

TRAFFIC DATA
 ADT: 30,000 (2011)
 37,000 (2031)
 SU: 3.4%
 MU: 24.2%



LATITUDE: 38.7595 LONGITUDE: -89.8351

GROSS LENGTH = 116'-0" FT. = 0.022 MILE
 NET LENGTH = 116'-0" FT. = 0.022 MILE

PROJECT ENGINEER: PATTI LEBEAU (618) 346-3179
 PROJECT MANAGER: HERVE GELIN (618) 346-3323

CONTRACT NO. 76E25

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION
 DIVISION OF HIGHWAYS

SUBMITTED February 16, 2011
Mark C. Jamie
 DEPUTY DIRECTOR OF HIGHWAYS, REGION ENGINEER

March 25, 2011
Scott E. Still, P.E.
 ENGINEER OF DESIGN AND ENVIRONMENT

March 25, 2011
Christine M. Reed
 DIRECTOR OF HIGHWAYS, CHIEF ENGINEER

**PRINTED BY THE AUTHORITY
 OF THE STATE OF ILLINOIS**

INDEX OF SHEETS

1. COVER PAGE
2. INDEX OF SHEETS/HIGHWAY STANDARDS/GENERAL NOTES/COMMITMENTS SUMMARY OF QUANTITIES
3. GENERAL PLAN AND ELEVATION
4. CONCRETE REMOVAL
5. CONCRETE DETAILS
6. BAR SPLICER
7. FOR INFORMATION SHEET - 1959 APPROACH PAVEMENT STD 2138-1
8. FOR INFORMATION SHEET - 1984 APPROACH PAVEMENT STD 2324-6
9. FOR INFORMATION SHEET - 1986 APPROACH PAVEMENT STD 2382-2 (SHT 1 OF 2)
10. FOR INFORMATION SHEET - 1986 APPROACH PAVEMENT STD 2382-2 (SHT 2 OF 2)

HIGHWAY STANDARDS

000001-06
001001-02
001006
701400-05
701402-08
704001-06
701901-01

GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
 2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
 3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AT&T ILLINOIS
 - BOND MADISON WATER COMPANY
 - SOUTHWESTERN ELECTRIC COOPERATIVE, INC.
- MEMBERS OF J.U.L.I.E. (800)-892-0123 ARE INDICATED BY *. NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
4. ALL TURF AREAS DISTURBED BY THE CONTRACTOR SHALL BE SEEDED WITH THE APPROPRIATE EROSION CONTROL AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE.

COMMITMENTS

NONE

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0014
CODE NO	ITEM	UNIT		
50102400	CONCRETE REMOVAL	CU YD	35.2	35.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	68.9	68.9
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6240	6240
50800515	BAR SPLICERS	EACH	64	64
67100100	MOBILIZATION	L SUM	1	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2	2
70400100	TEMPORARY CONCRETE BARRIER	FOOT	550	550
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	550	550
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3056	3056
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	522	522
78300100	PAVEMENT MARKING REMOVAL	SO FT	1193	1193
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1

FILE NAME *	USER NAME * gelrh	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pwwork\psidot\gelrh\d820025\08766	5-shr-500.dgn	DRAWN - ---	REVISED - ---			70	60-118-1	MADISON	10	2	
	PLOT SCALE = 1/8" = 100.0000' / IN.	CHECKED - ---	REVISED - ---								
	PLOT DATE = 3/4/2011	DATE - -----	REVISED - ---								
						SCALE: -----		SHEET NO. 1 OF 1 SHEETS		STA. ----- TO STA. -----	
						FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					

SN 060-0027(EB) & 060-0028(WB) was originally built in 1963 as I-70, Section 60-HB-1. It consists of dual 3 span continuous WF structures on pile bent abutments, and pile supported solid wall piers. In 1970 the decks and approaches were overlaid with bituminous overlays. In 1988 the deck overlays were removed, the decks were scarified 1/4" and overlaid with a 2" concrete overlay. The west approach of the south bridge was replaced with the 24' wide Bridge Approach Pavement Std 2324, and all 4 approaches were widened with concrete Bridge Approach Shoulders Std 2324-6.

GENERAL NOTES

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. See Special Provisions.

Reinforcement bars designated (E) shall be epoxy coated.


Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

Existing reinforcement shall be cleaned and incorporated into the new construction. Cost included with Concrete Removal.

The Contractor shall ensure the approach slabs and approach shoulders do not settle after removal of the ends of the approaches. If voids are encountered after removal of the deck ends, the Contractor shall pump grout under the approaches to maintain support during removal. Cost included with "Concrete Removal".

INDEX OF SHEETS

- 1) General Plan & Elevation
- 2) Concrete Removal
- 3) Concrete Details
- 4) Bar Splicer
- 5) For Information Sheet - 1959 Approach Pavement Std 2138-1
- 6) For Information Sheet - 1984 Approach Shoulder Std 2324-6
- 7) For Information Sheet - 1986 Approach Pavement Std 2382-2 (Sh 1 of 2)
- 8) For Information Sheet - 1986 Approach Pavement Std 2382-2 (Sh 2 of 2)




DESIGN STRESSES

FIELD UNITS
 $f'_c = 3,500$ psi
 $f_y = 60,000$ psi (Reinforcement)

TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
Concrete Removal	Cu. Yd.	35.2
Concrete Superstructure	Cu. Yd.	68.9
Reinforcement Bars, Epoxy Coated	Pound	6240
Bar Splicers	Each	64







Expires 11/30/2012

DESIGNED John Uehle	EXAMINED <i>John F. [Signature]</i>	DATE 3-16-2011
CHECKED Brad Williams	ENGINEER OF STRUCTURAL SERVICES	
DRAWN John Uehle	PASSED <i>John Carl Puzey</i>	
CHECKED Brad Williams	ENGINEER OF BRIDGES AND STRUCTURES	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL PLAN AND ELEVATION
STRUCTURE NO. 060-0027 & 0028
SHEET NO. 1 OF 8 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-11HB-1	MADISON	10	3
CONTRACT NO. 76E25				
[ILLINOIS] FED. AID PROJECT				



Deck / Approach Slab Removal
 Haunch Removal

DESIGNED John Uehle
 CHECKED Brad Williams
 DRAWN John Uehle
 CHECKED Brad Williams

EXAMINED *Joe J. [Signature]*
 PASSED *Brad Williams*
 ENGINEER OF STRUCTURAL SERVICES
 ENGINEER OF BRIDGES AND STRUCTURES


DATE - 3-16-2011

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CONCRETE REMOVAL
STRUCTURE NO. 060-0027 & 0028


SHEET NO. 2 OF 8 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-11B-1	MADISON	10	4
CONTRACT NO. 76E25				
ILLINOIS FED. AID PROJECT				



ELEVATION


N. Bridge East Abut Looking East
S. Bridge West Abut Looking West
(Other Abutments Opposite Hand)



PLAN


N. Bridge East Abut
S. Bridge West Abut
(Other Abutments Opposite Hand)

**** Drill and epoxy grout v2(E) bars into the abutment cap in accordance with Article 584 of the Standard Specifications. Lap the v(E) and v(E) bars with v2(E) bars. Cost included with "Reinforcement Bars, Epoxy Coated".



EXISTING SECTION A-A

* Varies 1'-3 3/4" (outside gutter) to 1'-7 3/4" (median gutter)
** Varies 12"-16" NW, NE, & SE Approach Pavt.
13" SW Approach Pavt.
10" Approach Shoulders
*** Varies 3"(Bm 1) to 7"(E) to 4 1/4" (Bm 8)




PROPOSED SECTION A-A

BILL OF MATERIAL

(All 4 Abutments)

Bar	No.	Size	Length	Shape
a(E)	32	#5	22'-2"	—
a1(E)	32	#5	24'-6"	—
a2(E)	32	#5	17'-2"	—
a3(E)	32	#5	18'-6"	—
v(E)	144	#5	8'-0"	└
v1(E)	160	#5	4'-2"	└
v2(E)	304	#6	3'-6"	—
Concrete Removal		Cu. Yds.	35.2	
Reinforcement Bars, Epoxy Coated		Pound	6240	
Concrete Superstructure		Cu. Yds.	68.9	



DESIGNED John Uehle
CHECKED Brad Williams
DRAWN John Uehle
CHECKED Brad Williams

EXAMINED *John F. Schmitt*
PASSED *Carl R. Taylor*


DATE - 3-16-2011

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CONCRETE DETAILS
STRUCTURE NO. 060-0027 & 0028

SHEET NO. 3 OF 8 SHEETS

F.A.I. RTEL.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-118-1	MADISON	10	5
CONTRACT NO. 76E25				
ILLINOIS FED. AID PROJECT				



STANDARD BAR SPLICER ASSEMBLY


Minimum Lap Lengths					
Bar size to be spliced	Table 1	Table 2	Table 3	Table 4	Table 5
3, 4	1'-5"	1'-11"	2'-1"	2'-4"	2'-3"
5	1'-9"	2'-5"	2'-7"	2'-11"	2'-10"
6	2'-1"	2'-11"	3'-1"	3'-6"	3'-4"
7	2'-9"	3'-10"	4'-2"	4'-8"	4'-6"
8	3'-8"	5'-1"	5'-5"	6'-2"	5'-10"
9	4'-7"	6'-5"	6'-10"	7'-9"	7'-5"

- Table 1: Black bar, 0.8 Class C
- Table 2: Black bar, Top bar lap, 0.8 Class C
- Table 3: Epoxy bar, 0.8 Class C
- Table 4: Epoxy bar, Top bar lap, 0.8 Class C
- Table 5: Epoxy bar, Top bar lap, Class B

Threaded splicer bar length = min. lap length + 1/2" + thread length


* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.

Location	Bar size	No. assemblies required	Table for minimum lap length
Abutments	#5	64	2'-11"




INSTALLATION AND SETTING METHODS

"A" : Set bar splicer assembly by means of a template bolt.
 "B" : Set bar splicer assembly by nailing to wood forms or cementing to steel forms.
 (E) : Indicates epoxy coating.




STANDARD MECHANICAL SPLICER

Location	Bar size	No. assemblies required



BAR SPLICER ASSEMBLY FOR #5 BAR ON INTEGRAL OR SEMI-INTEGRAL ABUTMENTS

No. required =



BAR SPLICER ASSEMBLY FOR #5 BAR ON STUB ABUTMENTS

No. required =

NOTES

Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi yield strength.
 All reinforcement shall be lapped and tied to the splicer bars.
 Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications.
 See special provision for Mechanical Splicers.
 See approved list of bar splicer assemblies and mechanical splicers for alternatives.

DESIGNED John Uehle
 CHECKED Brad Williams
 DRAWN John Uehle
 CHECKED Brad Williams

EXAMINED *Joy F. [Signature]*
 ENGINEER OF STRUCTURAL SERVICES

PASSED *John [Signature]*
 ENGINEER OF BRIDGES AND STRUCTURES

DATE 3-16-2011

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION



BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS
 STRUCTURE NO. 060-0027 & 0028

SHEET NO. 4 OF 8 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-11HB-1	MADISON	10	6

CONTRACT NO. 76E25
 [ILLINOIS] FED. AID PROJECT

**DETAILS OF BRIDGE APPROACHES
FOR FEDERAL AID INTERSTATE ROUTES**



OPTIONAL LONGITUDINAL CONSTRUCTION JOINT
As approved by the Engineer, the Contractor may elect to reduce the widths of pour by use of the Optional Longitudinal Construction Joint shown. Joint shall be located at the edge of Traffic Lane.











TABLE OF "A" DIMENSIONS

Width of Approach Slab	Dimension "A" (Spacing of Mud Jack Cylinders)
14'	6'-0"
24'	6'-0"
36'	2 Spaces at 8'-0"


Expanded Metal weighing not less than 78 Lbs. per 100 sq. ft. or a welded bar mat weighing not less than 78 Lbs. per 100 sq. ft. having members of equal size in both directions and spaced not over 6" apart may be used instead of the #2 Welded Wire Fabric, 6" x 6", provided the expanded metal or bar mat is furnished at no additional cost to the State.



LONGITUDINAL EXPANSION JOINT
To be used when Approach Slabs are greater than 36'-0" wide. Joint shall be placed at edge of Traffic Lane nearest to the E. of the total width of Approach Slab.



SECTION A-A



SECTIONAL VIEW OF CONCRETE SLAB AND CAP

GENERAL NOTES
The slab or slabs will be paid for at the contract unit price for PORTLAND CEMENT CONCRETE PAVEMENT (16'-0" x 12'-0" x 16'-0").
The concrete cap will be paid for at the contract unit price for CLASS X CONCRETE.
All Reinforcement Bars, except tie bars for curb and gutter or gutter, will be paid for at the contract unit price for REINFORCEMENT BARS.
The Welded Wire Fabric, Mud Jack Cylinders and Preformed Expansion Joint Filler shall be included in the unit price bid for PORTLAND CEMENT CONCRETE PAVEMENT (16'-0" x 12'-0" x 16'-0").
Preformed Expansion Joint Filler shall conform to Section 129 of the Standard Specifications.
Width of Bridge Approach Slab pours shall be determined before the reinforcement bars are fabricated.
Quantities shown for Reinforcement Bars are for two(2) thickened edges only.

**FOR INFORMATION ONLY
1959 Bridge Approach Pavement
Standard 2138-1**

STANDARD 2138-1

STATE OF ILLINOIS
DEPARTMENT OF PUBLIC WORKS AND BUILDINGS
DIVISION OF HIGHWAYS

REVISIONS	DATE
1	2-2-59
2	10-22-59

APPROVED: [Signature] 1958


DESIGNED <u>John Uehle</u>	EXAMINED _____	DATE _____
CHECKED <u>Brad Williams</u>	ENGINEER OF STRUCTURAL SERVICES	
DRAWN <u>John Uehle</u>	PASSED _____	
CHECKED <u>Brad Williams</u>	ENGINEER OF BRIDGES AND STRUCTURES	

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**FOR INFORMATION SHEET (STANDARD 2138-1)
STRUCTURE NO. 060-0027 & 0028**

SHEET NO. 5 OF 8 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-11B-1	MADISON	10	7
			CONTRACT NO. 76E25	
ILLINOIS FED. AID PROJECT				



GENERAL NOTES

When Inlet Box or Boxes are not required, surface of the shoulder pavement shall be finished to provide a smooth transition from back of the abutment to normal approach roadway shoulder.

See plans for location of bridge approach shoulder pavement. Use Type C Inlet Box for 5' and 6' shoulder widths, use Type D Inlet Box for 7' and wider shoulder widths, use Type B Inlet Box for shoulders less than 5' wide.

For placement of approach shoulder pavement an existing construction substitute expansion anchor ties for tie bars. For non-rigid approaches, shoulder pavement will be as shown except omit tie bars in approach pavement.

The material for 12" Pipe Drains shall be either corrugated steel, aluminum alloy or polyethylene (PE) pipe with UV protection. Corrugated steel and aluminum alloy pipe shall have 2" coupling bands. All pipe connections shall be water tight.

The P.C. Concrete used in the shoulder slab shall meet the requirements of Section 408 of the Standard Specifications.

The lengths of #4 bars used in the approach shoulder pavement shall be as required to accommodate the length, width and skew of the slab.

Class X concrete or precast concrete shall be used for the inlet. Precast concrete shall be in accordance with Sections 503.04 thru 503.05 of the Standard Specifications except that the concrete strength shall be 4000 p.s.i. after 28 days.

All exposed edges of the inlet, except the upper perimeter, shall be beveled 1/4".

Shop drawings will not be required for precast Inlet Boxes.

A 3" deep CA-12 bedding conforming to Article 704.04 Quality or better shall be provided under full length and width of precast units, and all voids around the pipe drain entrances, both inside and outside, shall be sealed with mortar.

The grating shall seat firmly in the frame and steel grates shall be secured to the frame with a locking device as shown. Cast grates will not require the locking device.

Steel grating and frames shall conform to Article 710.04 of the Standard Specifications and shall be galvanized to AASHTO Specification #111 or better fabrication.

Cast grating and frames shall conform to Article 710.17 of the Standard Specifications. Cast grating and frames shall not be galvanized.

FOR INFORMATION ONLY

DETAIL B 1984 Approach Shoulder Pavement Standard 2324-6

Pipe drains shall be installed, measured and paid for in accordance with Section 607 of the Standard Specifications, except sand bedding will not be required.

Metal End Sections shall be installed, measured and paid for in accordance with Section 511 of the Standard Specifications.

Bridge approach shoulder pavement will be measured in place and paid for in square yards as P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT which shall include the cost of subgrade preparation, expansion anchor, ties, reinforcement and joint fillers. In computing the area for payment, a deduction will be made for the area displaced by the inlet (1/2 Sq. Yds. Type C; 1/7 Sq. Yds. Type D, 0.6 Sq. Yds. Type B).

The contract unit price "Each" for TYPE (B, C or D) INLET BOX STANDARD 2324, in place, shall include the frame and grating, class X or precast concrete, reinforcement bars, excavation, bedding when required, and compacted backfill.

The contract unit price "Each" for CONCRETE THRUST BLOCKS, in place, shall include excavation and compacted backfilling.

Material Required for One Type B Inlet Box

Bar	No.	Size	Length
u	4	#4	8'-5"
u ₂	3	#4	8'-0"
u ₆	4	#4	6'-2"
Concrete - Class X or Precast		Cu. Yds.	0.4
Rein. Bars		Lbs.	60
Grating		Sq. Ft.	3.7

Material Required for One Type C Inlet Box

Bar	No.	Size	Length
u	6	#4	8'-5"
u ₂	3	#4	10'-1"
u ₄	4	#4	8'-4"
Concrete - Class X or Precast		Cu. Yds.	0.9
Rein. Bars		Lbs.	80
Grating		Sq. Ft.	7.3

Material Required for One Type D Inlet Box

Bar	No.	Size	Length
u	8	#4	8'-5"
u ₂	3	#4	12'-2"
u ₄	4	#4	10'-4"
Concrete - Class X or Precast		Cu. Yds.	1.2
Rein. Bars		Lbs.	100
Grating		Sq. Ft.	11.0

Illinois Department of Transportation

PASSED July 18, 1984


Engineer of Bridge and Traffic Structures

APPROVED July 18, 1984


Engineer of Design

BRIDGE APPROACH SHOULDER PAVEMENT


STANDARD 2324-6



SECTION C-C
*Stagger alternate #7 bars as shown on plan - full width.




DETAIL "A"
(When bituminous surface is being placed)




DETAIL "A"
(P.C.C. Pavement Construction)

Keyed Longitudinal Construction Joint in accordance with details shown on Standard 2323.




OPTIONAL LONGITUDINAL CONSTRUCTION JOINT


As approved by the Engineer, the Contractor may elect to reduce the width of pour by use of the Optional Longitudinal Construction Joint shown. Joints shall be located at the edge of a traffic lane.



PLAN - WITH SKEW




PLAN - WITHOUT SKEW




#7 BARS

When the road plans show curb and gutter, gutter, or bridge approach shoulder pavement adjacent to approach slabs, place 1/2 inch steel tie bars at 2'-6 inch centers in accordance with the detail for Bulkhead Longitudinal Construction Joint shown on Standard 2323. Cost of the tie bars will be included in the contract unit price for the adjacent item. Transitions for curb and gutter or gutter shall be as shown on the plans.



SECTION D-D



SECTION E-E

Notes:
For skews of less than 10° omit wire fabric. For skews of 10° or more use Welded Wire Fabric, 6"x6"-W5.5 x W5.5, placed 3/4" below top of slab. Expanded Metal weighing not less than 78 Pounds per 100 Sq. Ft. or a welded bar mat weighing not less than 78 Pounds per 100 Sq. Ft. having members of equal size in both directions and spaced not over 8" apart may be used instead of the Welded Wire Fabric, 6"x6"-W5.5 x W5.5, provided the expanded metal or bar mat is furnished at no additional cost to the State. Reinforcement bars shall conform to the requirements of A.A.S.H.T.O. M 31 or M 53, Grade 60.

DESIGN STRESSES

$f_y = 60,000 \text{ p.s.i.}$
 $f_c = 3500 \text{ p.s.i.}$
 $n = 8.5$

GENERAL NOTES

The cost of tie bars, expansion joint filler, sub-base, welded wire fabric and bituminous prime when required shall be considered as included in the unit cost of the Bridge Approach Pavement.

Preformed Expansion Joint Filler shall conform to A.A. 715.10 of the Standard Specifications. Width of Bridge Approach Slab shall be determined before the reinforcement bars are fabricated.

The bituminous patch, when required, will be paid for in accordance with Section 620 of the Standard Specifications.

FOR INFORMATION ONLY
1986 Bridge Approach Pavement
Standard 2382-2 (Sheet 1 of 2)

BRIDGE APPROACH PAVEMENT

Sheet 1 of 2

STANDARD 2382-2

Illinois Department of Transportation

APPROVED Mar. 10, 1986
John Uehle
Engineer of Bridges and Structures

APPROVED Mar. 10, 1986
John Uehle
Engineer of Design

DESIGNED John Uehle	EXAMINED _____	DATE _____
CHECKED Brad Williams	ENGINEER OF STRUCTURAL SERVICES	
DRAWN John Uehle	PASSED _____	
CHECKED Brad Williams	ENGINEER OF BRIDGES AND STRUCTURES	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FOR INFORMATION SHEET (STANDARD 2382-2 SHEET 1)
STRUCTURE NO. 060-0027 & 0028
SHEET NO. 7 OF 8 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-118-1	MADISON	10	9
			CONTRACT NO. 76E25	
[ILLINOIS] FED. AID PROJECT				


Note: The notation for the number of bars given as "4 x 2" indicates 4 lines of bars with 2 lengths per line. Min. bar lap = 1'-3"

Skew Angle Degrees	Bottom Reinforcement		Top Reinforcement		Reinforcement (Total Weight) (Pounds)	Slab Area (Sq. Yds.)	6x6-W5.5xW5.5 W.W.F.	
	Transverse #5	Longitudinal #7	Transverse #4	Longitudinal #4			Dimensions L(1)xW(1)	Area* (Sq. Yds.)
18'-0" PAVEMENT								
0	20	17'-6"	6	17'-6"	2300	40.0		
5	20	17'-7"	6	17'-7"	2302	41.6		
10	20	17'-9"	6	17'-9"	2306	43.2	7'-0" x 9'-6"	7.4
15	20	18'-1"	5	18'-1"	2303	44.6	8'-6" x 9'-6"	9.0
20	19	18'-8"	5	18'-8"	2297	46.6	10'-6" x 9'-6"	11.1
25	18	19'-4"	5	19'-4"	2292	48.4	12'-3" x 9'-6"	12.9
30	18	20'-3"	5	20'-3"	2313	50.4	14'-3" x 9'-6"	15.0
35	17	21'-4"	5	21'-4"	2315	52.6	16'-6" x 9'-6"	17.4
40	16	22'-10"	4	22'-10"	2307	55.1	19'-0" x 9'-6"	20.1
45	14	24'-9"	4	24'-9"	2293	58.0	21'-9" x 9'-6"	23.0
50	13	27'-3"	4	27'-3"	2308	61.5	25'-6" x 9'-6"	26.9
55	12x2	15'-9"	3x2	15'-9"	2322	65.7	29'-9" x 9'-6"	31.4
60	10x2	18'-0"	3x2	18'-0"	2313	71.2	35'-3" x 9'-6"	37.2
24'-0" PAVEMENT								
0	20	23'-6"	6	23'-6"	3019	53.3		
5	20	23'-7"	6	23'-7"	3021	56.1		
10	20	23'-10"	6	23'-10"	3028	58.9	8'-0" x 12'-6"	11.1
15	20	24'-4"	5	24'-4"	3024	61.9	10'-3" x 12'-6"	14.2
20	19	25'-0"	5	25'-0"	3014	64.9	12'-6" x 12'-6"	17.2
25	18	25'-11"	5	25'-11"	3008	68.2	15'-0" x 12'-6"	20.8
30	18	27'-2"	5	27'-2"	3036	71.8	17'-9" x 12'-6"	24.7
35	17	28'-9"	5	28'-9"	3039	75.7	20'-9" x 12'-6"	28.8
40	16x2	16'-0"	4x2	16'-0"	3055	80.2	24'-0" x 12'-6"	33.3
45	14x2	17'-3"	4x2	17'-3"	3031	85.3	27'-6" x 12'-6"	38.2
50	13x2	18'-10"	4x2	18'-10"	3046	91.4	32'-9" x 12'-6"	45.5
55	12x2	21'-1"	3x2	21'-1"	3047	99.0	38'-3" x 12'-6"	53.1
60	10x2	24'-0"	3x2	24'-0"	3032	108.7	45'-6" x 12'-6"	63.2


*Area does not include 8" longitudinal laps.
W.W.F. = Welded Wire Fabric.

Skew Angle Degrees	Bottom Reinforcement		Top Reinforcement		Reinforcement (Total Weight) (Pounds)	Slab Area (Sq. Yds.)	6x6-W5.5xW5.5 W.W.F.	
	Transverse #5	Longitudinal #7	Transverse #4	Longitudinal #4			Dimensions L(1)xW(1)	Area* (Sq. Yds.)
26'-0" PAVEMENT								
0	20	25'-6"	6	25'-6"	3236	57.8		
5	20	25'-7"	6	25'-7"	3240	61.1		
10	20	25'-11"	6	25'-11"	3249	64.4	8'-6" x 13'-6"	12.8
15	20	26'-5"	5	26'-5"	3243	67.8	11'-0" x 13'-6"	16.5
20	19	27'-2"	5	27'-2"	3233	71.4	13'-6" x 13'-6"	20.3
25	18	28'-2"	5	28'-2"	3227	75.3	16'-3" x 13'-6"	24.4
30	18x2	15'-3"	5x2	15'-3"	3276	79.5	19'-0" x 13'-6"	28.5
35	17x2	16'-1"	5x2	16'-1"	3282	84.1	22'-3" x 13'-6"	33.4
40	16x2	17'-2"	4x2	17'-2"	3269	89.3	25'-3" x 13'-6"	38.6
45	14x2	18'-6"	4x2	18'-6"	3243	95.3	30'-0" x 13'-6"	45.0
50	13x2	20'-4"	4x2	20'-4"	3264	102.5	35'-0" x 13'-6"	52.5
55	12x2	22'-9"	3x2	22'-9"	3265	111.4	41'-3" x 13'-6"	61.9
60	10x2	26'-0"	3x2	26'-0"	3251	122.8	49'-0" x 13'-6"	73.5
36'-0" PAVEMENT								
0	20x2	18'-3"	6x2	18'-3"	4471	80.0		
5	20x2	18'-4"	6x2	18'-4"	4478	86.3		
10	20x2	18'-6"	6x2	18'-6"	4483	92.7	10'-0" x 18'-6"	20.6
15	20x2	18'-10"	5x2	18'-10"	4479	99.3	13'-6" x 18'-6"	27.7
20	19x2	19'-5"	5x2	19'-5"	4462	106.2	17'-0" x 18'-6"	34.9
25	18x2	20'-2"	5x2	20'-2"	4455	113.6	20'-6" x 18'-6"	42.1
30	18x2	21'-0"	5x2	21'-0"	4492	121.6	24'-9" x 18'-6"	50.8
35	17x2	22'-3"	5x2	22'-3"	4501	130.4	29'-0" x 18'-6"	59.6
40	16x2	23'-9"	4x2	23'-9"	4483	140.4	33'-9" x 18'-6"	69.4
45	14x2	25'-9"	4x2	25'-9"	4450	152.0	39'-6" x 18'-6"	81.2
50	13x2	28'-2"	4x2	28'-2"	4477	165.8	46'-6" x 18'-6"	95.6
55	12x3	21'-4"	3x3	21'-4"	4492	182.8	55'-0" x 18'-6"	113.0
60	10x3	24'-4"	3x3	24'-4"	4471	204.7	65'-9" x 18'-6"	135.1

*Area does not include 8" longitudinal laps.



PLACEMENT OF 6x6-W5.5xW5.5
W.W.F. only required on skews $\geq 10^\circ$



CUTTING DIAGRAM

FOR INFORMATION ONLY
1986 Bridge Approach Pavement
Standard 2382-2 (Sheet 2 of 2)

Illinois Department of Transportation
APPROVED Mar. 10 1986
James J. K... ..
Engineer of Bridges and Structures
APPROVED Mar. 10 1986
...
Engineer of Design

BRIDGE APPROACH PAVEMENT
Sheet 2 of 2
STANDARD 2382-2

DESIGNED John Uehle
CHECKED Brad Williams
DRAWN John Uehle
CHECKED Brad Williams

EXAMINED _____ DATE _____
ENGINEER OF STRUCTURAL SERVICES

PASSED _____
ENGINEER OF BRIDGES AND STRUCTURES

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FOR INFORMATION SHEET (STANDARD 2382-2 SHEET 2)
STRUCTURE NO. 060-0027 & 0028

SHEET NO. 8 OF 8 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-11B-I	MADISON	10	10
CONTRACT NO. 76E25			ILLINOIS FED. AID PROJECT	