

STANDARDS

- 000001-06
- 001006
- 482001-02
- 482006-03
- 482011-03
- 635006-03
- 701400-05
- 701411-07
- 701422-03
- 701446-02
- 701451-01
- 701901-01

INDEX OF SHEETS

1. COVER SHEET
2. INDEX OF SHEETS, STANDARDS, AND GENERAL NOTES, MIXTURE REQUIREMENT CHARTS
3. SUMMARY OF QUANTITIES
4. SCHEDULE OF QUANTITIES
- 5.-8. STRUCTURE ELEVATION
- 9.-17. GENERAL PLAN AND TYPICAL SECTIONS
18. GENERAL PLAN FOR APPROACH WORK AND SHOULDER CURB
19. INTERSTATE WEEKEND CLOSURE PLAN (EB I-70)
20. INTERSTATE WEEKEND CLOSURE PLAN (MLK DRIVE AND COLLINSVILLE AVE INTERSECTION)
21. INTERSTATE WEEKEND CLOSURE PLAN (WB I-55/70/64)
- 22.-26. INTERSTATE WEEKEND CLOSURE PLAN (WB I-55/70)
27. INTERSTATE WEEKEND CLOSURE PLAN (WB I-64)
- 28.-29. APPROACH WORK DETAILS

HMA MIXTURE TABLES

MIXTURE USE	POLY SURFACE
AC/PG	SBS PG 76-22
RAP% (MAX)	SEE SPEC.
DESIGN AIR VOIDS	4.0% @Ndes=90
MIX COMPOSITION	
GRADATION MIXTURE	IL 12.5/IL 9.5
FRICTION AGG	MIXTURE E

MIXTURE USE	SHOULDERS <2.25"
AC/PG	PG 64-22
RAP% (MAX)	See Contract RAP
DESIGN AIR VOIDS	Special Provison
MIX COMPOSITION	2.0% @ Ndes=30
GRADATION MIXTURE	NMAS 1/2"

GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING STRUCTURE AND ROADWAY HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.
4. IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16, THE CONTRACTOR SHALL PROTECT THE SURFACE OF THE BRIDGE DECK AND BRIDGE APPROACH PAVEMENT IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 107.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.
5. UTILITIES INTERFERENCES ARE NOT ANTICIPATED ON THIS CONTRACT. NO ADDITIONAL COST SHALL BE ADDED TO THE CONTRACT RESULTING FROM ANY UNANTICIPATED UTILITY INTERFERENCE. FOR ADDITIONAL INFORMATION, CONTACT THE JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (J.U.L.I.E.) SYSTEM AT (800) 892-0123 OR 811.
6. THE DEPARTMENT STRONGLY ENCOURAGES THE PRIME CONTRACTOR AND THEIR APPROVED SUB- CONTRACTOR TO HIRE MINORITY, WOMEN AND DISADVANTAGED INDIVIDUALS FROM ITS FEDERALLY FUNDED HIGHWAY CONSTRUCTION CAREERS TRAINING PROGRAM (HCCTP) TO HELP MEET WORK FORCE AND TRAINEE GOALS. THIS PROGRAM IS TRAINING MINORITIES, WOMEN AND DISADVANTAGED INDIVIDUALS IN HIGHWAY CONSTRUCTION -RELATED SKILLS, E.G., MATH FOR THE TRADES, JOB READINESS, TECHNICAL SKILLS COURSE WORK (CARPENTRY, CONCRETE FLAT WORK, BLUEPRINT READING, SITE PLANS, SITE WORK, TOOLS USE, ETC.) AND OSHA 10 HOUR CERTIFICATION, TO PREPARE THEM FOR A CAREER IN THEIR HIGHWAY CONSTRUCTION TRADES. GRADUATES ARE WELL-TRAINED AND READY TO BECOME PRODUCTIVE ENTRY-LEVEL CONSTRUCTION WORKERS. CONTACT THE DISTRICT 8 EEO OFFICE AT 618-346-3360 AND/OR THE HCCTP COORDINATOR AT 618-874-6528 TO LEARN MORE ABOUT THE PROGRAM AND FOR ASSISTANCE IN MEETING WORKFORCE AND TRAINEE GOALS.
7. EXISTING PAVEMENT MARKINGS SHALL BE TEMPORARILY COVERED PRIOR TO APPLICATION OF THE DECK SURFACE TREATMENT, TO PREVENT THE MATERIAL FROM BEING APPLIED TO THE MARKINGS. THE TEMPORARY COVERING SHALL BE REMOVED AFTER APPLICATION OF THE DECK SURFACE TREATMENT AND PRIOR TO OPENING TO TRAFFIC. COST IS INCLUDED WITH THE DECK SURFACE TREATMENT SPECIFIED.

FILE NAME = c:\pwwork\pwwork\d0247784\sheet	USER NAME = lengdk _eng.dgn	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STANDARDS AND GENERAL NOTES MIXTURE REQUIREMENT CHARTS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 1/8" = 1' / in.	CHECKED -	REVISED -	799			1-BR, 05-1	ST. CLAIR	29	2	
PLOT DATE = 6/23/2011	DATE -	REVISED -	SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 76E72		