



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 18, 2011

SUBJECT: Various Routes
Section D9 Deck Seal 2012-1
Various Counties
Contract No. 78260
Item No. 40, August 5, 2011 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page i of the Table of Contents to the Special Provisions.
2. Added page 25 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 9; Mike Renner; D. Carl Puzey;
Estimates

TBW:DB:jc

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
UTILITIES.....	1
TRAFFIC CONTROL PLAN	1
COOPERATION OF CONTRACTS	3
APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS (BDE)	3
CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE)	4
CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE).....	5
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	6
EQUIPMENT RENTAL RATES (BDE).....	14
LIQUIDATED DAMAGES (BDE).....	15
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE)	15
PAYMENTS TO SUBCONTRACTORS (BDE)	17
POST MOUNTING OF SIGNS (BDE).....	18
SELECTION OF LABOR (BDE).....	18
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	18
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE)	19
UTILITY COORDINATION AND CONFLICTS (BDE).....	19
WORKING DAYS (BDE)	24
BRIDGE DECK CONCRETE SEALER.....	25

Revised 07/18/2011

BRIDGE DECK CONCRETE SEALER

Effective: June 17, 2010

Revised: October 26, 2010

(BRIDGE DECK CONCRETE SEALER may be substituted in place of PROTECTIVE COAT, per the following specification.)

Description: This work shall consist of the preparation and placement of a concrete sealer upon the entire top surface of the deck and the tops and inside vertical faces of the parapets of the structure(s), as outlined in the contract. This work shall be according to Section 587 of the Standard Specifications except as modified herein.

Materials shall be according to Article 587.02 except only non-water based, penetrating sealers of the Silane or Siloxane categories from the Departments approved list of concrete sealers will be allowed.

In addition to the requirements of Article 587.03, the following shall apply.

- (a) The distribution sprayers shall include a skirting system to control overspray. Deck drains shall be temporarily plugged before the agent is applied to control run off. The material used to plug the drains shall be removed and disposed of upon the completion of the sealing treatment.
- (b) For new concrete, sealing shall be performed after all grinding and/or saw cut grooving is completed and before the deck is marked and open to traffic.

Added 07/18/2011