STORM SEWER

STATION	OFFSET (FT)	TYPE	STANDARD	STORM SEWERS CLASS A, TYPE 1 12" (FOOT)	15"	36"	CLASS A, TYPE 2 12"	15"	18"	24"	30"	36"	INLETS TYPE A TY. 3 FRAME & GRATE (EACH)	TYPE 8 GRATE	INLETS TYPE B TY. 3 FRAME AND GRATE (EACH)	TYPE 8 GRATE	MANHOLES TYPE A 4' DIAMETER TY. 1 FRAME CLOSED LID (EACH)	TY. 3 FRAME AND GRATE	TYPE 8 GRATE	MANHOLES TYPE A 5' DIAMETER TY.1 FRAME CLOSED LID (EACH)	TY. 3 FRAME AND GRATE	TYPE 8 GRATE	P.R.C. FLARED END SECTION 24" (EACH)	30"	STEEL END SECTION, 12" (EACH)	PIPE DRAINS, 12" (FOOT)	CONCRETE THRUST BLOCKS (EACH)	TRENCH BACKFILL (CU YD)
		SS									4																	
126+00.00	23.00 RT	MH	602401, 604006																		1							
		SS									44																	48
126+00.00	24.96 LT	MH	602401, 604006																		1							
		SS									60																	32
126+55.57	53.48 LT	MH	602401, 604001, 602601																	1								
		SS							4																			
126+62.65	53.48 LT	INLET	602306, 604006												1													
		SS							56																			34
127+20.65	53.82' LT	INLET	602306, 604006												1													
		SS							34																			
127+50.00	38.56 LT	INLET	602306, 604036													1												
		SS							36																			15
127+50.00	CL	MH	602401, 604036, 602601														1											
		SS							98																			36
128+50.00	CL	MH	602401, 604036, 602601														1											
		SS					22																					3
128+50.00	23.00 LT	INLET	602301, 604006										1															
		SS					22																					3
128+50.00	23.00 RT	INLET	602301, 604006										1															
		SS						112																				37
129+65.00	CL	MH	602401, 604036, 602601														1											
		SS					22																					3
129+65.00	23.00 LT	INLET	602301, 604006										1															
		SS					22																					3
129+65.00	23.00 RT	INLET	602301, 604006										1															
		SS					128																					31
130+95.00	CL	MH	604001, 602601														1											
		SS					18																					3
130+95.00	20.26 LT	INLET	602306, 604006												1													
		SS		4																								
130+95.00	25.72 LT	INLET	602301, 604036											1														
		SS					18																					3
130+95.00	20.56 RT	INLET	602301, 604006										1															
OLD RENWICK RD.																												
49+30.00	14.00 RT	INLET	602301, 604006										1															
		SS					26																					5
49+30.00	14.00 LT	INLET	602306, 604006												1													
		SS					12																					2
49+45.00	14.00 LT	INLET	602306, 604006												1													
RIVER RD.																												
10+10.00	18.91 RT	INLET	602301, 604006										1															
		SS					36																					9
10+10.00	18.91 LT	INLET	602306, 604006												1													
		SS					4																					
10+10.00	24.86 LT	MH	602301, 604036, 602601														1											
		SS					172																					15
11+85.00	25.95 LT	MH	602301, 604036, 602601														1											
		SS					4																					
11+85.00	20.00 LT	INLET	602306, 604006												1													
		SS					38																					7
11+85.00	20.00 RT	INLET	602301, 604006										1															
		SS						72																				7
12+59.00	28.61 LT	MH	602301, 604006														1											
		SS							30																			
12+89.79	39.80 LT	MH	602301, 604006														1											
		SS					4																					
12+59.19	22.49 LT	MH	602401, 604006															1										
		SS					8																					1
12+49.19	21.27 LT	INLET	602301, 604006										1															
		SS					40																					9
12+59.19	20.00 RT	MH	602401, 6064006, 602601															1										
		SS					8																					1
12+49.19	20.00 RT	INLET	602301, 604006										1															
		SS					24																					3
12+84.16	22.90 RT	INLET	602301, 604006										1															

CONTINUED ON NEXT SHEET