



PAVEMENT GRADES WEST SIDE OF RAILROAD TRACKS										
STATION	PROFILE ELEVATION	SLOPE	LEFT SIDE				RIGHT SIDE			
			SLOPE	WIDTH	DROP	EOP	SLOPE	WIDTH	DROP	EOP
116+46.00	605.32	-0.848%					0.0200	15	0.30	605.02
116+50.00	605.29	-0.797%					0.0182	15	0.27	605.02
116+51.00	605.28	-0.784%					0.0178	15	0.27	605.01
116+52.00	605.27	-0.771%					0.0173	15	0.26	605.01
116+53.00	605.27	-0.758%					0.0169	15	0.25	605.01
116+54.00	605.26	-0.745%					0.0165	15	0.25	605.01
116+55.00	605.25	-0.733%					0.0160	15	0.24	605.01
116+56.00	605.24	-0.720%					0.0156	15	0.23	605.01
116+57.00	605.24	-0.707%	0.0200	15	0.30	604.94	0.0151	15	0.23	605.01
116+58.00	605.23	-0.694%	0.0200	15	0.30	604.93	0.0147	15	0.22	605.01
116+59.00	605.22	-0.681%	0.0200	15	0.30	604.92	0.0142	15	0.21	605.01
116+60.00	605.22	-0.669%	0.0200	15	0.30	604.92	0.0138	15	0.21	605.01
116+61.00	605.21	-0.656%	0.0200	15	0.30	604.91	0.0134	15	0.20	605.01
116+62.00	605.20	-0.643%	0.0200	15	0.30	604.90	0.0129	15	0.19	605.01
116+63.00	605.20	-0.630%	0.0200	15	0.30	604.90	0.0125	15	0.19	605.01
116+64.00	605.19	-0.617%	0.0200	15	0.30	604.89	0.0120	15	0.18	605.01
116+65.00	605.18	-0.605%	0.0200	15	0.30	604.88	0.0116	15	0.17	605.01
116+66.00	605.18	-0.592%	0.0200	15	0.30	604.88	0.0111	15	0.17	605.01
116+67.00	605.17	-0.579%	0.0200	15	0.30	604.87	0.0107	15	0.16	605.01
116+68.00	605.17	-0.566%	0.0200	15	0.30	604.87	0.0103	15	0.15	605.01
116+69.00	605.16	-0.553%	0.0200	15	0.30	604.86	0.0098	15	0.15	605.01
116+70.00	605.15	-0.541%	0.0200	15	0.30	604.85	0.0094	15	0.14	605.01
116+71.00	605.15	-0.528%	0.0200	15	0.30	604.85	0.0089	15	0.13	605.02
116+72.00	605.14	-0.515%	0.0200	15	0.30	604.84	0.0085	15	0.13	605.02
116+73.00	605.14	-0.502%	0.0200	15	0.30	604.84	0.0081	15	0.12	605.02
116+74.00	605.13	-0.489%	0.0200	15	0.30	604.83	0.0076	15	0.11	605.02
116+75.00	605.13	-0.477%	0.0200	15	0.30	604.83	0.0072	15	0.11	605.02
117+00.00	605.05	-0.156%	0.0200	15	0.30	604.75	-0.0039	15	-0.06	605.11
117+01.00	605.05	-0.144%	0.0196	15	0.29	604.75	-0.0043	15	-0.07	605.11
117+02.00	605.05	-0.131%	0.0192	15	0.29	604.76	-0.0048	15	-0.07	605.12
117+03.00	605.05	-0.118%	0.0189	15	0.28	604.76	-0.0052	15	-0.08	605.12
117+03.24	605.05	-0.115%	0.0188	15	0.28	604.76	-0.0053	15	-0.08	605.13
117+04.00	605.05	-0.105%	0.0185	15	0.28	604.77				
117+05.00	605.04	-0.092%	0.0181	15	0.27	604.77				
117+06.00	605.04	-0.080%	0.0177	15	0.27	604.78				
117+07.00	605.04	-0.067%	0.0173	15	0.26	604.78				
117+08.00	605.04	-0.054%	0.0170	15	0.25	604.79				
117+09.00	605.04	-0.041%	0.0166	15	0.25	604.79				
117+10.00	605.04	-0.028%	0.0162	15	0.24	604.80				
117+11.00	605.04	-0.016%	0.0158	15	0.24	604.80				
117+12.00	605.04	-0.003%	0.0154	15	0.23	604.81				
117+13.00	605.04	0.010%	0.0151	15	0.23	604.81				
117+14.00	605.04	0.023%	0.0147	15	0.22	604.82				
117+15.00	605.04	0.036%	0.0143	15	0.21	604.83				
117+16.00	605.04	0.048%	0.0139	15	0.21	604.83				
117+17.00	605.04	0.061%	0.0135	15	0.20	604.84				
117+18.00	605.04	0.074%	0.0132	15	0.20	604.85				
117+19.00	605.04	0.087%	0.0128	15	0.19	604.85				
117+20.00	605.04	0.100%	0.0124	15	0.19	604.86				
117+21.00	605.05	0.112%	0.0120	15	0.18	604.87				
117+21.25	605.05	0.116%	0.0119	15	0.18	604.87				
117+22.00	605.05	0.125%	0.0117	15	0.17	604.87				
117+23.00	605.05	0.138%	0.0113	15	0.17	604.88				
117+24.00	605.05	0.151%	0.0109	15	0.16	604.89				
117+25.00	605.05	0.164%	0.0105	15	0.16	604.89				
117+25.00	605.05	0.164%	0.0105	15	0.16	604.89				
117+32.38	605.07	0.258%	0.0077	15	0.12	604.95				
117+33.38	605.07	0.271%	0.0073	15	0.11	604.96				

PAVEMENT GRADES EAST SIDE OF RAILROAD TRACKS										
STATION	PROFILE ELEVATION	SLOPE	LEFT SIDE				RIGHT SIDE			
			SLOPE	WIDTH	DROP	EOP	SLOPE	WIDTH	DROP	EOP
117+15.17	605.04	0.038%					-0.0053	15	-0.080	605.12
117+16.17	605.04	0.051%					-0.0049	15	-0.074	605.12
117+25.00	605.05	0.164%					-0.0012	15	-0.018	605.07
117+26.00	605.05	0.176%					-0.0007	15	-0.011	605.06
117+27.00	605.05	0.189%					-0.0003	15	-0.005	605.06
117+28.00	605.06	0.202%					0.0001	15	0.001	605.06
117+29.00	605.06	0.215%					0.0005	15	0.008	605.05
117+30.00	605.06	0.228%					0.0009	15	0.014	605.05
117+31.00	605.06	0.241%					0.0014	15	0.021	605.04
117+32.00	605.07	0.253%					0.0018	15	0.027	605.04
117+33.00	605.07	0.266%					0.0022	15	0.033	605.04
117+34.00	605.07	0.279%					0.0026	15	0.040	605.03
117+35.00	605.07	0.292%					0.0031	15	0.046	605.03
117+36.00	605.08	0.305%					0.0035	15	0.052	605.02
117+37.00	605.08	0.317%					0.0039	15	0.059	605.02
117+38.00	605.08	0.330%					0.0043	15	0.065	605.02
117+39.00	605.09	0.343%					0.0048	15	0.071	605.02
117+40.00	605.09	0.356%					0.0052	15	0.078	605.01
117+41.00	605.09	0.369%					0.0056	15	0.084	605.01
117+42.00	605.10	0.381%					0.0060	15	0.090	605.01
117+43.00	605.10	0.394%					0.0065	15	0.097	605.00
117+44.00	605.11	0.407%					0.0069	15	0.103	605.00
117+45.00	605.11	0.420%					0.0073	15	0.109	605.00
117+45.32	605.11	0.424%	0.0073	15	0.11	605.00				
117+50.00	605.13	0.484%	0.0093	15	0.14	604.99	0.0094	15	0.141	604.99
117+51.00	605.14	0.497%	0.0098	15	0.15	604.99	0.0098	15	0.148	604.99
117+52.00	605.14	0.509%	0.0102	15	0.15	604.99	0.0103	15	0.154	604.99
117+53.00	605.15	0.522%	0.0106	15	0.16	604.99	0.0107	15	0.160	604.99
117+54.00	605.15	0.535%	0.0110	15	0.17	604.99	0.0111	15	0.167	604.99
117+55.00	605.16	0.548%	0.0115	15	0.17	604.99	0.0115	15	0.173	604.98
117+56.00	605.16	0.561%	0.0119	15	0.18	604.99	0.0120	15	0.179	604.98
117+57.00	605.17	0.573%	0.0123	15	0.18	604.98	0.0124	15	0.186	604.98
117+58.00	605.17	0.586%	0.0127	15	0.19	604.98	0.0128	15	0.192	604.98
117+59.00	605.18	0.599%	0.0132	15	0.20	604.98	0.0132	15	0.198	604.98
117+60.00	605.19	0.612%	0.0136	15	0.20	604.98	0.0136	15	0.205	604.98
117+61.00	605.19	0.625%	0.0140	15	0.21	604.98	0.0141	15	0.211	604.98
117+62.00	605.20	0.637%	0.0145	15	0.22	604.98	0.0145	15	0.217	604.98
117+63.00	605.21	0.650%	0.0149	15	0.22	604.98	0.0149	15	0.224	604.98
117+64.00	605.21	0.663%	0.0153	15	0.23	604.98	0.0153	15	0.230	604.98
117+65.00	605.22	0.676%	0.0157	15	0.24	604.98	0.0158	15	0.236	604.98
117+66.00	605.23	0.689%	0.0162	15	0.24	604.98	0.0162	15	0.243	604.98
117+67.00	605.23	0.701%	0.0166	15	0.25	604.98	0.0166	15	0.249	604.98
117+68.00	605.24	0.714%	0.0170	15	0.26	604.98	0.0170	15	0.256	604.98
117+69.00	605.25	0.727%	0.0174	15	0.26	604.99	0.0175	15	0.262	604.99
117+70.00	605.25	0.740%	0.0179	15	0.27	604.99	0.0179	15	0.268	604.99
117+71.00	605.26	0.753%	0.0183	15	0.27	604.99	0.0183	15	0.275	604.99
117+72.00	605.27	0.765%	0.0187	15	0.28	604.99	0.0187	15	0.281	604.99
117+73.00	605.28	0.778%	0.0191	15	0.29	604.99	0.0192	15	0.287	604.99
117+74.00	605.29	0.791%	0.0196	15	0.29	604.99	0.0196	15	0.294	604.99
117+75.00	605.29	0.804%	0.0200	15	0.30	604.99	0.0200	15	0.300	604.99

FILE NAME = V:\2545\2545r006.dgn	USER NAME = bdecrane	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	T.R. (RENWICK RD.) RAILROAD DETAIL			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -		SCALE: 1"=1'	SHEET NO. 4 OF 6 SHEETS	STA. N/A	TO STA. N/A	TR 55	90-16103-01-BR	WILL	255	127
		CHECKED -	REVISED -							CONTRACT NO. 83126			
		DATE -	REVISED -										