



CITY OF URBANA  
PUBLIC WORKS  
ENGINEERING DIVISION

DRAWN BY: AUS

CHECKED BY: GLJ

DATED: 1/11

DESIGNED BY: CES

CITY SECTION  
05-00416-00-BT

HIGH CROSS ROAD MULTI-USE PATH  
GENERAL NOTES

SHEET NO.  
2  
OF  
40

# GENERAL NOTES

## GENERAL NOTES

- ALL ELEVATIONS SHOWN ARE REFERRED TO THE N.A.V.D. 29 DATUM.
  - WHEREVER IN THE PLANS OR SPECIFICATIONS THE TERM "STANDARD SPECIFICATIONS" IS USED IT SHALL BE UNDERSTOOD BY THE CONTRACTOR TO MEAN THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" AS PREPARED BY THE DEPARTMENT OF TRANSPORTATION OF THE STATE OF ILLINOIS AND ADOPTED ON JANUARY 1, 2007.
  - WHEREVER IN THE PLANS OR SPECIFICATIONS THE TERM "STANDARD SPECIFICATIONS FOR WATER MAIN AND SEWER CONSTRUCTION" IS USED IT SHALL BE UNDERSTOOD BY THE CONTRACTOR TO MEAN THE "STANDARD SPECIFICATIONS FOR WATER MAIN AND SEWER MAIN CONSTRUCTION IN ILLINOIS" AS PREPARED BY I.S.P.E., A.G.C.I., I.M.L., AND U.C.A., LATEST EDITION.
  - ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT OF TRANSPORTATION AS SHOWN ON THE HIGHWAY STANDARDS AND LEGEND SHEET.
  - IT IS THE CONTRACTOR'S RESPONSIBILITY TO ASCERTAIN EXISTING FIELD CONDITIONS BEFORE BIDDING ON THE PROJECT.
  - THE CONTRACTOR WILL BE REQUIRED TO COMPLY WITH STATE AND LOCAL REGULATIONS REGARDING AIR, WATER, AND NOISE POLLUTION.
  - THE CONTRACTOR SHALL TAKE CARE NOT TO STORE OR DISPOSE OF DEBRIS OR UNSUITABLE MATERIALS WITHIN LIMITS OF THE IMPROVEMENT AND TAKE CARE TO LIMIT CONSTRUCTION TO WITHIN THE RIGHT-OF-WAY AND EASEMENT AREAS. UNNECESSARY ENCROACHMENTS ONTO PRIVATE OR PUBLIC AREAS WILL NOT BE ALLOWED.
  - WHERE SECTION OR SUBSECTION MONUMENTS, BENCHMARKS, OR IRON PIPE MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN ILLINOIS REGISTERED LAND SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR WILL BE RESPONSIBLE FOR HAVING AN ILLINOIS REGISTERED LAND SURVEYOR RE-ESTABLISH ANY MONUMENTS UNNECESSARILY DESTROYED BY HIS OPERATIONS.
  - ALL STREET RETURNS HAVE RADII DESIGNATED TO THE EDGE OF PAVEMENT UNLESS OTHERWISE NOTED ON PLANS.
  - THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANUP OF THE SITE PRIOR TO FINAL ACCEPTANCE IN ACCORDANCE WITH ARTICLE 104.06 OF THE STANDARD SPECIFICATIONS, THIS WORK SHALL ALSO INCLUDE CLEANING ALL DRAINAGE FACILITIES OF FOREIGN MATERIALS.
- ### UTILITIES
- UTILITIES WERE PLOTTED FROM INFORMATION FURNISHED BY THE VARIOUS UTILITY COMPANIES INVOLVED AND THEIR ACCURACY SHOULD BE CONSIDERED APPROXIMATE ONLY. NO RESPONSIBILITY IS ACCEPTED FOR THE LOCATIONS AS SHOWN OR THAT ALL LINES ARE SHOWN. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THEIR EXACT LOCATION AND TO PROTECT THE SAME.
  - THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.
  - THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE J.U.L.I.E. NUMBER IS 800-892-0123. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED.
  - THE FOLLOWING IS A LIST OF UTILITY COMPANIES LOCATED ALONG THIS SECTION. THE UTILITY OWNERS MARKED WITH AN "\*" BELONG TO J.U.L.I.E.
    - \*ILLINOIS AMERICAN WATER (WATER)
    - \*AMEREN IP (ELECTRIC AND GAS)
    - \*AT&T (COMMUNICATIONS)
    - \*MCLEOD USA (COMMUNICATIONS)
    - \*COMCAST (CATV)
    - \*URBANA CHAMPAIGN SANITARY DISTRICT (SANITARY SEWER INTERCEPTORS)
    - \*CITY OF URBANA (STORM AND SANITARY SEWERS, STREETLIGHTS, TRAFFIC SIGNALS)
  - ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE REMOVED AND DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS APPROVED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED WITHIN THE CONTRACT UNIT PRICE FOR EARTH EXCAVATION AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

## EARTHWORK - REMOVALS

- THE EXCAVATION FOR THIS PROJECT IS CLASSIFIED AS EARTH EXCAVATION IN ACCORDANCE WITH SECTION 202 OF THE STANDARD SPECIFICATIONS. THE EARTH EXCAVATION SHALL INCLUDE THE REMOVAL OF EARTH AND UNCLASSIFIED MATERIALS. THE REMAINING EXCAVATION IS CLASSIFIED AS REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL, PAVEMENT REMOVAL, DRIVEWAY PAVEMENT REMOVAL, SIDEWALK REMOVAL AND CURB AND GUTTER REMOVAL.
- ONLY EXISTING PAVEMENT, BASE COURSES AND DRIVEWAY PAVEMENTS COMPOSED OF PORTLAND CEMENT CONCRETE OR BITUMINOUS CONCRETE AS IDENTIFIED IN THE PLANS SHALL BE MEASURED AND PAID FOR AS "PAVEMENT REMOVAL" AND "DRIVEWAY PAVEMENT REMOVAL" IN ACCORDANCE WITH SECTION 440 OF THE STANDARD SPECIFICATIONS. REMOVAL OF OTHER TYPES OF PAVEMENT COMPOSITION SUCH AS AGGREGATE OR OIL AND CHIP SHALL BE MEASURED AND PAID FOR AS "EARTH EXCAVATION" IN ACCORDANCE WITH SECTION 202 OF THE STANDARD SPECIFICATIONS.
- THE CONTRACTOR SHALL CAREFULLY PROTECT ANY TREES OR SHRUBS NOT INCLUDED IN THE CONTRACT FOR REMOVAL. TEMPORARY FENCE SHALL BE ERECTED, AT THE DIRECTION OF THE ENGINEER, TO PROTECT TREES AND SHRUBS TO REMAIN, THAT ARE IMMEDIATELY ADJACENT TO THE WORK, FOR PROTECTION DURING CONSTRUCTION OPERATIONS. THE COST OF THIS WORK SHALL BE INCLUDED IN THE PAY ITEM FOR EARTH EXCAVATION WITH NO ADDITIONAL COMPENSATION ALLOWED.
- THE EXISTING PIPE CULVERTS OR STORM SEWERS SHOWN TO BE REMOVED ON THE PLANS SHALL BE REMOVED IN ACCORDANCE WITH SECTION 551 OF THE STANDARD SPECIFICATIONS EXCEPT THAT SALVAGING OF THE PIPE WILL NOT BE REQUIRED UNLESS OTHERWISE NOTED IN THE PLANS. REMOVAL SHALL ALSO INCLUDE THE REMOVAL OF END SECTIONS AND OTHER APPURTENANCES FOUND.
- EXISTING TRAFFIC CONTROL SIGNS AND POSTS SHALL BE REMOVED AND RESET, AS THE CASE MAY BE, AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER. THIS WORK SHALL BE PERFORMED IN ACCORDANCE WITH ARTICLE 107.25 OF THE STANDARD SPECIFICATIONS. EXISTING SIGNS THAT WILL NOT BE RESET AS DIRECTED BY THE ENGINEER SHALL BE RETURNED TO THE CITY OF URBANA'S PUBLIC WORKS GARAGE AT 706 S. GLOVER AVENUE. REMOVAL AND RE-INSTALLATION OF ALL EXISTING SIGNAGE WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCLUDED WITHIN THE CONTRACT UNIT PRICE FOR EARTH EXCAVATION.

## LANDSCAPING - EROSION CONTROL

- THE FINISHED EARTHWORK SHALL HAVE VEGETATIVE SUSTAINING SOIL COVERING THE TOP 4 INCHES IN AREAS TO BE SODDED OR SEEDED. THE TOPSOIL REQUIRED WILL BE PAID FOR PER CUBIC YARD FOR "TOPSOIL EXCAVATION AND PLACEMENT".
- ALL DISTURBED AREAS SHALL BE SODDED OR SEEDED AS SHOWN ON THE PLANS. SEEDING, SODDING, AND MULCHING SHALL BE PERFORMED AS SOON AS EACH STAGE IS COMPLETED AS DIRECTED BY THE ENGINEER. EXISTING TURF WHICH IS DAMAGED OUTSIDE THE LIMITS OF CONSTRUCTION SHALL BE REESTABLISHED WITH SOD OR SEED AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE.
- THIS PROJECT IS GOVERNED BY THE CITY'S N.P.D.E.S. GENERAL PERMIT NO. ILR 400462. THIS PERMIT WILL REQUIRE EROSION AND SEDIMENT CONTROL. THE CONTRACTOR WILL BE REQUIRED TO PROVIDE TEMPORARY EROSION CONTROL SEEDING, INLET AND PIPE PROTECTION, INLET FILTERS, AND PERIMETER EROSION CONTROL BARRIER AS SHOWN ON THE STORM WATER POLLUTION PREVENTION PLAN AND STANDARD 280001. INLET AND PIPE PROTECTION AND INLET FILTERS SHALL BE INSTALLED AT ALL OPEN DRAINAGE GRATES TO PREVENT SILT AND SEDIMENT FROM ENTERING THE STORM SEWER SYSTEM. PERIMETER EROSION CONTROL BARRIER SHALL BE PLACED ADJACENT TO CONSTRUCTION AREAS TO PREVENT SOIL FROM LEAVING THE SITE AS DIRECTED BY THE ENGINEER. AN ESTIMATED QUANTITY FOR THE EROSION CONTROL ITEMS HAS BEEN INCLUDED IN THE PROJECT AS SHOWN ON THE STORM WATER POLLUTION PREVENTION PLAN AND MAY BE ADJUSTED AS DIRECTED BY THE ENGINEER.

## PAVEMENTS - CURB & GUTTERS - SIDEWALKS

- THE ENGINEER SHALL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS BITUMINOUS LIFTS.
- WHERE THE PROPOSED COMBINATION CONCRETE CURB AND GUTTER JOINS THE EXISTING CURB AND GUTTER, A TRANSITION BETWEEN THE TWO CONFIGURATIONS MAY BE REQUIRED. THIS WORK SHALL BE CONSIDERED INCLUDED IN THE CONTRACT UNIT PRICE FOR CURB AND GUTTER OF THE SIZE AND TYPE SPECIFIED IN THE PLANS.
- EXISTING PAVEMENTS, CURBS AND GUTTERS, AND SIDEWALKS IN WHICH THE TOP SURFACE IS TO BE JOINED TO THE PROPOSED WORK SHALL BE SO JOINED THROUGH SAW CUT JUNCTURES AS DIRECTED BY THE ENGINEER.
- THE FOLLOWING RATES OF APPLICATION HAVE BEEN ASSUMED IN CALCULATING PLAN QUANTITIES:
 

BITUMINOUS PRIME COAT - FOG COAT	0.03 TO 0.05 GAL/SQ YD
- PAVED SURFACE	0.05 TO 0.10 GAL/SQ YD
AGGREGATE PRIME COAT - AGGREGATE SURFACE	0.25 TO 0.50 GAL/SQ YD
BITUMINOUS CONCRETE (ALL TYPES)	3 LBS/SQ YD
AGGREGATE MATERIALS	112 LBS/SQ YD/INCH THICK
	2.05 TON/CU YD

## SEWERS

- ALL SALVAGEABLE FRAMES AND GRATES WHICH ARE NOT INCORPORATED IN THE WORK SHALL BECOME THE PROPERTY OF THE CONTRACTOR. THE CONTRACTOR'S BID PRICE FOR VARIOUS STORM DRAINAGE WORK SHOULD REFLECT THE SALVAGE VALUE OF THE ITEMS.
- ALL TRENCHES AND EXCAVATIONS FOR DRAINAGE PIPES, STRUCTURES, OR STRUCTURE REMOVALS BELOW OR WITHIN TWO FEET Laterally OF THE PROPOSED PAVEMENT, DRIVEWAY PAVEMENT, SIDEWALK, OR CURB AND GUTTER, SHALL BE BACKFILLED WITH TRENCH BACKFILL AS SHOWN ON THE PLANS AND IN ACCORDANCE WITH THE SPECIAL PROVISIONS AND THE DETAIL IN THE PLANS. THE BACKFILLING AROUND DRAINAGE STRUCTURES WILL NOT BE MEASURED FOR PAYMENT AS DESCRIBED IN SECTION 602 OF THE STANDARD SPECIFICATIONS.
- STORM SEWER, WATER MAIN QUALITY IS TO BE USED AT LOCATIONS WHERE LATERAL SEPARATION BETWEEN THE SEWER AND WATER MAIN IS LESS THAN 10 FEET OR WHERE THE WATER MAIN CROSSES BELOW THE SEWER, REGARDLESS OF VERTICAL SEPARATION OR WHERE THE BOTTOM OF THE WATER MAIN IS LESS THAN 18 INCHES ABOVE THE TOP OF THE SEWER. THE MATERIAL SHALL BE CONCRETE PRESSURE PIPE OR DUCTILE IRON PIPE MEETING THE REQUIREMENTS OF SECTION 40-2.01 OF THE STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS. PVC PIPE WILL NOT BE ALLOWED.
- WHEN CONNECTIONS ARE TO BE MADE TO EXISTING PIPING AND STRUCTURES, THE LOCATION AND ELEVATION OF THE EXISTING PIPING SHALL BE FIELD VERIFIED AND NOTIFICATION GIVEN TO THE ENGINEER IF THE EXISTING PIPING IS FOUND TO BE DIFFERENT THAN THAT SHOWN ON THE DRAWINGS. WHERE SUCH DISCREPANCY IS FOUND, WORK SHALL NOT PROCEED UNTIL DIRECTED ACCORDINGLY BY THE ENGINEER.
- WHERE PROPOSED STORM SEWERS ARE TO BE CONNECTED INTO EXISTING MANHOLES OR EXISTING STORM SEWERS THE CONNECTIONS SHALL BE MADE IN A WORKMANLIKE MANNER AND MASONRY CONSTRUCTED AROUND THEM SO AS TO PREVENT LEAKAGE. CONNECTIONS OF STORM SEWERS TO EXISTING STRUCTURES SHALL BE MADE BY CORE DRILLING HOLES IN THE STRUCTURES. THE COST OF MAKING ANY SEWER CONNECTIONS TO AN EXISTING DRAINAGE STRUCTURE OR PIPE SHALL BE CONSIDERED INCLUDED WITHIN THE CONTRACT UNIT PRICE FOR THE NEW SEWER.
- THE FOLLOWING ARE THE LOCATIONS FOR THE TOP-OF-FRAME ELEVATIONS REFERRED TO IN THE DRAINAGE STRUCTURE CALL-OUTS:
 

TYPE 1 FRAME AND LID	ADJACENT PAVEMENT OR GROUND SURFACE
TYPE 3 FRAME AND GRATE	TOP FRONT CENTER (EQUALS ADJACENT EDGE OF GUTTER FOR B-6.18 CC&G) (0.03 LESS THAN EDGE OF GUTTER FOR B-6.24 CC&G)
TYPE 11 FRAME AND GRATE	TOP FRONT CENTER (EQUALS ADJACENT EDGE OF GUTTER FOR B-6.12 CC&G)
TYPE 8, 37, AND 37M GRATE	ADJACENT GROUND SURFACE
- TYPE 3 AND TYPE 11 FRAME AND GRATES SHALL BE PROVIDED WITH OPEN FACE CURB BOXES AS DESCRIBED IN THE SPECIAL PROVISIONS.

## TRAFFIC CONTROL

- THE CITY OF URBANA SHALL BE RESPONSIBLE FOR NOTIFYING THE PUBLIC, THE UNITED STATES POSTAL SERVICE, AND THE EMERGENCY SERVICE AGENCIES OF ALL ROAD CLOSURES AND CHANGES IN THE TRAFFIC MAINTENANCE PLANS. THE CONTRACTOR SHALL NOTIFY THE CITY OF URBANA OF ALL ROAD CLOSURES AND CHANGES IN THE TRAFFIC MAINTENANCE PLANS A MINIMUM OF 48 HOURS IN ADVANCE.
- THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO WEIGHTED SAND BAGS ON EACH TYPE 11 BARRICADE USED. (ONE WEIGHTED SAND BAG ACROSS EACH BOTTOM RAIL.)
- FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.