

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9557	05-00081-00-RP	SALINE	45	2
CITY OF HARRISBURG		GRANGER STREET		

CONTRACT NO. 99439

SUMMARY OF QUANTITIES

Code Number	Item	Unit	Quantity
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	258.6
20200100	EARTH EXCAVATION	CU YD	500
20800150	TRENCH BACKFILL	CU YD	2260.2
25100630	EROSION CONTROL BLANKET	SQ YD	4500
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150
28000400	PERIMETER EROSION BARRIER	FOOT	1000
28000500	INLET AND PIPE PROTECTION	EACH	71
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	2400
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	500
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	796
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	19300
42400800	DETECTABLE WARNINGS	SQ FT	264
44000100	PAVEMENT REMOVAL	SQ YD	7500
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	775.2
44000600	SIDEWALK REMOVAL	SQ FT	21975
44213204	TIE BARS 3/4"	EACH	100
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	909
550A0070	STORM SEWERS, CLASS A, TYPE 1, 15"	FOOT	496
550A0090	STORM SEWERS, CLASS A, TYPE 1, 18"	FOOT	684
550A0120	STORM SEWERS, CLASS A, TYPE 1, 24"	FOOT	462
550A0130	STORM SEWERS, CLASS A, TYPE 1, 27"	FOOT	178
550B0050	STORM SEWERS, CLASS B, TYPE 1, 12"	FOOT	206
550B0070	STORM SEWERS, CLASS B, TYPE 1, 15"	FOOT	90
550B0090	STORM SEWERS, CLASS B, TYPE 1, 18"	FOOT	86
55100500	STORM SEWER REMOVAL 12"	FOOT	153
55100700	STORM SEWER REMOVAL 15"	FOOT	93
55101200	STORM SEWER REMOVAL 24"	FOOT	43
△ *56100700	WATER MAIN 8"	FOOT	2040
△ *56105000	WATER VALVES 8"	EACH	4
△ *56108710	TAPPING VALVES AND SLEEVES 4"	EACH	3
△ *56108800	TAPPING VALVES AND SLEEVES 6"	EACH	10
△ *56200200	WATER SERVICE LINE 3/4"	FOOT	1000
△ *56200300	WATER SERVICE LINE 1"	FOOT	60
△ *56500200	DOMESTIC WATER SERVICE BOXES TO BE MOVED	EACH	5

Code Number	Item	Unit	Quantity
60218400	MANHOLES, TYPE A, 4-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4
60221100	MANHOLES, TYPE A, 5-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	6
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1
60500040	REMOVING MANHOLES	EACH	4
60500060	REMOVING INLETS	EACH	13
△ 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	30
△ 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1
△ 66900530	SOIL DISPOSAL ANALYSIS	EACH	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12
67100100	MOBILIZATION	L SUM	1
72000100	SIGN PANEL, TYPE 1	SQ FT	12
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	108
△ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	510
△ 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	1279
△ 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	143
LR420125	PORTLAND CEMENT CONCRETE PAVEMENT 7" (SPL) WITH I.C.	SQ YD	8173
X2500900	SEEDING, CLASS 1 (SPECIAL)	ACRE	0.9
△ X5620106	WATER SERVICE RECONNECTIONS	EACH	55
*X6024242	INLETS, SPECIAL, NO. 1	EACH	50
*X6024244	INLETS, SPECIAL, NO. 2	EACH	1
△ *XX000679	CUT AND CAP EXISTING WATER MAIN	EACH	12
△ *XX004760	FIRE HYDRANT WITH AUXILIARY VALVE, VALVE BOX AND TEE	EACH	5
△ *XX005890	DETECTION WIRE	FOOT	3300
△ *XX006537	WATER SERVICE LINE 3/4", BORED	FOOT	120
△ *XX007968	PIPE CASING, 12" PVC	FOOT	190
△ XX008811	WATER MAIN 8" BORED	FOOT	1260
△ XX009545	PVC CASING PIPE, 2"	FOOT	650
△ XX009546	PVC CASING PIPE, 2" BORED	FOOT	60
△ XX009544	PVC CASING PIPE, 12" BORED	FOOT	160
△ XX009548	WATER SERVICE LINE 3/4" INSIDE 2" CASING	FOOT	710
△ XX009545	INLETS, TYPE A, SPECIAL	EACH	7

△ SPECIALTY ITEMS