


**SIGN SCHEDULE**

LOCATION	NAME	SIGNS		POSTS (FOOT)
		NO.	SQ. FT.	
STA. 52+80 LT	MILEPOST "MILE 1"	M1-8	1.50	13.5
	MILEPOST "MILE 1"	M1-8	1.50	-
STA. 67+10 LT	NO MOTOR VEHICLES	R5-3	4.00	14.0
STA. 67+10 RT	YIELD	R1-2	0.97	13.5
STA. 67+50 LT	YIELD	R1-2	0.97	13.5
PROJECT TOTALS			8.94	54.5

**CULVERT AND RIPRAP SCHEDULE**

STATION	24" DIA RCCP (FOOT)	36" DIA RCCP (FOOT)	8'x4' PCBC (FOOT)	24" DIA PRCFES (EACH)	36" DIA PRCFES (EACH)	8'x4' PRC END SEC NO.1	TRENCH BACKFILL (CU YD)	STONE RR A3 (TON)
51+50		32			2		8.9	
53+12			24			2	13.5	10
55+00	25			2			3.9	10
48+90 to 51+65								440
TOTALS	25	32	24	2	2	2	26.3	460

**BROWN AND ROBERTS, INC.**  
 CONSULTING ENGINEERS & LAND SURVEYORS  
 1 WESTRIDGE ROAD HARRISBURG, IL. 62946 (618) 252-8111



**S.V.C.D.**  
 ILLINOIS TRANSPORTATION  
 ENHANCEMENT PROGRAM  
 MATERIAL SCHEDULES

Drawn By: VJW Checked By: MWR

Revisions  
 Item Date By

Scale: AS SHOWN Field Bk: 10-209

Job Number: 10-209 Date: 02/11

Sheet

**3**

of 25

17 May 2011 - 7:27am X:\2010\10209\AC\2-3 Summary of Quantities and typical details.dwg

